



Squeezer Update Review

August 25, 2009


H1 Squeezer Experiment

ANU, AEI, MIT, CIT and LHO collaboration


Highlights

- ❑ Grad. students Sheila D. (MIT), Sheon C. (ANU) and Michael S. (ANU)
- ❑ OPO development at ANU
 - 6 dB of squeezing observed
 - Traveling wave bowtie design works
- ❑ AEI loaner SHG at MIT
 - In the process of building our own (copy AEI design)
- ❑ Laser, optical table and clean room installed at MIT
- ❑ Noise model and simulation done
- ❑ Electronics design done for RF distribution
 - Shared with advanced LIGO

Block Schematics




ANU Traveling Wave OPO



Squeezing Performance

Squeezing Spectrum




Electronics

- + *Mains harmonics*
- ▲ *Cross coupling from Coherent Lock*
- *Electronic Noise?*

Lab environment

- *Acoustic Noise*



Servo Model

- ❑ Laser 0: Frequency locked to PSL using FSS
- ❑ Laser 1 (aux): Frequency locked to laser 0 using FSS
- ❑ Coherent Lock 2: Phase lock laser 1 to green light using feedback to PZT & laser 1 additive offset
- ❑ LO Lock 3: Phase lock squeeze angle to AS port light using feedback to PZT & laser 0 additive offset
- ❑ SHG Lock 4: PDH to cavity PZT
- ❑ OPO Lock 5: PDH to cavity PZT

Servo Model (2)

Servo	Description	Bandwidth	Crossover
0	Laser 0	500kHz	10kHz
1	Laser 1	500kHz	10kHz
2	Coherent field	100kHz	~2kHz
3	Local oscillator	100kHz	~2kHz
4	SHG length	~1kHz	—
5	OPO length	~1kHz	—

**Fiber Stabilization no longer needed:
Laser 0 is frequency locked to PSL and
phase locked to AS port light**

Noise Model

- ❑ **No bad surprises**
- ❑ **Acoustic couplings**
 - Direct back scattering under control
 - Require second in-vacuum Faraday
 - OPO ring topology is very helpful
- ❑ **Phase noise requirement: <50 mrad rms**
 - Remaining modulation sidebands after OMC are important
- ❑ **Noise couplings**
 - Laser frequency noise not important due to large bandwidth
 - Path length variations not important due to large bandwidth
 - Shot noise: 1 mW per detector seems enough
 - OPO length fluctuations are not getting suppressed by LO servo!

Schedule

- ❑ ANU/OPO well on track
- ❑ Noise model completed
- ❑ AEI homodyne detector will be shipped to ANU ahead of schedule
- ❑ Assembly at MIT
 - Optical layout on track
 - Parts late by ~2 months (initial funds exhausted)
- ❑ Electronics production at LHO
 - Design on track
 - Procurement late by ~2 months (person power & money & H2 unavailable)

Plan

- ❑ Need get some additional resources for
 - Electronics production at LHO
 - Setup at MIT
 - Procurement
- ❑ ANU will continue on development of OPO
 - On track for 2010 delivery
- ❑ Setup at MIT will continue with SHG & laser locking
- ❑ Electronics production can go forward
 - RF, PDs, TTFFS and length servos (common mode board)
- ❑ Additional funding is required now

Budget Request

Task	Amount
Optics	90k
Electronics	80k
Travel	40k
Total	210k

Summary

- ❑ Impressive progress on the OPO
- ❑ Setup at MIT is coming along
- ❑ No major roadblocks so far
- ❑ More funding is required now
- ❑ Some additional person-power is required at MIT and LHO for the second half of this year