

**BUILT-UP AIR HANDLING UNIT SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	SUPPLY AIR FAN #	CHILLED WATER COIL #	HEATING COIL #	HUMIDIFIER #	FILTER #	AIR FLOW		REMARKS
									SUPPLY AIR CFM	OUTSIDE AIR CFM	
W-CS-107-AH-03	LVEA BUILDING	OSB (LAB)	BUILT-UP	W-CS-107-SF-05 W-CS-107-SF-06	W-CS-107-CC-05 W-CS-107-CC-06	W-CS-107-HC-09 W-CS-107-HC-10	W-CS-107-HU-05 W-CS-107-HU-06	W-CS-107-AF-03	24,000	1,720	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-MA-203-AH-01	MID STATION A	MID STATION A	BUILT-UP	W-MA-203-SF-01 W-MA-203-SF-02	W-MA-203-CC-01 W-MA-203-CC-02	-----	W-MA-203-HU-01 W-MA-203-HU-02	W-MA-203-AF-01 W-MA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-MB-203-AH-01	MID STATION B	MID STATION B	BUILT-UP	W-MB-203-SF-01 W-MB-203-SF-02	W-MB-203-CC-01 W-MB-203-CC-02	-----	W-MB-203-HU-01 W-MB-203-HU-02	W-MB-203-AF-01 W-MB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-EA-203-AH-01	END STATION A	END STATION A	BUILT-UP	W-EA-203-SF-01 W-EA-203-SF-02	W-EA-203-CC-01 W-EA-203-CC-02	-----	W-EA-203-HU-01 W-EA-203-HU-02	W-EA-203-AF-01 W-EA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-EB-203-AH-01	END STATION B	END STATION B	BUILT-UP	W-EB-203-SF-01 W-EB-203-SF-02	W-EB-203-CC-01 W-EB-203-CC-02	-----	W-EB-203-HU-01 W-EB-203-HU-02	W-EB-203-AF-01 W-EB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL

**NOTES:**  
 1. FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES SEE SHEETS WA-H-001 AND WA-H-002.

\* SEE INDIVIDUAL EQUIPMENT SCHEDULES

**PACKAGED AIR-COOLED WATER CHILLER SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	CHILLED FLUID	DESIGN TEMP (*F DB)	AMBIENT ALTITUDE (FT)	MIN OPER TEMP (*F DB)	COMPRESSOR		MINIMUM CAPACITY (TONS)	MAX KW	REFRIGERANT	EVAPORATOR			CONDENSER		SINGLE POINT ELECT CONN	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS			
								TYPE	DRIVER				ENT TEMP (*F)	LVD TEMP (*F)	GPM	MAX PD (FT)	NO. FANS EACH UNIT					HP EACH FAN	VOLTS/ PH/Hz	TOTAL RLA
W-MA-200-CH-01	MID STATION A	MID STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-MA-200-CH-02	MID STATION A	MID STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-MB-200-CH-01	MID STATION B	MID STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-MB-200-CH-02	MID STATION B	MID STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-EA-200-CH-01	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-EA-200-CH-02	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-EB-200-CH-01	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-EB-200-CH-02	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY

**CHILLED WATER COOLING COIL SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	MAX FACE VEL (FPM)	ACFM	MAX AIR PD (IN. WG)	ROWS	MAX FP	EAT			LWT (*F)	GPM	MAX WTR PD (FT)	MANUFACTURER/ MODEL NO.	OVERBALL SIZE (IN. X IN.)	REMARKS		
										*FDB	*FDB	*FDB								
W-CS-107-CC-05	CORNER STATION	OSB	393	387	445	11,500	0.60	8	8	83.1	52.7	50.9	50	42	50	95	15	CARRIER BC	36 X 105	40% GLYCOL
W-CS-107-CC-06	CORNER STATION	OSB	393	387	445	11,500	0.60	8	8	83.1	52.7	50.9	50	42	50	95	15	CARRIER BC	36 X 105	40% GLYCOL
W-MA-203-CC-01	MID STATION A	MID STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-MA-203-CC-02	MID STATION A	MID STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-MB-203-CC-01	MID STATION B	MID STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-MB-203-CC-02	MID STATION B	MID STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-EA-203-CC-01	END STATION A	END STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-EA-203-CC-02	END STATION A	END STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-EB-203-CC-01	END STATION B	END STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL
W-EB-203-CC-02	END STATION B	END STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	CARRIER BC	2(30 X 60)	40% GLYCOL


**EXPANSION TANK SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	MIN CAP (GAL)	MAX WORKING PRESS (PSIG)	MAX OPER TEMP (*F)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
W-MA-203-TK-01	MID STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO C184	
W-MB-203-TK-01	MID STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO C184	
W-EA-203-TK-01	END STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO C184	
W-EB-203-TK-01	END STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO C184	

**AIR SEPARATOR SCHEDULE**

UNIT NO.	LOCATION	SERVICE	MIN CAP (GPM)	SIZE (IN.)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
W-MA-203-AS-01	MID STATION A	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-MB-203-AS-01	MID STATION B	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-EA-203-AS-01	END STATION A	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-EB-203-AS-01	END STATION B	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	

ISSUED FOR CONSTRUCTION  
 DRAWN: CLP 6-24-96  
 CHECKED: MS 7-3-96  
 ENGINEER: AA 7-3-96  
 PROJ: HUBU 7/1/96



LASER INTERFEROMETER  
 GRAVITATIONAL-WAVE OBSERVATORY  
 SITE NO. 1 - HANFORD, WASHINGTON

TITLE: HVAC EQUIPMENT SCHEDULES SHEET 1

SHEET NUMBER: PP150969 8094

REVISION: WA-H-003

LIGO-D960345-00-0

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.  
 FOR JUI BY 12/28/98 1170 8511806C - JAT/LUIS/MUR/CAV/286Z/IN/003/01P

A B C D E  
 5 4 3 2  
 LIGOWAF.BDR