

LASER INTERFEROMETER GRAVITATIONAL WAVE OBSERVATORY
- LIGO -
CALIFORNIA INSTITUTE OF TECHNOLOGY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

Document Type LIGO-T960024-A - CDR 10/11/96

**Vacuum Control and Monitoring
System (VCMS) Design Requirements**

R. Bork


Distribution of this draft:

This is an internal working note
of the LIGO Project.

California Institute of Technology
LIGO Project - MS 51-33
Pasadena CA 91125
Phone (818) 395-2129
Fax (818) 304-9834
E-mail: info@ligo.caltech.edu

Massachusetts Institute of Technology
LIGO Project - MS 20E-145
Cambridge, MA 02139
Phone (617) 253-4824
Fax (617) 253-7014
E-mail: info@ligo.mit.edu

WWW: <http://www.ligo.caltech.edu/>



| | |
|---|-----------|
| 1 Introduction | 5 |
| 1.1. Purpose | 5 |
| 1.2. Scope | 6 |
| 1.3. Definitions | 6 |
| 1.4. Acronyms | 6 |
| 1.5. Applicable Documents | 7 |
| 1.5.1. LIGO Documents | 7 |
| 1.5.2. Non-LIGO Documents | 7 |
| 2 General description | 8 |
| 2.1. Specification Tree | 8 |
| 2.2. Product Perspective | 10 |
| 2.3. Product Functions | 10 |
| 2.4. General Constraints | 11 |
| 2.5. Assumptions and Dependencies | 11 |
| 2.5.1. LIGO Global CDS | 11 |
| 2.5.2. Vacuum Equipment (VE) Design | 11 |
| 2.5.3. VE Vendor Provided Equipment/Documentation for Control and Monitor- ing | 11 |
| 2.5.4. System Installation | 11 |
| 3 Requirements | 12 |
| 3.1. Characteristics | 12 |
| 3.1.1. Performance Characteristics | 12 |
| 3.1.1.1 System Level | 12 |
| 3.1.1.1.1 General | 12 |
| 3.1.1.1.2 Operator Stations | 12 |
| 3.1.1.1.2.1 Remote | 12 |
| 3.1.1.1.2.2 Local | 12 |
| 3.1.1.1.3 Operator System Level Displays | 12 |
| 3.1.1.1.3.1 System Overview Panel | 12 |
| 3.1.1.1.3.2 System Trend Plots | 13 |
| 3.1.1.1.3.3 Use of color on displays | 13 |
| 3.1.1.1.3.4 Symbols | 13 |
| 3.1.1.1.3.5 Interactive icons | 13 |
| 3.1.1.1.4 VCMS Diagnostics | 13 |
| 3.1.1.1.5 VCMS Start-up | 14 |
| 3.1.1.1.6 Power Failure | 14 |
| 3.1.1.1.7 System Status Reporting | 14 |
| 3.1.1.1.7.1 Ready for LIGO Operations | 14 |
| 3.1.1.1.7.2 VCMS Status | 14 |
| 3.1.1.1.8 Alarm Management | 14 |

| | |
|--|----|
| 3.1.1.1.9 Data Archival | 14 |
| 3.1.1.1.9.1 General | 14 |
| 3.1.1.1.10 On-Line Documentation | 15 |
| 3.1.1.2 Subsystems | 15 |
| 3.1.1.2.1 Stand-alone Operation | 15 |
| 3.1.1.2.2 Location | 15 |
| 3.1.1.2.3 Control and Monitoring | 15 |
| 3.1.1.2.3.1 Hanford Site | 16 |
| 3.1.1.2.3.2 Livingston Site | 16 |
| 3.1.1.2.4 Alarms | 16 |
| 3.1.1.2.5 Data Archival | 16 |
| 3.1.1.2.6 Watchdog Timers | 16 |
| 3.1.1.3 Assemblies | 16 |
| 3.1.1.3.1 Beam Tubes | 17 |
| 3.1.1.3.1.1 Gauge Pairs | 17 |
| 3.1.1.3.1.2 10" Pumpout Ports | 17 |
| 3.1.1.3.2 Beam Manifolds | 18 |
| 3.1.1.3.2.1 10" Pumpout Ports | 18 |
| 3.1.1.3.2.2 6" Pumpout Ports | 18 |
| 3.1.1.3.2.3 75 l/s annulus ion pumps | 19 |
| 3.1.1.3.3 80 K Cryo Pump | 19 |
| 3.1.1.3.3.1 General Signal Monitoring | 19 |
| 3.1.1.3.3.2 Liquid Level Control | 19 |
| 3.1.1.3.3.3 Regeneration Control | 19 |
| 3.1.1.3.3.4 Dewar Statistics | 20 |
| 3.1.1.3.3.5 Gauge Pairs | 20 |
| 3.1.1.3.3.6 10" Pumpout Ports | 20 |
| 3.1.1.3.4 HAM Chamber | 20 |
| 3.1.1.3.5 Beam Splitter Chamber | 20 |
| 3.1.1.3.5.1 Gauge Pairs | 21 |
| 3.1.1.3.5.2 75 l/s annulus ion pumps | 21 |
| 3.1.1.3.5.3 Control Functions | 21 |
| 3.1.1.3.6 Vacuum Section Isolation Valves | 21 |
| 3.1.1.3.6.1 General Monitoring | 21 |
| 3.1.1.3.6.2 Control Functions | 21 |
| 3.1.1.3.6.3 Interlocks | 21 |
| 3.1.1.3.7 2500 l/s Ion Pumps | 23 |
| 3.1.1.3.7.1 Signal monitoring, archiving and alarms | 23 |
| 3.1.1.3.7.2 Control Functions | 23 |
| 3.1.1.3.7.3 Interlocks | 23 |
| 3.1.2. Physical Characteristics | 24 |
| 3.1.2.1 Electronic equipment housings | 24 |
| 3.1.2.2 Weight Limits | 24 |
| 3.1.3. Interface Definitions | 24 |
| 3.1.3.1 Interfaces to other LIGO detector subsystems | 24 |
| 3.1.3.1.1 Mechanical Interfaces | 24 |

| | |
|---|-----------|
| 3.1.3.1.2 Electrical Interfaces | 24 |
| 3.1.3.1.3 Optical Interfaces | 24 |
| 3.1.3.1.4 Stay Clear Zones | 24 |
| 3.1.3.2 Interfaces external to LIGO detector subsystems | 24 |
| 3.1.3.2.1 Mechanical Interfaces | 24 |
| 3.1.3.2.1.1 Facility | 24 |
| 3.1.3.2.1.2 PSI | 24 |
| 3.1.3.2.2 Electrical Interfaces | 25 |
| 3.1.3.2.2.1 Facility | 25 |
| 3.1.3.2.2.2 PSI | 25 |
| 3.1.3.2.3 Stay Clear Zones | 25 |
| 3.1.4. Reliability | 25 |
| 3.1.5. Maintainability | 25 |
| 3.1.6. Environmental Conditions | 25 |
| 3.1.6.1 Natural Environment | 25 |
| 3.1.6.1.1 Temperature and Humidity | 25 |
| 3.1.6.1.2 Atmospheric Pressure | 25 |
| 3.1.6.2 Induced Environment | 26 |
| 3.1.6.2.1 Acoustic Noise | 26 |
| 3.1.6.2.2 Electromagnetic Radiation | 26 |
| 3.1.7. Transportability | 26 |
| 3.2. Design and Construction | 26 |
| 3.2.1. Materials and Processes | 26 |
| 3.2.1.1 Finishes | 26 |
| 3.2.2. Component Naming | 26 |
| 3.2.3. Workmanship | 26 |
| 3.2.4. Interchangeability | 27 |
| 3.2.5. Safety | 27 |
| 3.2.6. Human Engineering | 27 |
| 3.3. Documentation | 27 |
| 3.3.1. Specifications | 27 |
| 3.3.2. Design Documents | 27 |
| 3.3.3. Engineering Drawings and Associated Lists | 27 |
| 3.3.4. Technical Manuals and Procedures | 27 |
| 3.3.4.1 Procedures | 27 |
| 3.3.4.2 Manuals | 28 |
| 3.3.5. Documentation Numbering | 28 |
| 3.3.6. Test Plans and Procedures | 28 |
| 3.4. Logistics | 28 |
| 3.5. Precedence | 28 |
| 3.6. Qualification | 28 |
| 4 Quality Assurance (QA) Provisions | 28 |
| 4.1. General | 28 |

| | |
|--|-----------|
| 4.1.1. Responsibility for Tests | 29 |
| 4.1.2. Special Tests | 29 |
| 4.1.3. Configuration Management | 29 |
| 4.2. Quality Conformance Inspections | 29 |
| 4.2.1. Inspections | 29 |
| 4.2.2. Analysis | 29 |
| 4.2.3. Demonstration | 29 |
| 4.2.4. Similarity | 29 |
| 4.2.5. Test | 30 |
| 5 Preparation For Delivery | 30 |
| 5.1. Preparation | 30 |
| 5.2. Packaging | 30 |
| 5.3. Marking | 30 |
| 6 Notes | 30 |

1 INTRODUCTION

1.1. Purpose

This document defines the requirements for that portion of the LIGO vacuum controls to be provided by the LIGO CDS group, hereafter referred to as the LIGO Vacuum Control and Monitoring System (VCMS). As can be seen in Figure 1: LIGO Vacuum Related Control Systems, various systems are involved in the control and monitoring of the LIGO vacuum systems. In general, these systems control and monitor different phases of the vacuum system operation.

- **Beam Tube Bakeout:** A separate system (provider TBD) will be used for initial pumpdown and bakeout of the LIGO beam tubes. This system is totally separate of the VCMS and the VCMS has no responsibilities for or connections to this system.
- **Pump Cart System:** The Vacuum Equipment (VE) vendor (Process Systems International (PSI)) will provide portable turbo and roughing pump systems for the purposes of initial pumpdown of VE to high vacuum. The VCMS shall provide for limited monitoring of these systems.
- **VE Bakeout:** PSI will provide control and monitoring as necessary to initially bakeout the VE components. This is a separate system from the VCMS.
- **Purge air control:** PSI will provide the controls necessary for applying purge air to the system. This is to be a portable system. *(Note: This is a change from the original requirements, in which this was a requirement on CDS to control. The PSI design for this system has changed, with CDS no longer providing control or monitoring of this function.)*
- **VCMS:** This is the system defined by this document. In general, the VCMS is responsible for control and monitoring of systems during “normal” high vacuum conditions.




Figure 1: LIGO Vacuum Related Control Systems

1.2. Scope

The end product, for which this document specifies the requirements, is an integrated Control and Data System (CDS) for the LIGO vacuum equipment at Hanford, WA and Livingston, LA. The primary function of the VCMS is to provide for remote operation and monitoring, from a central control room, of LIGO vacuum equipment during LIGO operations. Included in this scope is:

- Hardware and software applications specific to Vacuum Equipment (VE) control and monitoring, including digital processing equipment, Input/Output (I/O) interfaces, interactive operator interfaces, data collection, conversion and logging, signal conditioning, closed loop control, automatic sequences, interlocks and all necessary equipment housings. (NOTE: All sensors and equipment actuators are to be provided by PSI, and therefore are not in the scope of the VCMS).
- Hardware and software, as necessary, to interface the VCMS to the VE provided by the VE vendor and to the infrastructure of the LIGO CDS.

The VCMS is to be developed as an integrated subsystem of the LIGO CDS. As such, the system infrastructure and operational support components will be provided by the LIGO CDS and are not included in the scope of the VCMS. This includes such items as the data communication networks, operator consoles, compute servers, mass storage systems, software development tools and software general services.

Also not in the scope of the VCMS are control functions associated with equipment, such as roughing, turbo pumps and bake out systems, used for initial pumpdown of LIGO vacuum spaces. This function is to be provided by stand-alone control and monitoring systems associated with portable "pumpdown carts", which are to be provided by the Vacuum Equipment (VE) vendor, Process Systems International (PSI). The VCMS will however provide for some limited monitoring of these systems, as outlined in the requirements section of this document.

1.3. Definitions

Isolation Valves: Large (44" and 48" diameter) gate valves used to isolate vacuum sections.

1.4. Acronyms

- AI Analog Input
- AO Analog Output
- BSC Beam Splitter Chamber
- CDS Control and Data System
- CIM Computer Integrated Manufacturing
- DI Digital Input
- FCR Facility Control Room
- GUI Graphical User Interface
- HAM Horizontal Access Module
- IFO Interferometer
- I/O Input/Output
- LIGO Laser Interferometer Gravitational Wave Observatory
- LN2 Liquid Nitrogen

- L/S Liters/Second
- MTBF Mean Time Before Failure
- MTTR Mean Time To Repair
- P&ID Piping and Instrumentation Drawing
- PSI Process Systems International
- RH Relative Humidity
- TBD To Be Determined
- T/C Thermocouple
- VCMS Vacuum Control and Monitoring System
- VE Vacuum Equipment

1.5. Applicable Documents

1.5.1. LIGO Documents

T950054-C Global CDS Control and Monitoring Design Requirements Document

T960142-C Global CDS Control and Monitoring Preliminary Design

M950046-F LIGO Project System Safety Management Plan

L950003 LIGO Document Numbering System

T950111 LIGO Naming Conventions

E950091 Detector - Vacuum Equipment ICD

E950090 Detector - Civil Construction ICD

D960073-E WA Chamber and Rack Designations

1.5.2. Non-LIGO Documents

- Process Systems International (PSI) Piping and Instrumentation Drawings (P&ID) , dated March 20, 1996, as listed in the following table:

Table 1: PSI P&ID Listing

| <i>PSI Number</i> | <i>LIGO Number</i> | <i>Rev</i> | <i>Description</i> | <i>Sheets</i> |
|-------------------|--------------------|------------|-----------------------------|---------------|
| V049-0-001 | D960107-00-V | 0 | Vac Equip Legend | 3 |
| V049-0-002 | D960108-00-V | 0 | BSC Mid Stations | 1 |
| V049-0-003 | D960109-00-V | 0 | BSC Corner Vertex Arms | 1 |
| V049-0-004 | D960110-00-V | 0 | Horizontal Access Module | 1 |
| V049-0-005 | D960111-00-V | 0 | 112cm and 122cm Gate Valves | 1 |
| V049-0-006 | D960112-00-V | 0 | 80K Cryopump | 1 |

Table 1: PSI P&ID Listing

| <i>PSI Number</i> | <i>LIGO Number</i> | <i>Rev</i> | <i>Description</i> | <i>Sheets</i> |
|-------------------|--------------------|------------|----------------------------------|---------------|
| V049-0-010 | D960113-00-V | 0 | Washington LT End Station | 1 |
| V049-0-011 | D960131-00-V | 0 | Washington LT Mid Station | 1 |
| V049-0-012 | D960114-00-V | 0 | Washington LT Beam Manifold | 1 |
| V049-0-013 | D960115-00-V | 0 | Washington Vertex Section | 1 |
| V049-0-014 | D960116-00-V | 0 | Washington Diagonal Section | 1 |
| V049-0-015 | D960117-00-V | 0 | Washington RT Beam Manifold | 1 |
| V049-0-016 | D960118-00-V | 0 | Washington RT Mid Station | 1 |
| V049-0-017 | D960119-00-V | 0 | Washington RT End Station | 1 |
| V049-0-018 | D960120-00-V | 0 | Washington Crrr St Mechanical Rm | 1 |
| V049-0-020 | D960121-00-V | 0 | LA Left End Station | 1 |
| V049-0-021 | D960122-00-V | 0 | LA Left & Right Mid Joints | 1 |
| V049-0-022 | D960123-00-V | 0 | LA Left Beam Manifold | 1 |
| V049-0-023 | D960124-00-V | 0 | LA Vertex Section | 1 |
| V049-0-024 | D960125-00-V | 0 | LA Right Beam Manifold | 1 |
| V049-0-025 | D960126-00-V | 0 | LA Right End Station | 1 |
| V049-0-026 | D960127-00-V | 0 | LA Corner St Mechanical Rm | 1 |

- PSI transmittal V049-1-013, Approximate Total I/O Count for WA site, dated December 1, 1995
- PSI transmittal V049-1-036, Rev. 1, Instrument List, dated March 11, 1996

2 GENERAL DESCRIPTION

2.1. Specification Tree

This document is part of an overall LIGO detector requirement specification tree. This particular document is highlighted in the following figure.




Figure 2: LIGO Specification Tree

2.2. Product Perspective

The VCMS is to be a subsystem of the larger LIGO CDS. Figure 2 depicts the relationship of the VMCS to the LIGO CDS and to the VE.




Figure 3: Product Perspective

2.3. Product Functions

The primary VCMS functions are:

- Monitoring of all sensors provided by the vacuum equipment manufacturer (except those associated with the bakeout system).
- Closed loop control of specified equipment.
- Appropriate interlocking systems, such that equipment is not operated in a hazardous manner (except those on the roughing pumps, turbo pumps and bakeout system).
- Local operation (adjacent to the equipment in the vacuum equipment areas) of all controlled and monitored vacuum equipment.
- Remote operation (from a central Facility Control Room (FCR)) of all controlled and monitored vacuum equipment.
- Operator interfaces, as necessary, to support both local and remote operation.
- Operational support services, such as data archiving and retrieval and alarm management.
- Integration with the remainder of the LIGO CDS systems.

2.4. General Constraints

The design and implementation of the VCMS shall be in compliance with the LIGO CDS control and monitoring requirements, LIGO T950054-C, and the global CDS design and design standards, as defined in LIGO T950120-C, to ensure proper integration with the remainder of the LIGO CDS.

2.5. Assumptions and Dependencies

2.5.1. LIGO Global CDS

The infrastructure, such as timing, networking, and operational support, will be provided by the LIGO CDS. As such, only requirements particular to the VCMS, such as particular display and alarm management layouts, are specified here and not the overall scheme for providing these functions.

2.5.2. Vacuum Equipment (VE) Design

The vacuum equipment and its sensors and actuators are being provided by PSI under contract to LIGO. The VCMS requirements are therefore highly dependent on the PSI designs and documentation. As details of the VE designs change, this document will be updated to reflect those changes.

2.5.3. VE Vendor Provided Equipment/Documentation for Control and Monitoring

The VE vendor is to provide all VE sensor and actuator equipment.

The VE vendor is to provide all P&IDs and signal lists which include types, levels, engineering unit conversions and calibration constants.

The VE vendor is to provide closed loop control specifications.

2.5.4. System Installation

It is assumed that LIGO CDS personnel will have access to VE areas prior to VE acceptance tests such that the VCMS required for those tests may be installed and tested.

3 REQUIREMENTS

3.1. Characteristics

3.1.1. Performance Characteristics

To define performance requirements, this section has been subdivided into requirement levels:

- System Level: Requirements which must be met by the overall VCMS.
- Subsystem Level: Requirements which must be met by all VCMS defined subsystems.
- Assembly Level: Requirements which must be met by defined VCMS assemblies.

3.1.1.1 System Level

3.1.1.1.1 General

The VCMS shall meet the applicable requirements as outlined in the LIGO CDS Control and Monitoring DRD, LIGO T950054-C, and be implemented using applicable standards as established in the LIGO CDS Control and Monitoring Preliminary Design, LIGO T960142-C. These documents provide the overall LIGO CDS requirements and design standards for the CDS infrastructure, including timing and networking systems, to which the VCMS must interface, and operational support hardware and software, such as operator stations and software for operator displays, alarm management, and archival tools, which will provide the infrastructure for specific implementations required for the VCMS.

3.1.1.1.2 Operator Stations

3.1.1.1.2.1 Remote

Remote operator consoles are to be provided by the LIGO Global CDS in the Facility Control Rooms (FCR) at both LIGO sites. The VCMS operator interface displays shall be designed and implemented such that they can be run from any of the operator consoles in the FCR.

3.1.1.1.2.2 Local

Local, i.e. in the vicinity of the VCMS equipment racks in the Vacuum Equipment (VE) areas, operation of VE will be required during acceptance testing and maintenance periods. To support this, the VCMS shall provide equipment to provide the same control and monitoring features as the FCR operator consoles for the subset of equipment in a particular area.

3.1.1.1.3 Operator System Level Displays

In general, the VCMS shall provide a hierarchy of operator interface displays, from a system overview panel, down through subsystem and assembly panels. Movement through this hierarchy shall be accommodated by the use of icon selections.

3.1.1.1.3.1 System Overview Panel

The following system level displays shall be provided as a minimum:

- Navigator: This window shall depict the various defined VE subsystems. On operator

- select of a subsystem, that subsystem overview window shall be displayed.
- Vacuum Summary: A summary window shall be provided which depicts the vacuum readings and isolation valve status in all sections of the VE.
 - Pump Summary: A summary window shall be provided which depicts the present status of all vacuum pumps and isolation valves.

3.1.1.1.3.2 *System Trend Plots*

Trend plots shall be provided to depict all vacuum readings in the system.

3.1.1.1.3.3 *Use of color on displays*

The use of certain colors shall be restricted and have specific meaning when applied to VCMS operator interface displays. These are:

- Green: Shall be used to indicate that a device is in its proper state to support LIGO laser operations.
- Blue: A device is a “don’t care” condition (i.e. is not critical to high vacuum operations)
- Yellow: Warning indication that a device is transiting to/from its proper state for high vacuum operations.
- Red: A device is in an alarm condition or is a critical item which is not in its proper state to support high vacuum operations.

3.1.1.1.3.4 *Symbols*

Standard symbols, as shown on PSI drawings, for vacuum components shall be depicted for VE on operator displays. Along with the use of the previous standard colors, the present state (i.e. opened/closed, on/off, etc.) of the components shall also be indicated.

3.1.1.1.3.5 *Interactive icons*

Various subsystem and assemblies and devices shall be operable via interactive icons on appropriate operator display pages. However, the operation of these units shall require two independent icons to be selected by the operator:

1. State to go to: Open/Close, On/Off, cooldown, vent, etc.
2. Verification, in the form of a Cancel/Confirm icon, that the Open/Close, On/Off, cooldown, vent, etc. request was not in error. The VCMS default shall be “Cancel” and automatically timeout in 30 seconds if there is no operator response.

The purpose of this is to prevent the devices from changing states due to an inadvertent operator selection on a VCMS display.

3.1.1.1.4 *VCMS Diagnostics*

The VCMS shall provide self-diagnostics, in keeping with LIGO CDS standards. These diagnostics shall be performed on all hardware and software associated with the VCMS.

3.1.1.1.5 VCMS Start-up

On power up or reset of any portion of the VCMS itself, the VCMS shall not disturb the present state of the VE. The VCMS shall detect the present state of the VE and update its internal state vectors to correspond to this state.

3.1.1.1.6 Power Failure

The VCMS shall provide its own backup power in the event of loss of facility power. This power source shall have sufficient backup capacity to operate the VCMS for a minimum of 15 minutes after power loss. The VCMS shall provide an alarm indication to LIGO operators whenever this backup power is being used by the system.

3.1.1.1.7 System Status Reporting

3.1.1.1.7.1 Ready for LIGO Operations

The VCMS shall provide a "Ready for Normal Operations" signal to the LIGO CDS. This signal shall be set True when and only when:

- The VCMS is operational as indicated by no failure in its self-diagnostic tests.
- VE system is at high vacuum state as indicated by all isolation valves being open, all high vacuum pumping operational, and all vacuum readings are in the normal, high vacuum range.

3.1.1.1.7.2 VCMS Status

The VCMS shall provide a TBD state vector to the CDS, updated at a rate of TBD, indicating the overall status of the VE and VCMS.

3.1.1.1.8 Alarm Management

The VCMS shall provide an alarm tree structure, which shall be viewable with the standard LIGO CDS alarm management software. This alarm tree shall be structured in the same manner as the VCMS CIM model. The VCMS shall monitor, record and enunciate all alarm conditions associated with the VE, as defined in following sections of this document.

One branch of the alarm tree shall be the internal VCMS self-diagnostics.

3.1.1.1.9 Data Archival

3.1.1.1.9.1 General

VCMS data archiving shall be developed and compatible with the standard LIGO CDS data archiving system. Specifically, the VCMS shall archive:

- All operator actions.
- All digital (binary) VE signals on change of state.
- The status of specific VE analog signals on change beyond a deadband.

The VCMS shall also provide a method for operators to start and stop the data archival processes.

3.1.1.1.10 On-Line Documentation

All VCMS documentation shall be available on-line, i.e. displayed on request at any FCR console or local operator station.

3.1.1.2 Subsystems

The VCMS shall be divided into the following subsystems:

- Right end station
- Right mid station (Hanford site only)
- Left end station
- Left mid station (Hanford site only)
- Corner station - Left
- Corner station - Right
- Mechanical Room

Note: No vacuum equipment controls are required or are to be provided in the mid stations at the Livingston site.

3.1.1.2.1 Stand-alone Operation

Each subsystem shall be capable of full stand-alone operation (i.e. no CDS network connections, for purposes of VE acceptance tests), including the ability to provide all functions as listed in the previous system level requirements section. This includes interactive operator display screens, alarm management and data archival.

3.1.1.2.2 Location

Each subsystem shall provide and be enclosed in a LIGO standard 19" rack enclosure at the following locations, as shown in LIGO D960073-E, *WA Chamber and Rack Designations*.

- Right end station: 1X19
- Right mid station: 1X16
- Left end station: 1Y20
- Left mid station: 1Y17
- Corner station left: 1Y16
- Corner station right: 1X15
- Mechanical Room: TBD

3.1.1.2.3 Control and Monitoring

Each subsystem shall provide all hardware and software as necessary to provide specified control and monitoring for all assemblies from/to which connections are provided by PSI as shown in PSI drawings listed in the following subsections.

3.1.1.2.3.1 *Hanford Site*

- Corner Station - Right (1X15): V049-3-123, sheet 1, signals shown as cabled to CDS-15.
- Corner Station - Left (1Y16): V049-3-123, sheet 2, signals shown as cabled to CDS-16.
- Mechanical Room (TBD): V049-3-123, sheet 3 thru 5, signals shown as cabled to CDS-17.
- Right Mid Station: (1X16): V049-3-308
- Right End Station (1X19): V049-3-508
- Left Mid Station (1Y17): V049-3-208
- Left End Station (1Y20): V049-3-408

3.1.1.2.3.2 *Livingston Site*

- Corner Station - Right (1X15 : TBD, sheet 1, signals shown as cabled to CDS-15.
- Corner Station - Left (1Y16): TBD, sheet 2, signals shown as cabled to CDS-16.
- Mechanical Room (TBD): TBD, sheet 3 thru 5, signals shown as cabled to CDS-17.
- Right End Station (1X19): TBD
- Left End Station (1Y20): TBD

3.1.1.2.4 *Alarms*

The VCMS equipment associated with subsystems shall provide self-diagnostics to verify the status of the VCMS hardware and software. An alarm and/or warning, as appropriate, will be generated for any VCMS components which do not pass these self-diagnostic tests.

3.1.1.2.5 *Data Archival*

Each subsystem shall be capable of archiving data locally (to its disk drives) or to the CDS data archivers (across CDS networks).

3.1.1.2.6 *Watchdog Timers*

Failures of processors, due to hardware or fatal software errors, employed in the design of the VCMS may cause undesirable effects in the system, particularly control loops involved in cryopumps. Therefore, the VCMS shall provide watchdog timers which, if not reset within 30 seconds by the processor(s), will:

- Cause a reset, and therefore reboot, of the failed processor.
- Open cryopump control loops, as defined in sections 3.1.1.3.3.2.3 Fault Condition and 3.1.1.3.3.3.4 Loss of Power/Processor Fault Condition.

3.1.1.3 *Assemblies*

The following subsections describe the requirements on the VCMS for control of various VE assemblies. These assemblies are:

- Beam Tubes
- Beam Manifolds
- 80K LN2 cryopumps
- Horizontal Access Module (HAM) Chambers
- Beam Splitter Chambers (BSC)
- Vacuum section isolation valves

- 2500 l/s. ion pumps

3.1.1.3.1 *Beam Tubes*

Four foot diameter beam tubes interconnect the buildings at a LIGO site. Each 2km section constitutes a beam tube, therefore there are a total of four beam tubes/site. These are designated X1 and X2 along the X arm and Y1 and Y2 along the Y arm.

Each beam tube section contains two gauge pairs and two 10" pumpout ports which shall be monitored by the VCMS.

3.1.1.3.1.1 *Gauge Pairs*

Vacuum gauges are provided by PSI in pairs: one Pirani gauge and one cold cathode gauge. This allows full range vacuum readings from atmosphere down to 1×10^{-10} Torr. For each gauge pair the VCMS shall provide monitoring, archiving and alarm enunciation. In addition, the VCMS shall provide a rate of rise calculation for each gauge in Torr/min.

3.1.1.3.1.2 *10" Pumpout Ports*

Ten inch pumpout ports are provided in various locations to connect portable turbo pump carts for rough pumping of the vacuum system from atmosphere to the pumping range of ion pumps.

3.1.1.3.1.2.1 *Pumpout Port Gate Valves*

Beam tube pumpout port gate valves, unlike the other 10" pumpout ports in other areas of the vacuum system, do not have position indicators. Therefore, there are no requirements on the VCMS to monitor these valves along the beam tube.

3.1.1.3.1.2.2 *Portable Turbo Pump Carts*

The VCMS shall provide for monitoring of turbo pump cart signals as shown in LIGO-D961253-00-V at each of the 10" pumpout ports located nearest the LIGO corner stations and end stations. Hanford site mid station monitoring is to be provided at the cryopump pumpout ports. No monitoring is required at the Livingston site mid station. In addition, the VCMS shall provide a pump operating hours log for vacuum pumps associated with each turbo pump cart.

3.1.1.3.1.2.2.1 *VCMS Connection Point*

The VCMS shall provide a mating plug in the vicinity of each 10" pumpout port defined above for interfacing the turbo pump cart signals to the VCMS.

3.1.1.3.1.2.2.2 *Umbilical Cable*

The VCMS shall provide an umbilical cable which mates with the connector specified in LIGO D961253-00-V, Turbo Pump Cart Electrical Schematic for each turbo pump cart. This cable shall have sufficient length to reach the nearest VCMS provided pump monitoring mating plug.

3.1.1.3.2 *Beam Manifolds*

Beam manifolds are defined, for purposes of this document, as the vacuum tubing interconnecting VE assemblies within the various LIGO buildings. Subassemblies and components associated with beam manifolds are:

- 10" Pumpout Ports
- 6" Pumpout Ports
- 75 l/s annulus ion pumps

3.1.1.3.2.1 *10" Pumpout Ports*

These pumpout ports provide the same function as described in 3.1.1.3.1.2 10" Pumpout Ports.

3.1.1.3.2.1.1 *Pumpout Port Gate Valve*

The VCMS shall provide monitoring of the position of each pumpout port gate valve supplied with an open and closed limit switch.

3.1.1.3.2.1.2 *Turbo Pump Cart*

The VCMS shall provide monitoring of turbo pump carts when attached to these port locations. Interfaces shall be in accordance with sections 3.1.1.3.1.2.2.1 VCMS Connection Point and 3.1.1.3.1.2.2.2 Umbilical Cable.

3.1.1.3.2.2 *6" Pumpout Ports*

Six inch pumpout ports are provided in the LIGO corner stations for connection of portable roughing pump carts.

3.1.1.3.2.2.1 *Pumpout Port Gate Valve*

The VCMS shall provide monitoring of the position of each pumpout port gate valve supplied with an open and closed limit switch.

3.1.1.3.2.2.2 *Roughing Pump Carts*

The VCMS shall provide for monitoring of roughing pump cart signals as shown in LIGO D960795-02-V, *Roughing Pump Cart Electrical Schematic* at each of the 6" pumpout ports. In addition, the VCMS shall provide a pump operating hours log for vacuum pumps associated with each roughing pump cart.

3.1.1.3.2.2.2.1 *VCMS Connection Point*

The VCMS shall provide a mating plug in the vicinity of each 6" pumpout port defined above for interfacing the turbo pump cart signals to the VCMS.

3.1.1.3.2.2.2.2 *Umbilical Cable*

The VCMS shall provide an umbilical cable which mates with the connector specified in LIGO LIGO D960795-02-V, *Roughing Pump Cart Electrical Schematic* for each roughing pump cart. This cable shall have sufficient length to reach the nearest VCMS provided pump monitoring mating plug.

3.1.1.3.2.3 *75 l/s annulus ion pumps*

Two 75 l/s ion pumps are provided along manifolds in the LVEA. The VCMS shall provide monitoring of the pump current.

3.1.1.3.3 *80 K Cryo Pump*

80K cryopumps will exist in the mid and end stations, and at the corner station in the right and left beam manifold areas. In total, there are 8 cryopumps at the Hanford site and 4 at the Livingston site (no mid stations). The signals associated with an 80K cryopump are as shown in PSI drawing V049-0-006.

The subassemblies and components which comprise each cryopump are:

- Pump Housing
- Gauge Pair
- Discharge Line
- Regeneration Line
- LN2 Dewar
- 10" Pumpout Port

3.1.1.3.3.1 *General Signal Monitoring*

The VCMS shall provide for the monitoring of cryopumps in accordance with LIGO D960112-00-V.

3.1.1.3.3.2 *Liquid Level Control*

3.1.1.3.3.2.1 *Normal Operation*

The VCMS shall provide LN2 level control within the cryopump to specifications and in accordance with procedures provided by PSI in *Operating Procedures 80K Pump for LIGO Vacuum Equipment*, LIGO-E960127-00-V.

3.1.1.3.3.2.2 *Interlocks*

The flow of liquid nitrogen from the LN2 Dewar to the cryopumps shall not be permitted when the pressure in the cryopump section is > TBD and all other conditions necessary for nitrogen fill are met as defined in *Operating Procedures 80K Pump for LIGO Vacuum Equipment*, LIGO-E960127-00-V.

3.1.1.3.3.2.3 *Fault Condition*

On loss of power to the VCMS, or a processor failure as detected by the VCMS watchdog timer, the pump LN2 level control valve shall automatically be set to the CLOSED state.

3.1.1.3.3.3 *Regeneration Control*

3.1.1.3.3.3.1 *Normal Operation*

Cryopumps are regenerated at periodic intervals by passing gaseous nitrogen through the pumps. This nitrogen is to be provided by vaporizing liquid nitrogen from the dewar and heating the gas. As part of this procedure, the VCMS shall control the heating and temperature of the nitrogen gas

in accordance with specifications and procedures provided by PSI in *Operating Procedures 80K Pump for LIGO Vacuum Equipment*, LIGO-E960127-00-V.

3.1.1.3.3.3.2 *Interlocks*

The regeneration heater shall be prevented from being turned on unless the conditions outlined in *Operating Procedures 80K Pump for LIGO Vacuum Equipment*, LIGO-E960127-00-V for regeneration are met.

3.1.1.3.3.3.3 *Regeneration Overtemperature*

The VCMS shall automatically turn off the regeneration line heater if the temperature in the line exceeds 200C.

3.1.1.3.3.3.4 *Loss of Power/Processor Fault Condition*

On loss of power to the VCMS, or a processor failure as detected by the VCMS watchdog timer, the regeneration heater shall automatically be set to an OFF state.

3.1.1.3.3.4 *Dewar Statistics*

The VCMS shall provide automatic calculations for the following parameters for operator information:

- Dewar LN2 consumption rate
- Estimated time to Dewar empty
- Dewar integrated absorption rate

3.1.1.3.3.5 *Gauge Pairs*

The VCMS shall provide for monitoring of gauge pair signals as described previously in section 3.1.1.3.1.1 Gauge Pairs.

3.1.1.3.3.6 *10" Pumpout Ports*

The VCMS shall provide monitoring of valve position and turbo pump cart signals as previously described in section 3.1.1.3.2.1 10" Pumpout Ports.

3.1.1.3.4 *HAM Chamber*

There are to be a total of 12 HAM chambers at the Hanford site and 6 at the Livingston site. All HAM chambers are located within the vertex and diagonal sections at the corner stations. The sole requirement on the VCMS for HAM chambers is to monitor the associated 75 l/s ion pumps currents.

3.1.1.3.5 *Beam Splitter Chamber*

There are to be a total of 10 BSC at the Hanford site and 5 at the Livingston site. The devices to be monitored by the VCMS for each BSC are:

- Gauge Pair
- 75 l/s ion pump

3.1.1.3.5.1 Gauge Pairs

The VCMS shall provide for monitoring of gauge pair signals as described previously in section 3.1.1.3.1.1 Gauge Pairs.

3.1.1.3.5.2 75 l/s annulus ion pumps

The VCMS shall provide monitoring of the pump current.

3.1.1.3.5.3 Control Functions

None. (Note: This is a change from the original DRD, as the purge air control is now accomplished by PSI provided portable units and is no longer to be controlled by the VCMS.)

3.1.1.3.6 Vacuum Section Isolation Valves

There will be a total of 20 vacuum section isolation valves at the Hanford site and 12 at the Livingston site. These valves are of two types and sizes:

- 44 inch pneumatic (4 at each site)
- 44 inch and 48 inch electric (16 Hanford, 8 Livingston)

From the VCMS point of view, the operation and monitoring of the various valve types is identical.

The isolation valve assembly consists of two devices:

- Valve
- 25 l/s annulus ion pump

Note: LGV7 and LGV8 at Livingston do not have associated ion pumps.

3.1.1.3.6.1 General Monitoring

The VCMS shall provide monitoring of valve position and 25 l/s ion pump currents.

3.1.1.3.6.2 Control Functions

The VCMS shall provide the capability to remotely (from the FCR) or locally (within the area of a VCMS subsystem) operate isolation valves between open and closed states.

3.1.1.3.6.3 Interlocks

The opening of these large isolation valves can have serious consequences on machine and human safety if allowed to be opened when there exists a large differential pressure between the two vacuum sections which they isolate. Therefore, the VCMS shall provide for interlocking of these valves, as described in the following subsections.

3.1.1.3.6.3.1 Manual Operation

Each of the large isolation valves is delivered by the manufacturer with a local mechanism for opening and closing a valve. If a valve is to be operated locally (typically for maintenance or test), a LIGO procedure TBD shall be followed to ensure safe operation. The VCMS has no requirements in providing interlocks in this mode of operation. However, the VCMS shall provide a positive lockout function such that the valve cannot be moved by the VCMS during the performance of this procedure.

3.1.1.3.6.3.2 Normal Operation

The VCMS shall provide interlocks to prevent the inadvertent opening of large isolation valves. The VCMS shall not permit an isolation valve to be opened unless all of the following conditions are met:

- The nearest up and down stream Parani gauges both provide a reading of $< 1 \times 10^{-3}$ Torr
- The nearest up and down stream cold cathode gauges both provide a reading of $< 1 \times 10^{-4}$ Torr
- The associated annulus ion pump current reading is in the normal range.
- The 2500 l/s ion pumps within the isolated section are on and reading in the normal range.
Note: As all isolatable sections do not contain these ion pumps, this applies only to those sections which do.
- All pumpout ports within the isolated section are closed. (*Note: Pumpout port valve position indications are not provided with valves on beam tubes, therefore this requirement does not pertain to those units.*)
- There exists no valve fault as indicated by the Valve Fault signal from each valve.

3.1.1.3.6.3.3 Bypassing Interlocks

During acceptance testing and various other maintenance periods, the network which is to interconnect the various VCMS subsystems will not be in place and/or operational. This has an impact on the interlock requirements for the 2500 l/s ion pumps and two pumpout port valves in the corner station, as all of their signals are to be wired by PSI to the VCMS subsystem in the mechanical room. Therefore, the VCMS shall provide a method to bypass the interlocks for these units, along with an approved procedure for implementation of the bypass. ***No other interlock bypass capabilities shall be built into the VCMS.***

3.1.1.3.6.3.4 Vacuum Fault

The VCMS shall automatically monitor the rate of rise and absolute pressure on all isolatable vacuum sections. If any of the rate of rise calculations or pressure readings are above a settable limit, a warning is to be issued through the VCMS alarm management system. If this condition continues beyond a set time limit after the warning, the VCMS shall automatically close all isolation valves. To support this feature, the VCMS shall provide:

- An adjustable rate of rise and pressure fault limit
- A time setting, indicating the time to wait between the warning condition and the automatic shutting of the isolation valve.
- An on/off mechanism, which would allow operators to turn on/off the automatic valve closing feature.

3.1.1.3.7 2500 l/s Ion Pumps

3.1.1.3.7.1 Signal monitoring, archiving and alarms

The VCMS shall provide monitoring, archival and alarm enunciation for each 2500 l/s ion pump.

3.1.1.3.7.2 *Control Functions*

The VCMS shall provide the capability to remotely (from the FCR) or locally (within the area of a VCMS subsystem) operate 2500 l/s ion pumps between on and off states.

3.1.1.3.7.3 *Interlocks*

For all 2500 l/s ion pumps, the VCMS shall provide an automatic function which turns off an ion pump if its current reading is not in its normal operating range. This function will become active 30 seconds after an ion pump has been turned on and deactivated when a pump is turned off.

3.1.2. Physical Characteristics

3.1.2.1 Electronic equipment housings

To the extent possible and reasonable, all VCMS electronic equipment shall be housed in standard 19" racks.

3.1.2.2 Weight Limits

VCMS equipment to be housed within the OSB shall not exceed weight limits imposed by the building raised floor loading capacities.

3.1.3. Interface Definitions

3.1.3.1 Interfaces to other LIGO detector subsystems

3.1.3.1.1 Mechanical Interfaces

The VCMS shall provide a VCMS standard hardware connection to the LIGO CDS communication networks.

3.1.3.1.2 Electrical Interfaces

The VCMS shall be electrically and software compatible with the LIGO CDS communication networks such that data can be transferred to/from the CDS infrastructure and the VCMS.

3.1.3.1.3 Optical Interfaces

None.

3.1.3.1.4 Stay Clear Zones

None.

3.1.3.2 Interfaces external to LIGO detector subsystems

The VCMS will have interfaces to the facilities and the VE provided by PSI.

3.1.3.2.1 Mechanical Interfaces

3.1.3.2.1.1 Facility

All VCMS equipment shall be housed in rack enclosures, mounted to the LIGO facilities floor at those points designated in the Detector - Civil Construction Interface Control Document.

3.1.3.2.1.2 PSI

The VCMS shall provide a standard 19" rack enclosure and terminal strips for the termination of PSI provided signal cables. This shall be the principle interface point between VE supplied by PSI and the VCMS provided by the LIGO CDS group.

The VCMS shall provide mounting space (4U, 7") within the VCMS racks for the mounting of PSI provided 24VDC power supplies.

For the turbomolecular and roughing pump carts, the VCMS shall interface at the PSI provided terminal blocks on these units.

3.1.3.2.2 Electrical Interfaces

3.1.3.2.2.1 Facility

Facility power shall be provided at a circuit breaker panel within each of the building areas where VCMS is to be installed. Facilities shall provide 20A, 110VAC breakers at each panel, with a conduit and/or raceway from the panel to each VCMS rack enclosure. VCMS shall provide the necessary cable to connect the breaker panels to the VCMS racks and further distribute AC power.

3.1.3.2.2.2 PSI

The electrical connection between PSI provided equipment and the VCMS shall be at the terminal strips defined in section 3.2.3.2.1.2 above.

3.1.3.2.3 Stay Clear Zones

As per the Detector - Civil Construction and Detector - Vacuum Equipment Interface Control Documents.

3.1.4. Reliability

The Mean Time Before Failure (MTBF) for the VCMS shall be greater than 480 hours.

3.1.5. Maintainability

The Mean Time To Repair (MTTR) for any VCMS component shall be less than 1 hour.

3.1.6. Environmental Conditions

The VCMS shall meet all performance requirements when exposed to all specified natural and induced environments.

3.1.6.1 Natural Environment

3.1.6.1.1 Temperature and Humidity

All VCMS equipment shall meet the following temperature and humidity requirements.

Table 2: Environmental Performance Characteristics

| <i>Operating</i> | <i>Non-operating (storage)</i> | <i>Transport</i> |
|------------------------|--------------------------------|--------------------------|
| +0 C to +50 C, 0-90%RH | -40 C to +70 C, 0-90% RH | -40 C to +70 C, 0-90% RH |

3.1.6.1.2 Atmospheric Pressure

The VCMS equipment design must accommodate atmospheric pressure change from a maximum of 15.2 psia to a minimum of 14.2 psia.

3.1.6.2 Induced Environment

3.1.6.2.1 Acoustic Noise

CDS equipment shall be designed to produce the lowest levels of acoustic noise as possible and practical. In any event, CDS equipment shall not produce acoustic noise levels greater than specified in *Derivation of CDS Rack Acoustic Noise Specifications*, LIGO-T960083-A-E.

3.1.6.2.2 Electromagnetic Radiation

The VCMS shall not degrade due to electromagnetic emissions as specified by IEEE C95.1-1991. The VCMS shall comply with the LIGO EMC Plan.

3.1.7. Transportability

All items shall be transportable by commercial carrier without degradation in performance. As necessary, provisions shall be made for measuring and controlling environmental conditions (temperature and accelerations) during transport and handling. Special shipping containers, shipping and handling mechanical restraints, and shock isolation shall be utilized to prevent damage. All containers shall be movable for forklift. All items over 100 lbs. which must be moved into place within LIGO buildings shall have appropriate lifting eyes and mechanical strength to be lifted by cranes.

3.2. Design and Construction

3.2.1. Materials and Processes

3.2.1.1 Finishes

- Ambient Environment: Surface-to-surface contact between dissimilar metals shall be controlled in accordance with the best available practices for corrosion prevention and control.
- External surfaces: External surfaces requiring protection shall be painted or otherwise protected in a manner to be approved.

3.2.2. Component Naming

All tagging and naming of VCMS equipment shall be in accordance with LIGO Naming Conventions LIGO-E950111-01-E.

3.2.3. Workmanship

All details of workmanship shall be of the highest grade appropriate to the methods and level of fabrication and consistent with the requirements specified herein. There shall be no evidence of poor workmanship that would make the components unsuitable for the purpose intended. All electronic circuits, modules and wiring shall be consistent with good engineering practice and fabricated to best commercial standards.

3.2.4. Interchangeability

The VCMS shall be designed to maximize interchangeability and replaceability of mating components. Using the Line Replaceable Unit (LRU) concept, the designs shall be such that mating assemblies may be exchanged without selection for fit or performance and without modification to the section, the unit being replaced or adjacent equipment. Mature, performance proven, standard, commercially available equipment shall not be modified unless it impacts safety.

3.2.5. Safety

This item shall meet all applicable NSF and other Federal safety regulations, plus those applicable State, Local and LIGO safety requirements. A hazard/risk analysis shall be conducted in accordance with guidelines set forth in the LIGO Project System Safety Management Plan LIGO-M950046-F, section 3.3.2.

3.2.6. Human Engineering

The VCMS shall be designed and laid out in a manner consistent with good human engineering practices. Particular attention shall be paid to layouts of operator consoles/stations, work space and environmental conditions.

3.3. Documentation

3.3.1. Specifications

The following specifications shall be provided as part of the design process:

- Software Requirements Specification (SRS) for all software to be developed as part of the system.
- Interface Control Document (ICD)

3.3.2. Design Documents

The following design documents shall be provided:

- System overall design.
- System software design.

3.3.3. Engineering Drawings and Associated Lists

Engineering drawings, schematics, wire lists and cable routing lists shall be produced for the VCMS. To the greatest extent possible and practical, electronic copies shall be maintained and available on-line. All drawings shall be formatted according to LIGO standards.

3.3.4. Technical Manuals and Procedures

3.3.4.1 Procedures

Procedures shall be provided for, at minimum,

- Initial installation and setup of equipment
- Normal operation of equipment
- Normal and/or preventative maintenance
- Troubleshooting guide for any anticipated potential malfunctions
- Bypassing the isolation valve interlocks.

3.3.4.2 Manuals

The following manuals shall be provided:

- All manuals provided by commercial vendors for VCMS components.
- Manuals for all VCMS custom designed electronics and software.
- VCMS Operating Manual.

3.3.5. Documentation Numbering

All documents shall be numbered and identified in accordance with the LIGO documentation control numbering system LIGO document TBD

3.3.6. Test Plans and Procedures

All test plans and procedures shall be developed in accordance with the LIGO Test Plan Guidelines, LIGO document TBD.

3.4. Logistics

The design shall include a list of all recommended spare parts and special test equipment required.

3.5. Precedence

In the event of conflicts between this requirement document and other LIGO documents, the order of precedence shall be in accordance with the LIGO Requirement Specification Tree.

3.6. Qualification

The VCMS design shall be qualified through a series of reviews as prescribed in the LIGO Detector Implementation Plan.

Qualification of various VCMS components and subsystems shall be in accordance with Section 4 of this document.

4 QUALITY ASSURANCE (QA) PROVISIONS

4.1. General

This system shall be tested in accordance with applicable LIGO QA standards.

4.1.1. Responsibility for Tests

The LIGO CDS group shall be responsible for performing and documenting all tests associated with the VCMS.

4.1.2. Special Tests

Due to their critical nature, the isolation valve interlocks shall undergo extensive testing to ensure proper operation.

4.1.3. Configuration Management

Configuration control of specifications and designs shall be in accordance with the LIGO Detector Implementation Plan.

4.2. Quality Conformance Inspections

Design and performance requirements identified in this specification and referenced specifications shall be verified by inspection, analysis, demonstration, similarity, test or a combination thereof. Verification method selection shall be specified by individual specifications, and documented by appropriate test and evaluation plans and procedures. Verification of compliance to the requirements of this and subsequent specifications may be accomplished by the following methods or combination of methods:

4.2.1. Inspections

Inspection shall be used to determine conformity with requirements that are neither functional nor qualitative; for example, identification marks.

4.2.2. Analysis

Analysis may be used for determination of qualitative and quantitative properties and performance of an item by study, calculation and modeling.

4.2.3. Demonstration

Demonstration may be used for determination of qualitative properties and performance of an item and is accomplished by observation. Verification of an item by this method would be accomplished by using the item for the designated design purpose and would require no special test for final proof of performance.

4.2.4. Similarity

Similarity analysis may be used in lieu of tests when a determination can be made that an item is similar or identical in design to another item that has been previously certified to equivalent or more stringent criteria. Qualification by similarity is subject to Detector management approval.

4.2.5. Test

Test may be used for the determination of quantitative properties and performance of an item by technical means, such as, the use of external resources, such as voltmeters, recorders, and any test equipment necessary for measuring performance. Test equipment used shall be calibrated to the manufacturer's specifications and shall have a calibration sticker showing the current calibration status.

5 PREPARATION FOR DELIVERY

Packaging and marking of equipment for delivery shall be in accordance with the Packaging and Marking procedures specified herein.

5.1. Preparation

Equipment shall be appropriately prepared. For example, vacuum components shall be prepared to prevent contamination.

5.2. Packaging

Procedures for packaging shall ensure cleaning, drying, and preservation methods adequate to prevent deterioration, appropriate protective wrapping, adequate package cushioning, and proper containers. Proper protection shall be provided for shipping loads and environmental stress during transportation, hauling and storage.

5.3. Marking

Appropriate identification of the product, both on packages and shipping containers; all markings necessary for delivery and for storage, if applicable; all markings required by regulations, statutes, and common carriers; and all markings necessary for safety and safe delivery shall be provided.

6 NOTES

BATCH
START

May 1996

STAPLE
OR
DIVIDER

LASER INTERFEROMETER GRAVITATIONAL WAVE OBSERVATORY
- LIGO -

CALIFORNIA INSTITUTE OF TECHNOLOGY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

| |
|--|
| Document Type LIGO-T960024-A - CDR 5/8/96 |
| Vacuum Control and Monitoring System (VCMS) Design Requirements |
| R. Bork |

Distribution of this draft:

This is an internal working note
of the LIGO Project.

California Institute of Technology
LIGO Project - MS 51-33
Pasadena CA 91125
Phone (818) 395-2129
Fax (818) 304-9834
E-mail: info@ligo.caltech.edu

Massachusetts Institute of Technology
LIGO Project - MS 20B-145
Cambridge, MA 01239
Phone (617) 253-4824
Fax (617) 253-7014
E-mail: info@ligo.mit.edu

WWW: <http://www.ligo.caltech.edu/>

| | |
|---|-----------|
| 1 Introduction | 7 |
| 1.1. Purpose | 7 |
| 1.2. Scope | 7 |
| 1.3. Definitions | 7 |
| 1.4. Acronyms | 7 |
| 1.5. Applicable Documents | 8 |
| 1.5.1. LIGO Documents | 8 |
| 1.5.2. Non-LIGO Documents | 8 |
| 2 General description | 9 |
| 2.1. Specification Tree | 9 |
| 2.2. Product Perspective | 11 |
| 2.3. Product Functions | 11 |
| 2.4. General Constraints | 12 |
| 2.5. Assumptions and Dependencies | 12 |
| 2.5.1. LIGO Global CDS | 12 |
| 2.5.2. Vacuum Equipment (VE) Design | 12 |
| 2.5.3. VE Vendor Provided Equipment/Documentation for Control and Monitor- ing | 12 |
| 2.5.4. System Installation | 12 |
| 3 Requirements | 12 |
| 3.1. Introduction | 12 |
| 3.2. Characteristics | 14 |
| 3.2.1. Performance Characteristics | 14 |
| 3.2.1.1 System Level | 14 |
| 3.2.1.1.1 General | 14 |
| 3.2.1.1.2 Operator Stations | 14 |
| 3.2.1.1.2.1 Remote | 14 |
| 3.2.1.1.2.2 Local | 14 |
| 3.2.1.1.3 Operator System Level Displays | 14 |
| 3.2.1.1.3.1 System Overview Panel | 14 |
| 3.2.1.1.3.2 System Trend Plots | 15 |
| 3.2.1.1.3.3 Use of color on displays | 15 |
| 3.2.1.1.3.4 Symbols | 15 |
| 3.2.1.1.4 VCMS Diagnostics | 15 |
| 3.2.1.1.5 VCMS Start-up | 15 |
| 3.2.1.1.6 Interlocks | 15 |
| 3.2.1.1.6.1 Overview | 15 |
| 3.2.1.1.6.2 Isolation Valve Open Permissives (Normal Oper- ations) | 16 |
| 3.2.1.1.6.3 Maintenance/Test Mode | 16 |

| | | |
|-------------|---|----|
| 3.2.1.3.3 | Beam Splitter Chamber | 25 |
| 3.2.1.3.3.1 | Control/Monitoring Signals | 26 |
| 3.2.1.3.3.2 | Operator Displays | 26 |
| 3.2.1.3.3.3 | Interlocks | 27 |
| 3.2.1.3.3.4 | Closed Loop Control | 27 |
| 3.2.1.3.3.5 | Automatic Sequences | 27 |
| 3.2.1.3.3.6 | Alarms | 27 |
| 3.2.1.3.3.7 | Data Archival | 27 |
| 3.2.1.3.4 | Isolation Valves | 28 |
| 3.2.1.3.4.1 | Control/Monitor Signals | 28 |
| 3.2.1.3.4.2 | Interlocks | 28 |
| 3.2.1.3.4.3 | Closed Loop Control | 29 |
| 3.2.1.3.4.4 | Automatic Sequences | 29 |
| 3.2.1.3.4.5 | Alarms | 29 |
| 3.2.1.3.4.6 | Data Archival | 29 |
| 3.2.1.3.5 | Beam Tube/Manifold Assembly | 30 |
| 3.2.1.3.5.1 | Control and Monitor Signals | 30 |
| 3.2.1.3.5.2 | Interlocks | 31 |
| 3.2.1.3.5.3 | Closed Loop Control | 31 |
| 3.2.1.3.5.4 | Automatic Sequences | 31 |
| 3.2.1.3.5.5 | Alarms | 31 |
| 3.2.1.3.6 | Pumpdown Carts | 32 |
| 3.2.1.3.6.1 | Signal Monitoring | 32 |
| 3.2.1.3.6.2 | Data Archival | 34 |
| 3.2.2. | Physical Characteristics | 34 |
| 3.2.2.1 | Electronic equipment housings | 34 |
| 3.2.2.2 | Weight Limits | 34 |
| 3.2.3. | Interface Definitions | 34 |
| 3.2.3.1 | Interfaces to other LIGO detector subsystems | 34 |
| 3.2.3.1.1 | Mechanical Interfaces | 34 |
| 3.2.3.1.2 | Electrical Interfaces | 35 |
| 3.2.3.1.3 | Optical Interfaces | 35 |
| 3.2.3.1.4 | Stay Clear Zones | 35 |
| 3.2.3.2 | Interfaces external to LIGO detector subsystems | 35 |
| 3.2.3.2.1 | Mechanical Interfaces | 35 |
| 3.2.3.2.1.1 | Facility | 35 |
| 3.2.3.2.1.2 | PSI | 35 |
| 3.2.3.2.2 | Electrical Interfaces | 35 |
| 3.2.3.2.2.1 | Facility | 35 |
| 3.2.3.2.2.2 | PSI | 35 |
| 3.2.3.2.3 | Stay Clear Zones | 35 |
| 3.2.4. | Reliability | 36 |
| 3.2.5. | Maintainability | 36 |
| 3.2.6. | Environmental Conditions | 36 |
| 3.2.6.1 | Natural Environment | 36 |
| 3.2.6.1.1 | Temperature and Humidity | 36 |

| | |
|--|-----------|
| 3.2.6.1.2 Atmospheric Pressure | 36 |
| 3.2.6.2 Induced Environment | 36 |
| 3.2.6.2.1 Vibrations | 36 |
| 3.2.6.2.2 Acoustic Noise | 36 |
| 3.2.6.2.3 Electromagnetic Radiation | 36 |
| 3.2.7. Transportability | 36 |
| 3.3. Design and Construction | 37 |
| 3.3.1. Materials and Processes | 37 |
| 3.3.1.1 Finishes | 37 |
| 3.3.2. Component Naming | 37 |
| 3.3.3. Workmanship | 37 |
| 3.3.4. Interchangeability | 37 |
| 3.3.5. Safety | 37 |
| 3.3.6. Human Engineering | 38 |
| 3.4. Documentation | 38 |
| 3.4.1. Specifications | 38 |
| 3.4.2. Design Documents | 38 |
| 3.4.3. Engineering Drawings and Associated Lists | 38 |
| 3.4.4. Technical Manuals and Procedures | 38 |
| 3.4.4.1 Procedures | 38 |
| 3.4.4.2 Manuals | 38 |
| 3.4.5. Documentation Numbering | 39 |
| 3.4.6. Test Plans and Procedures | 39 |
| 3.5. Logistics | 39 |
| 3.6. Precedence | 39 |
| 3.7. Qualification | 39 |
| 4 Quality Assurance (QA) Provisions | 39 |
| 4.1. General | 39 |
| 4.1.1. Responsibility for Tests | 39 |
| 4.1.2. Special Tests | 39 |
| 4.1.3. Configuration Management | 40 |
| 4.2. Quality Conformance Inspections | 40 |
| 4.2.1. Inspections | 40 |
| 4.2.2. Analysis | 40 |
| 4.2.3. Demonstration | 40 |
| 4.2.4. Similarity | 40 |
| 4.2.5. Test | 40 |
| 5 Preparation For Delivery | 41 |
| 5.1. Preparation | 41 |
| 5.2. Packaging | 41 |

5.3. Marking41

6 Notes41

Appendix 1 VCMS QA Matrix 42

Table 1: List of Revisions

| <i>Rev. No.</i> | <i>Date</i> | <i>Author</i> | <i>Description</i> |
|-----------------|-------------|---------------|--|
| 00 | 3/19/96 | R. Bork | Initial Draft Release |
| 01 | 4/15/96 | R. Bork | Incorporates initial comments |
| A | 5/8/96 | R. Bork | Incorporates comments from DRR held 5/1/96 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

1 INTRODUCTION

1.1. Purpose

This document defines the requirements for the LIGO Vacuum Control and Monitoring System (VCMS).

1.2. Scope

The end product, for which this document specifies the requirements, is an integrated Control and Data System (CDS) for the LIGO vacuum equipment at Hanford, WA and Livingston, LA. The primary function of the VCMS is to provide for remote operation and monitoring of LIGO vacuum equipment during LIGO operations. Included in this scope is:

- Hardware and software applications specific to Vacuum Equipment (VE) control and monitoring, including digital processing equipment, Input/Output (I/O) interfaces, interactive operator interfaces, data collection, conversion and logging, signal conditioning, closed loop control, automatic sequences, interlocks and all necessary equipment housings.
- Hardware and software, as necessary, to interface the VCMS to the VE provided by the VE vendor and to the infrastructure of the LIGO CDS.

The VCMS is to be developed as an integrated subsystem of the LIGO CDS. As such, the system infrastructure and operational support components will be provided by the LIGO CDS and are not included in the scope of the VCMS. This includes such items as the data communication networks, operator consoles, compute servers, mass storage systems, software development tools and software general services.

Also not in the scope of the VCMS are control functions associated with equipment, such as roughing, turbo pumps and bake out systems, used for initial pumpdown of LIGO vacuum spaces. This function is to be provided by stand-alone control and monitoring systems associated with portable "pumpdown carts", which are to be provided by the Vacuum Equipment (VE) vendor, Process Systems International (PSI).

1.3. Definitions

Isolation Valves: Large (44" and 48" diameter) gate valves used to isolate vacuum sections.

1.4. Acronyms

- AI Analog Input
- AO Analog Output
- BSC Beam Splitter Chamber
- CDS Control and Data System
- CIM Computer Integrated Manufacturing
- DI Digital Input
- FCR Facility Control Room

- GUI Graphical User Interface
- HAM Horizontal Access Module
- IFO Interferometer
- I/O Input/Output
- LIGO Laser Interferometer Gravitational Wave Observatory
- LN2 Liquid Nitrogen
- L/S Liters/Second
- MTBF Mean Time Before Failure
- MTTR Mean Time To Repair
- P&ID Piping and Instrumentation Drawing
- PSI Process Systems International
- RH Relative Humidity
- TBD To Be Determined
- T/C Thermocouple
- VCMS Vacuum Control and Monitoring System
- VE Vacuum Equipment

1.5. Applicable Documents

1.5.1. LIGO Documents

T950054-C Global CDS Control and Monitoring Design Requirements Document

T950120-C Global CDS Control and Monitoring Conceptual Design

M950046-F LIGO Project System Safety Management Plan

L950003 LIGO Document Numbering System

T950111 LIGO Naming Conventions

E950091 Detector - Vacuum Equipment ICD

E950090 Detector - Civil Construction ICD

1.5.2. Non-LIGO Documents

- Process Systems International (PSI) Piping and Instrumentation Drawings (P&ID) , dated March 20, 1996, as listed in the following table:

Table 2: PSI P&ID Listing

| <i>PSI Number</i> | <i>LIGO Number</i> | <i>Rev</i> | <i>Description</i> | <i>Sheets</i> |
|-------------------|--------------------|------------|------------------------|---------------|
| V049-0-001 | D960107-00-V | 0 | Vac Equip Legend | 3 |
| V049-0-002 | D960108-00-V | 0 | BSC Mid Stations | 1 |
| V049-0-003 | D960109-00-V | 0 | BSC Corner Vertex Arms | 1 |

Table 2: PSI P&ID Listing

| <i>PSI Number</i> | <i>LIGO Number</i> | <i>Rev</i> | <i>Description</i> | <i>Sheets</i> |
|-------------------|--------------------|------------|----------------------------------|---------------|
| V049-0-004 | D960110-00-V | 0 | Horizontal Access Module | 1 |
| V049-0-005 | D960111-00-V | 0 | 112cm and 122cm Gate Valves | 1 |
| V049-0-006 | D960112-00-V | 0 | 80K Cryopump | 1 |
| V049-0-010 | D960113-00-V | 0 | Washington LT End Station | 1 |
| V049-0-011 | D960131-00-V | 0 | Washington LT Mid Station | 1 |
| V049-0-012 | D960114-00-V | 0 | Washington LT Beam Manifold | 1 |
| V049-0-013 | D960115-00-V | 0 | Washington Vertex Section | 1 |
| V049-0-014 | D960116-00-V | 0 | Washington Diagonal Section | 1 |
| V049-0-015 | D960117-00-V | 0 | Washington RT Beam Manifold | 1 |
| V049-0-016 | D960118-00-V | 0 | Washington RT Mid Station | 1 |
| V049-0-017 | D960119-00-V | 0 | Washington RT End Station | 1 |
| V049-0-018 | D960120-00-V | 0 | Washington Crrr St Mechanical Rm | 1 |
| V049-0-020 | D960121-00-V | 0 | LA Left End Station | 1 |
| V049-0-021 | D960122-00-V | 0 | LA Left & Right Mid Joints | 1 |
| V049-0-022 | D960123-00-V | 0 | LA Left Beam Manifold | 1 |
| V049-0-023 | D960124-00-V | 0 | LA Vertex Section | 1 |
| V049-0-024 | D960125-00-V | 0 | LA Right Beam Manifold | 1 |
| V049-0-025 | D960126-00-V | 0 | LA Right End Station | 1 |
| V049-0-026 | D960127-00-V | 0 | LA Corner St Mechanical Rm | 1 |

- PSI transmittal V049-1-013, Approximate Total I/O Count for WA site, dated December 1, 1995
- PSI transmittal V049-1-036, Rev. 1, Instrument List, dated March 11, 1996

2 GENERAL DESCRIPTION

2.1. Specification Tree

This document is part of an overall LIGO detector requirement specification tree. This particular document is highlighted in the following figure.




Figure 1: LIGO Specification Tree

2.2. Product Perspective

The VCMS is to be a subsystem of the larger LIGO CDS. Figure 2 depicts the relationship of the VCMS to the LIGO CDS and to the VE.




Figure 2: Product Perspective

2.3. Product Functions

The primary VCMS functions are:

- Monitoring of all sensors provided by the vacuum equipment manufacturer (except those associated with the bakeout system).
- Closed loop control of specified equipment.
- Appropriate interlocking systems, such that equipment is not operated in a hazardous manner (except those on the roughing pumps, turbo pumps and bakeout system).
- Local operation (adjacent to the equipment in the vacuum equipment areas) of all controlled and monitored vacuum equipment.
- Remote operation (from a central Facility Control Room (FCR)) of all controlled and monitored vacuum equipment.
- Operator interfaces, as necessary, to support both local and remote operation.
- Operational support services, such as data archiving and retrieval and alarm management.
- Integration with the remainder of the LIGO CDS systems.

2.4. General Constraints

The design and implementation of the VCMS shall be in compliance with the LIGO CDS control and monitoring requirements, LIGO T950054-C, and the global CDS design and design standards, as defined in LIGO T950120-C, to ensure proper integration with the remainder of the LIGO CDS.

2.5. Assumptions and Dependencies

2.5.1. LIGO Global CDS

The infrastructure, such as timing, networking, and operational support, will be provided by the LIGO CDS. As such, only requirements particular to the VCMS, such as particular display and alarm management layouts, are specified here and not the overall scheme for providing these functions.

2.5.2. Vacuum Equipment (VE) Design

The vacuum equipment and its sensors and actuators are being provided by PSI under contract to LIGO. The VCMS requirements are therefore highly dependent on the PSI designs and documentation. As details of the VE designs change, this document will be updated to reflect those changes.

2.5.3. VE Vendor Provided Equipment/Documentation for Control and Monitoring

The VE vendor is to provide all VE sensor and actuator equipment.

The VE vendor is to provide all P&IDs and signal lists which include types, levels, engineering unit conversions and calibration constants.

The VE vendor is to provide closed loop control specifications.

2.5.4. System Installation

It is assumed that LIGO CDS personnel will have access to VE areas prior to VE acceptance tests such that the VCMS required for those tests may be installed and checked out. Access is also required to install the LIGO CDS network infrastructure if data logging and archiving is desired during the acceptance test period.

3 REQUIREMENTS

3.1. Introduction

A Computer Integrated Manufacturing (CIM) model has been developed and is used to as a guide to specify the VCMS requirements. This CIM model is shown in figure 3. The remainder of this

section follows this model, from the system level down to the device level. At each level, requirements are listed which either:

- Are general requirements that pertain to that level and everything below that level.
- Pertain to the control and monitoring of multiple, lower level components. Example: System level would specify any requirements which would involve the control of multiple sub-systems; Subsystem level would specify the control requirements for multiple assemblies; etc.




Figure 3: Vacuum System CIM Model

3.2. Characteristics

3.2.1. Performance Characteristics

3.2.1.1 System Level

3.2.1.1.1 *General*

The VCMS shall meet the applicable requirements as outlined in the LIGO CDS Control and Monitoring DRD, LIGO T950054-C, and be implemented using applicable standards as established in the LIGO CDS Control and Monitoring Conceptual Design, LIGO T950120-C. These documents provide the overall LIGO CDS requirements and design standards for the CDS infrastructure, including timing and networking systems, to which the VCMS must interface, and operational support hardware and software, such as operator stations and software for operator displays, alarm management, and archival tools, which will provide the infrastructure for specific implementations required for the VCMS.

3.2.1.1.2 *Operator Stations*

3.2.1.1.2.1 *Remote*

Remote operator consoles are to be provided by the LIGO Global CDS in the Facility Control Rooms (FCR) at both LIGO sites. The VCMS operator interface displays shall be designed and implemented such that they can be run from any of the operator consoles in the FCR.

3.2.1.1.2.2 *Local*

Local, i.e. in the vicinity of the VCMS equipment racks in the Vacuum Equipment (VE) areas, operation of VE will be required during acceptance testing and maintenance periods. To support this, the VCMS shall provide TBD portable computers, which provide the same control and monitoring features as the FCR operator consoles for the subset of equipment in a particular area.

3.2.1.1.3 *Operator System Level Displays*

In general, the VCMS shall provide a hierarchy of operator interface displays, from a system overview panel, down through subsystem and assembly panels. Movement through this hierarchy shall be accommodated by the use of icon selections.

3.2.1.1.3.1 *System Overview Panel*

The following system level displays shall be provided as a minimum:

- Navigator: This window shall depict the various defined VE subsystems. On operator select of a subsystem, that subsystem overview window shall be displayed.
- Vacuum Summary: A summary window shall be provided which depicts the vacuum readings and isolation valve status in all sections of the VE.
- Pump Summary: A summary window shall be provided which depicts the present status of all vacuum pumps and isolation valves.

3.2.1.1.3.2 *System Trend Plots*

Trend plots shall be provided to depict all vacuum readings in the system.

3.2.1.1.3.3 *Use of color on displays*

The use of certain colors shall be restricted and have specific meaning when applied to VCMS operator interface displays. These are:

- Green: Shall be used to indicate that a device is in its proper state to support LIGO laser operations.
- Blue: A device is a “don’t care” condition (i.e. is not critical to high vacuum operations)
- Yellow: Warning indication that a device is transiting to/from its proper state for high vacuum operations.
- Red: A device is in an alarm condition or is a critical item which is not in its proper state to support high vacuum operations.

3.2.1.1.3.4 *Symbols*

Standard symbols, as shown on PSI drawings, for vacuum components shall be depicted for VE on operator displays. Along with the use of the previous standard colors, the present state (i.e. opened/closed, on/off, etc.) of the components shall also be indicated.

3.2.1.1.4 *VCMS Diagnostics*

The VCMS shall provide self-diagnostics, in keeping with LIGO CDS standards. These diagnostics shall be performed on all hardware and software associated with the VCMS.

3.2.1.1.5 *VCMS Start-up*

On power up or reset of any portion of the VCMS itself, the VCMS shall not disturb the present state of the VE. The VCMS shall detect the present state of the VE and update its internal state vectors to correspond to this state.

3.2.1.1.6 *Interlocks*

3.2.1.1.6.1 *Overview*

The primary interlocks associated with the LIGO VE is the opening of the large 44” and 48” vacuum section isolation valves. The VCMS shall provide a hierarchy of interlocks, as shown in Figure 4: Isolation Valve Interlock Chain, all of which must be met prior to permitting the opening of these valves.




Figure 4: Isolation Valve Interlock Chain

3.2.1.1.6.2 *Isolation Valve Open Permissives (Normal Operations)*

The VCMS shall ensure that the two isolatable vacuum sections either side of an isolation valve have a “VE Section Permissive” (see section 3.2.1.2.2 Interlocks) prior to permitting opening of the associated isolation valve.

3.2.1.1.6.3 *Maintenance/Test Mode*

There will be certain times, such as during VE acceptance testing and at atmosphere maintenance periods, that it will be desired to operate the isolation valves without the VE system being under vacuum, and thereby not meeting the interlock requirements specified in 3.2.1.1.6.2 Isolation Valve Open Permissives (Normal Operations) above. Therefore, the VCMS shall provide a mechanism which allows bypassing these interlocks. This bypass mechanism:

- Shall not be implemented in software or otherwise be readily accessible such that it could be inadvertently installed.
- Shall cause an alarm condition to be introduced into the VCMS alarm monitors, with visual and audible enunciation at operator stations whenever this bypass is invoked.
- Shall cause a visual (red light) panel indication to be illuminated at the associated VCMS sub-system equipment rack whenever this bypass is invoked.

3.2.1.1.7 *System Status Reporting*

The VCMS shall provide a “Ready for Normal Operations” signal to the LIGO CDS. This signal shall be set True when and only when:

- The VCMS is operational as indicated by no failure in its self-diagnostic tests.
- VE system is at high vacuum state as indicated by all isolation valves being open, all high vacuum pumping operational, and all vacuum readings are in the normal, high vacuum range.

3.2.1.1.8 Closed Loop Control

None.

3.2.1.1.9 Automatic Sequences

3.2.1.1.9.1 Rate of Rise Calculations

The VCMS shall provide automatic rate of rise calculations for each isolatable vacuum section. Provisions shall be made to allow turning this function on/off and setting both the frequency and period of the calculations.

3.2.1.1.9.2 Fault Condition Monitoring and Corrective Action

While the “Ready for Normal Operations”, defined above, is set to True, the VCMS shall automatically monitor the rate of rise and absolute pressure on all isolatable vacuum sections. If any of the rate of rise calculations or pressure readings are above a settable limit, a warning is to be issued through the VCMS alarm management system. If this condition continues beyond a set time limit after the warning, the VCMS shall automatically close all isolation valves. To support this feature, the VCMS shall provide:

- An adjustable rate of rise and pressure fault limit
- A time setting, indicating the time to wait between the warning condition and the automatic shutting of the isolation valve.
- An on/off mechanism, which would allow operators to turn on/off the automatic valve closing feature.

3.2.1.1.10 Alarm Management

3.2.1.1.10.1 General

The VCMS shall provide an alarm tree structure, which shall be viewable with the standard LIGO CDS alarm management software. This alarm tree shall be structured in the same manner as the VCMS CIM model. The VCMS shall monitor, record and enunciate all alarm conditions associated with the VE, as defined in following sections of this document.

One branch of the alarm tree shall be the internal VCMS self-diagnostics.

3.2.1.1.10.2 VCMS Status

The VCMS shall provide a TBD status word to the CDS, updated at a rate of TBD, indicating that the VCMS has/has not passed its self-diagnostic tests.

3.2.1.1.11 Data Archival

3.2.1.1.11.1 General

VCMS data archiving shall be developed and compatible with the standard LIGO CDS data archiving system. Specifically, the VCMS shall archive:

- All operator actions.
- All digital (binary) VE signals on change of state.
- The status of specific VE analog signals on change beyond a deadband, as detailed in following sections of this document.

The VCMS shall also provide a method for operators to start and stop the data archival processes.

3.2.1.1.11.2 System Level Analog Signals

Table 3: System Level Data Archival lists the signals at this level which are to be archived by the VCMS and under what conditions.

Table 3: System Level Data Archival

| <i>Signal</i> | <i>Archive Condition</i> |
|---------------|--------------------------|
| Rate of Rise | Deadband TBD |
| | |
| | |

3.2.1.1.11.3 Pump Hours

For all pumps monitored by the VCMS, a pump operating hours log shall be maintained to augment, not replace, a separate pump use and maintenance log. The VCMS shall facilitate operator input of pump serial numbers for pump tracking.

3.2.1.1.11.4 State Vector

A state vector (TBD format) indicating the state of the VE monitored by the VCMS (and the time) shall be archived whenever the state changes. The state vector shall be the concatenation of subsystem status words.

3.2.1.1.11.5 State Vector

3.2.1.1.12 On-Line Documentation

All VCMS documentation shall be available on-line, i.e. displayed on request at any FCR console or local operator station.

3.2.1.2 Subsystems

The VCMS CIM has defined subsystems to agree with the PSI P&IDs to maintain the same terminology. These subsystems and the assemblies which they contain are listed below. (Note: The

Beam Tube (BT)/Manifold assembly is intended to cover and is defined as devices which are not a part of other assemblies but rather directly connect to the beam tube/manifold, such as various gauges and pumps.)

1. Right and Left End Stations

- 80K Cryopump (1)
- 44" Isolation Valve, Electric Actuator (2)
- BSC (1)
- BT/Manifold (1)

2. Right and Left Mid Stations

Since only the Hanford site contains a 2Km IFO, the mid stations at the two sites differ in the assemblies which they contain. The Hanford site contains:

- 80K Cryopump (2)
- 44" Isolation Valve, Electric Actuator (4)
- BSC (1)
- BT/Manifold (1)

The Livingston site mid stations only contain the following assemblies:

- 48" Isolation Valve, Electric Actuator (1)
- BT/Manifold (1)

3. Corner Station - Right and Left Beam Manifolds

- 80K Cryopump (1)
- 44" Isolation Valve, Pneumatic Actuator (2)
- BSC (1) (Hanford site only)
- BT/Manifold (1)

4. Corner Station - Vertex

- 48" Isolation Valve, Electric Actuator (2)
- BSC (3)
- HAM (6)
- BT/Manifold (1)

5. Corner Station - Diagonal

The corner station diagonal at the Hanford site contains the following assemblies. Since Livingston only has one interferometer, this subsystem and its associated assemblies will not exist at that site.

- 48" Isolation Valve, Electric Actuator (2)
- BSC (1)
- HAM (6)
- BT/Manifold (1)

3.2.1.2.1 General Subsystem Requirements

3.2.1.2.1.1 Operator Interfaces

An interactive GUI shall be provided for each defined subsystem. This GUI shall provide a background replicating the appropriate PSI P&ID.

A parameter page shall be provided which lists all devices and signal channels associated with a subsystem.

3.2.1.2.1.2 Subsystem Operations

Various subsystem and assemblies and devices shall be operable via interactive icons on appropriate operator display pages. However, the operation of these units shall require two independent icons to be selected by the operator:

1. State to go to: Open/Close, On/Off, cooldown, vent, etc.
2. Verification, in the form of a Cancel/Confirm icon, that the Open/Close, On/Off, cooldown, vent, etc. request was not in error. The VCMS default shall be "Cancel" and automatically timeout in 30 seconds if there is no operator response.

The purpose of this is to prevent the devices from changing states due to an inadvertent operator selection on a VCMS display.

3.2.1.2.1.3 Stand alone operation

To accommodate VE acceptance testing and certain maintenance periods, each VCMS subsystem shall be capable of stand alone operation i.e. without the LIGO CDS network backbone installed and/or operational. In stand alone operation, data archival and alarm logging shall still be provided locally.

3.2.1.2.2 Interlocks

3.2.1.2.2.1 VE Section Permissive

Each VCMS subsystem shall provide a "VE Section Permissive", to be used by the VCMS system level interlock chain for the isolation valves, for each isolatable vacuum volume in its domain.

This VE Section Permissive shall be set True when, and only when:

1. Isolation valve interlocks are satisfied. (See 3.2.1.3.4.2 Interlocks)
2. All ion pumps are on and operational within the isolatable section.
3. All pumpout port valves in that section are closed.

3.2.1.2.3 Subsystem Status

Each subsystem shall issue a "Subsystem Ready", i.e. ready for normal operations, for use by the system level to determine readiness of the VCMS as a whole for normal operations, when:

1. The conditions of 3.2.1.2.2.1 VE Section Permissive are met.
2. All isolation valves associated with a subsystem are open.

3.2.1.2.4 Subsystem State

A subsystem state vector (word) shall be maintained for each subsystem. Changes in the subsystem state vector shall be flagged to the system level.

3.2.1.2.5 Closed loop controls

None.

3.2.1.2.6 Automatic Sequences

None

3.2.1.2.7 Alarms

The VCMS equipment associated with subsystems shall provide self-diagnostics to verify the status of the VCMS hardware and software. An alarm and/or warning, as appropriate, will be generated for any VCMS components which do not pass these self-diagnostic tests.

3.2.1.2.8 Data Archival

None, except as noted in section 3.2.1.2.1.3 Stand alone operation.

3.2.1.3 Assemblies

3.2.1.3.1 80 K Cryo Pump

80K cryopumps will exist in the mid and end stations, and at the corner station in the right and left beam manifold areas. In total, there are 8 cryopumps at the Hanford site and 4 at the Livingston site. Each 80K cryopump consists of the following devices as shown in Figure 5: Vacuum System CIM Model - 80K Cryopump Devices




Figure 5: Vacuum System CIM Model - 80K Cryopump Devices

3.2.1.3.1.1 Control/Monitoring Signals

A list of signals associated with these devices is shown in Table 4: 80K Cryo Pump Device Signals.

Table 4: 80K Cryo Pump Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|--------------------|--|-------------|---------------------|-------------------------------|
| Pump Housing | Level Control Loop Output | AO | | |
| Pump Housing | Level Transmitter (LT) | AI | | |
| Pump Housing | Level Control Valve Solenoid | DO | | |
| Pump Housing | Level Control Valve Closed | DI | | |
| Pump Housing | Discharge Pressure Transmitter (DPT) | AI | | |
| Pump Housing | Discharge Temperature Thermocouple (DTT) | T/C | | |
| Regen Line | Temperature Control Output | AO | | |
| Regen Line | Loop Temperature Thermocouple (3 ea) | T/C | | |
| Dewar | LN2 Level Transmitter | AI | | |
| Pirani Gauge | Vacuum Reading | AI | | |
| Ion Gauge | Vacuum Reading | AI | | |
| Pumpout Port Valve | Closed Indication | DI | | |
| Pumpout Port Valve | Open Indication | DI | | |
| Outlet Iso. Valve | Closed Indication | DI | | |
| Outlet Iso. Valve | Open Indication | DI | | |

3.2.1.3.1.2 Operator Displays

The VCMS shall provide an interactive operator display which emulates the 80K cryopump P&ID V049-0-006. Such a display shall be provided for each cryopump.

3.2.1.3.1.3 Interlocks

The flow of liquid nitrogen (LN) from the LN Dewar to the cryopumps shall not be permitted when the pressure in the cryopump section is > TBD.

3.2.1.3.1.4 Closed Loop Control

The VCMS shall provide for closed loop control of the LN2 level within the pump housing and the regeneration temperature in accordance with specifications to be provided by PSI.

3.2.1.3.1.5 Automatic Sequences

3.2.1.3.1.5.1 Calculations

The VCMS shall provide automatic calculations for the following parameters for operator information:

- Dewar LN2 consumption rate
- Estimated time to Dewar empty
- Dewar integrated absorption rate

3.2.1.3.1.5.2 Mode Sequences

The VCMS shall provide automated sequences for transitioning between 80K cryopump operational, regeneration and cooldown modes.

3.2.1.3.1.6 Alarms

The VCMS shall produce alarms and warnings for the 80K cryopump in accordance with the conditions shown in Table 5: 80K Cryopump Alarm and Warning Conditions.

Table 5: 80K Cryopump Alarm and Warning Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|------------------------|-------------|--------------------------------|
| Pump Level Transmitter | Hi Alarm | TBD |
| Pump Level Transmitter | Low Alarm | TBD |
| Pump Discharge Temp. | Hi Alarm | TBD |
| Regen Loop Temperature | Hi Alarm | TBD |
| Dewar Level | Low Warning | TBD |
| Dewar Level | Low Alarm | TBD |
| Pirani Guage | Hi Alarm | TBD |
| Ion Gauge | Hi Alarm | TBD |

Table 5: 80K Cryopump Alarm and Warning Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|--------------------|-------------|--------------------------------|
| Pumpout Port Valve | Hi Alarm | Valve not closed |
| | | |
| | | |

3.2.1.3.1.7 Data Archival

The VCMS shall archive 80K cryopump signals in accordance with Table 6: 80K Cryopump Data Archival.

Table 6: 80K Cryopump Data Archival

| <i>Signal</i> | <i>Archive Condition</i> |
|-----------------------------|--------------------------|
| Pump LN2 Level | TBD |
| Regen Loop Temperature | TBD |
| Pump Discharge Temp. | TBD |
| Pump Discharge Pressure | TBD |
| Regen Line Temperature | TBD |
| Dewar LN2 Level | TBD |
| Dewar LN2 consumption rate | TBD |
| Dewar integrated absorption | TBD |
| Pirani Gauge Vacuum Reading | TBD |
| Ion Gauge Vacuum Reading | TBD |

3.2.1.3.2 HAM Chamber

There are to be a total of 12 HAM chambers at the Hanford site and 6 at the Livingston site. All HAM chambers are located within the vertex and diagonal sections at the corner stations.

3.2.1.3.2.1 Control/Monitoring Signals

The only VCMS monitored devices associated with a HAM chamber are to be 75 l/s annulus ion pumps. Table 7: HAM Chamber Devices shows the signals to be monitored by the VCMS.

Table 7: HAM Chamber Devices

| <i>Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|------------------------------------|-------------|---------------------|-------------------------------|
| 75 l/s Ion Pump Current Indication | AI | | |

3.2.1.3.2.2 Operator Displays

None.

3.2.1.3.2.3 Interlocks

None.

3.2.1.3.2.4 Closed Loop Control

None.

3.2.1.3.2.5 Automatic Sequences

None.

3.2.1.3.2.6 Alarms

The VCMS shall enunciate alarm conditions for a HAM chamber as described in Table 8: Ham Chamber Alarm Conditions.

Table 8: Ham Chamber Alarm Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|------------------------------|-------------|--------------------------------|
| 75 l/s IP Current Indication | High Alarm | TBD |
| 75 l/s IP Current Indication | Low Alarm | TBD |

3.2.1.3.2.7 Data Archival

The VCMS shall log the 75 l/s ion pump current whenever it changes by TBD.

3.2.1.3.3 Beam Splitter Chamber

There are to be a total of 10 BSC at the Hanford site and 5 at the Livingston site. The devices associated with a BSC are shown in Figure 6: Vacuum System CIM Model - BSC Devices.

Note: BSC 1 and 3 at Hanford and Livingston do not have purge air control valves or vacuum gauges.




Figure 6: Vacuum System CIM Model - BSC Devices

3.2.1.3.3.1 Control/Monitoring Signals

The control and monitoring signals for these devices are shown in Table 9: BSC Device Signals.

Table 9: BSC Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|------------------------|---------------------------|-------------|---------------------|-------------------------------|
| Pressure Control Valve | Control Loop Output | AO | | |
| Pirani Gauge | Vacuum Reading | AI | | |
| Ion Gauge | Vacuum Reading | AI | | |
| 75 l/s Ion Pump | Current | AI | | |

3.2.1.3.3.2 Operator Displays

The VCMS shall provide an interactive operator display which emulates the BSC P&ID V049-0-002 and -003. Such a display shall be provided for each BSC.

3.2.1.3.3.3 Interlocks

The VCMS shall provide a TBD interlock for the purge air connection.

3.2.1.3.3.4 Closed Loop Control

The VCMS shall provide closed loop control on the purge air lines to all BSC which contain them. This control is to be in accordance with a TBD procedure to be specified by PSI.

3.2.1.3.3.5 Automatic Sequences

None.

3.2.1.3.3.6 Alarms

The VCMS shall provide alarm enunciation for each BSC in accordance with Table 10: BSC Alarm Conditions.

Table 10: BSC Alarm Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|---------------------|-------------|--------------------------------|
| Pirani Gauge | High Alarm | TBD |
| Ion Gauge | High Alarm | TBD |
| 75 l/s Pump Current | High Alarm | TBD |
| 75 l/s Pump Current | Low Alarm | TBD |
| | | |
| | | |

3.2.1.3.3.7 Data Archival

The VCMS shall log BSC signals in accordance with Table 11: BSC Data Archival.

Table 11: BSC Data Archival

| <i>Signal</i> | <i>Archive Condition</i> |
|-------------------------------|--------------------------|
| Pirani Gauge | TBD |
| Ion Gauge | TBD |
| 75 l/s Pump Current | TBD |
| Purge air control loop output | TBD |

3.2.1.3.4 Isolation Valves

There will be a total of 20 vacuum section isolation valves at the Hanford site and 12 at the Livingston site. These valves are of two types and sizes:

- 44 inch pneumatic (4 at each site)
- 44 inch and 48 inch electric (16 Hanford, 8 Livingston)

From the VCMS point of view, the operation and monitoring of the various valve types is identical.

The isolation valve assembly consists of two devices:

- Valve
- 25 l/s annulus ion pump

Note: LGV7 and LGV8 at Livingston do not have associated ion pumps.

3.2.1.3.4.1 Control/Monitor Signals

Table 12: Isolation Valve Device Signals lists the control and monitor points for the isolation valves.

Table 12: Isolation Valve Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|-----------------|---------------------------|-------------|---------------------|-------------------------------|
| Valve | Closed Indicator Switch | DI | | |
| Valve | Open Indicator Switch | DI | | |
| Valve | Open Solenoid | DO | | |
| Valve | Common Alarm | DI | | |
| 25 l/s ion pump | Current Reading | AI | | |

3.2.1.3.4.2 Interlocks

This section describes the requirements for the “Local Vacuum Permissive” portion of the Isolation Valve Open interlock chain (refer to Figure 4: Isolation Valve Interlock Chain and section 3.2.1.1.6 Interlocks).

3.2.1.3.4.2.1 Normal Operation

The VCMS shall provide interlocks to prevent the inadvertent opening of these isolation valves. At the Assembly Level of this interlock chain, the VCMS shall not issue a “Local Vacuum Permissive” unless:

- The nearest up and down stream Parani gauges both provide a reading of $< 1 \times 10^{-3}$ Torr
- The nearest up and down stream Ion gauges both provide a reading of $< 1 \times 10^{-4}$ Torr

When and only when these conditions are met, a “Local Vacuum Permissive” shall be set to True for use by the subsystem level interlock checks (section 3.2.1.2.2.1 VE Section Permissive).

3.2.1.3.4.3 *Closed Loop Control*

None.

3.2.1.3.4.4 *Automatic Sequences*

The isolation valves shall be automatically closed on a fault condition as defined in section 3.2.1.1.9.2 Fault Condition Monitoring and Corrective Action.

3.2.1.3.4.5 *Alarms*

The VCMS shall provide alarm enunciation for isolation valves as defined in Table 13: Isolation Valve Alarm Conditions.

Table 13: Isolation Valve Alarm Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|--------------------|-------------|--|
| Valve Common Alarm | High Alarm | Valve signal is set to True |
| Valve | High Alarm | Valve moves from its Open or Closed seat without being commanded to do so. |
| | | |
| | | |
| | | |
| | | |

3.2.1.3.4.6 *Data Archival*

The VCMS shall log data for isolation valves in accordance with Table 14: Isolation Valve Data Archival.

Table 14: Isolation Valve Data Archival

| <i>Signal</i> | <i>Archive Condition</i> |
|---------------------|--------------------------|
| 25 l/s pump current | TBD |
| | |
| | |

3.2.1.3.5 Beam Tube/Manifold Assembly

This assembly is defined for the purposes of this specification to cover those devices which are not a direct part of other assemblies previously specified and which directly attach to the beam tube or beam manifold. Table 15: BT/Manifold Devices lists these devices and their quantity per VCMS subsystem. Predominantly, these devices are to be provided by PSI, with the exception of 10" pumpout port valves at the end of beam tube sections, which are to be provided by CB&I.

Table 15: BT/Manifold Devices

| <i>Subsystem</i> | <i>Ion Gauge</i> | <i>Pirani Gauge</i> | <i>10" Pumpout Valve</i> | <i>6" Pumpout Valve</i> | <i>2500 l/s ion pump</i> |
|------------------|------------------|---------------------|--------------------------|-------------------------|--------------------------|
| WA Left End Sta. | 1 | 1 | 2 | 0 | 1 |
| WA Left Mid Sta. | 2 | 2 | 3 | 0 | 1 |
| WA Left Manifold | 1 | 1 | 2 | 1 | 1 |
| WA Vertex | 0 | 0 | 1 | 1 | 4 |
| WA Diagonal | 0 | 0 | 1 | 1 | 2 |
| WA Rht Manifold | 1 | 1 | 2 | 1 | 1 |
| WA Rht Mid Sta. | 2 | 2 | 3 | 0 | 1 |
| WA Rht End Sta. | 1 | 1 | 2 | 0 | 1 |
| LA Left End Sta. | 1 | 1 | 2 | 0 | 1 |
| LA Left Mid Jnt. | 2 | 2 | 2 | 0 | 0 |
| LA Left Manifold | 2 | 2 | 2 | 1 | 0 |
| LA Vertex | 0 | 0 | 1 | 1 | 4 |
| LA Rht Manifold | 2 | 2 | 2 | 1 | 0 |
| LA Rht Mid Jnt. | 2 | 2 | 2 | 0 | 0 |
| LA Rht End Sta. | 1 | 1 | 2 | 0 | 1 |

3.2.1.3.5.1 Control and Monitor Signals

The signals associated with the BT/Manifold devices are as shown in Table 16: BT/Manifold Device Signals. (Note: The Open/Closed indicators for the 2500 l/s ion pump gate valves are not in the present PSI instrumentation list)

Table 16: BT/Manifold Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|-------------------|---------------------------|-------------|---------------------|-------------------------------|
| Ion Gauge | Pressure Reading | AI | | |
| Pirani Gauge | Pressure Reading | AI | | |
| 10" Pumpout Valve | Open Indication | DI | | |
| 10" Pumpout Valve | Closed Indication | DI | | |
| 6" Pumpout Valve | Open Indication | DI | | |
| 6" Pumpout Valve | Closed Indication | DI | | |
| 2500 l/s ion pump | High Volt Start Switch | DO | | |
| 2500 l/s ion pump | High Volt Stop Switch | DO | | |
| 2500 l/s ion pump | Voltage Indication | AI | | |
| 2500 l/s ion pump | Current Indication | AI | | |
| 2500 l/s ion pump | Fault Alarm | DI | | |
| 2500 l/s ion pump | Gate Valve Open Ind. | DI | | |
| 2500 l/s ion pump | Gate Valve Closed Ind. | DI | | |

3.2.1.3.5.2 *Interlocks*

None.

3.2.1.3.5.3 *Closed Loop Control*

None.

3.2.1.3.5.4 *Automatic Sequences*

For all 2500 l/s ion pumps, the VCMS shall provide an automatic function which turns off an ion pump if its current reading is not in its normal operating range. This function will become active 30 seconds after an ion pump has been turned on and deactivated when a pump is turned off.

3.2.1.3.5.5 *Alarms*

The VCMS shall monitor and post alarms in accordance with Table 17: Beam Tube/Manifold Device Alarm Conditions.

Table 17: Beam Tube/Manifold Device Alarm Conditions

| <i>Device</i> | <i>Type</i> | <i>Alarm/Warning Condition</i> |
|------------------------------|--------------|--------------------------------------|
| Ion Gauge | High Alarm | |
| Pirani Gauge | High Alarm | |
| 10" Pumpout Valve | High Alarm | Valve not closed |
| 6" Pumpout Valve | High Alarm | Valve not closed |
| 2500 l/s ion pump current | High Alarm | |
| 2500 l/s ion pump current | Low Alarm | |
| 2500 l/s ion pump fault | High Alarm | |
| 2500 l/s ion pump gate valve | High Warning | Ion pump on and gate valve not open. |
| | | |
| | | |

3.2.1.3.6 Pumpdown Carts

3.2.1.3.6.1 Signal Monitoring

The VCMS shall provide for the monitoring of PSI provided signals from the roughing pump carts and turbomolecular pump carts used for initial pumpdown of LIGO vacuum sections. This includes both the main carts in the LVEA and VEA areas and the backing carts in the Mechanical Room and VE support rooms. The latter, backing carts, are to be wired by PSI to the main carts, at which point the signals are interfaced to the VCMS.

The portable pumpdown carts can be placed at a number of pump port locations, as shown in Table 18: Pumpdown Cart Locations +. The VCMS operator display shall indicate the current configuration in a graphical display. No more than one turbopump and one roughing pump will ever be used in a single subsystem (vacuum section). In addition, no more than 2 roughing pumps will be used simultaneously in the corner station. The VCMS shall request operator input of the pumpdown cart serial number (or other unique identifier) for tagging archival data.

* *Hanford site only*

+ *Not including pumpdown cart ports on the beam tube.*

The devices and signals associated with these assemblies are shown in Table 19: Turbo Pump Cart Device Signals and Table 20: Roughing Pump Cart Device Signals. (Note: Pump speed indications are not on PSI's present list of available signals)

Table 18: Pumpdown Cart Locations +

| <i>Subsystem</i> | <i>Main Turbo</i> | <i>Main Roughing</i> |
|----------------------------------|-------------------|----------------------|
| Right and Left End Stations | 1 | 1 |
| Right and Left Beam Tube Modules | 2 | 2 |
| Right and Left Mid Stations | 2 | 1 |
| Right and Left Beam Manifolds | 2 | 1 |
| Corner Vertex | 1 | 1 |
| Corner Diagonal | 1 | 1 |
| | | |

Table 19: Turbo Pump Cart Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|-----------------|---------------------------|-------------|---------------------|-------------------------------|
| Backing Pump | On/Off Indication | DI | | |
| Backing Pump | Vacuum Reading | AI | | |
| Backing Pump | Speed Indication | AI | | |
| Turbo Pump | On/Off Indication | DI | | |
| Turbo Pump | Inlet Vacuum Reading (2) | AI | | |
| Turbo Pump | Speed Indication | AI | | |
| Auto Valve | Closed Indication | DI | | |
| Auto Valve | Open Indication | DI | | |
| Purge Gas Valve | Open/Closed Indication | DI | | |

Table 20: Roughing Pump Cart Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|---------------|---------------------------|-------------|---------------------|-------------------------------|
| Backing Pump | On/Off Indication | DI | | |
| Backing Pump | Vacuum Reading | AI | | |
| Backing Pump | Speed Indication | AI | | |
| Roots Pump | On/Off Indication | DI | | |

Table 20: Roughing Pump Cart Device Signals

| <i>Device</i> | <i>Signal Description</i> | <i>Type</i> | <i>Signal Range</i> | <i>Engineering Unit Range</i> |
|-----------------|---------------------------|-------------|---------------------|-------------------------------|
| Roots Pump | Inlet Vacuum Reading (2) | AI | | |
| Roots Pump | Speed Indication | AI | | |
| Auto Valve | Open/Closed Indication | DI | | |
| Purge Gas Valve | Open/Closed Indication | DI | | |

3.2.1.3.6.2 *Data Archival*

The VCMS shall log pump cart data in accordance with Table 21: Pump Cart Data Archival.

Table 21: Pump Cart Data Archival

| <i>Signal</i> | <i>Archive Condition</i> |
|-------------------|--------------------------|
| Pump Speeds (All) | TBD |
| Pump Vacuum (All) | TBD |
| | |

3.2.2. **Physical Characteristics**

3.2.2.1 **Electronic equipment housings**

To the extent possible and reasonable, all VCMS electronic equipment shall be housed in standard 19" racks.

3.2.2.2 **Weight Limits**

VCMS equipment to be housed within the OSB shall not exceed weight limits imposed by the building raised floor loading capacities.

3.2.3. **Interface Definitions**

3.2.3.1 **Interfaces to other LIGO detector subsystems**

3.2.3.1.1 *Mechanical Interfaces*

The VCMS shall provide a VCMS standard hardware connection to the LIGO CDS communication networks.

3.2.3.1.2 *Electrical Interfaces*

The VCMS shall be electrically and software compatible with the LIGO CDS communication networks such that data can be transferred to/from the CDS infrastructure and the VCMS.

3.2.3.1.3 *Optical Interfaces*

None.

3.2.3.1.4 *Stay Clear Zones*

None.

3.2.3.2 *Interfaces external to LIGO detector subsystems*

The VCMS will have interfaces to the facilities and the VE provided by PSI.

3.2.3.2.1 *Mechanical Interfaces*

3.2.3.2.1.1 *Facility*

All VCMS equipment shall be housed in rack enclosures, mounted to the LIGO facilities floor at those points designated in the Detector - Civil Construction Interface Control Document.

3.2.3.2.1.2 *PSI*

The VCMS shall provide a standard 19" rack enclosure and terminal strips for the termination of PSI provided signal cables. This shall be the principle interface point between VE supplied by PSI and the VCMS provided by the LIGO CDS group.

The VCMS shall provide mounting space (4U, 7") within the VCMS racks for the mounting of PSI provided 24VDC power supplies.

For the turbomolecular and roughing pump carts, the VCMS shall interface at the PSI provided terminal blocks on these units.

3.2.3.2.2 *Electrical Interfaces*

3.2.3.2.2.1 *Facility*

Facility power shall be provided at a circuit breaker panel within each of the building areas where VCMS is to be installed. Facilities shall provide 20A, 110VAC breakers at each panel, with a conduit and/or raceway from the panel to each VCMS rack enclosure. VCMS shall provide the necessary cable to connect the breaker panels to the VCMS racks and further distribute AC power.

3.2.3.2.2.2 *PSI*

The electrical connection between PSI provided equipment and the VCMS shall be at the terminal strips defined in section 3.2.3.2.1.2 above.

3.2.3.2.3 *Stay Clear Zones*

As per the Detector - Civil Construction and Detector - Vacuum Equipment Interface Control Documents.

3.2.4. Reliability

The Mean Time Before Failure (MTBF) for the VCMS shall be greater than TBD.

3.2.5. Maintainability

The Mean Time To Repair (MTTR) for any VCMS component shall be less than TBD.

3.2.6. Environmental Conditions

The VCMS shall meet all performance requirements when exposed to all specified natural and induced environments.

3.2.6.1 Natural Environment

3.2.6.1.1 Temperature and Humidity

All VCMS equipment shall meet the following temperature and humidity requirements.

Table 22: Environmental Performance Characteristics

| <i>Operating</i> | <i>Non-operating (storage)</i> | <i>Transport</i> |
|------------------------|--------------------------------|--------------------------|
| +0 C to +50 C, 0-90%RH | -40 C to +70 C, 0-90% RH | -40 C to +70 C, 0-90% RH |

3.2.6.1.2 Atmospheric Pressure

The VCMS equipment design must accommodate atmospheric pressure change from a maximum of 15.2 psia to a minimum of 14.2 psia.

3.2.6.2 Induced Environment

3.2.6.2.1 Vibrations

VCMS equipment shall not produce mechanical vibrations greater than those specified in TBD.

3.2.6.2.2 Acoustic Noise

VCMS equipment shall be designed to produce the lowest levels of acoustic noise as possible and practical. In any event, VCMS equipment shall not produce acoustic noise levels greater than TBD.

3.2.6.2.3 Electromagnetic Radiation

The VCMS shall not degrade due to electromagnetic emissions as specified by IEEE C95.1-1991.

The VCMS shall not produce electromagnetic emissions beyond those specified in TBD and shall comply with the LIGO EMC Plan.

3.2.7. Transportability

All items shall be transportable by commercial carrier without degradation in performance. As necessary, provisions shall be made for measuring and controlling environmental conditions (tem-

perature and accelerations) during transport and handling. Special shipping containers, shipping and handling mechanical restraints, and shock isolation shall be utilized to prevent damage. All containers shall be movable for forklift. All items over 100 lbs. which must be moved into place within LIGO buildings shall have appropriate lifting eyes and mechanical strength to be lifted by cranes.

3.3. Design and Construction

3.3.1. Materials and Processes

3.3.1.1 Finishes

- Ambient Environment: Surface-to-surface contact between dissimilar metals shall be controlled in accordance with the best available practices for corrosion prevention and control.
- External surfaces: External surfaces requiring protection shall be painted or otherwise protected in a manner to be approved.

3.3.2. Component Naming

All tagging and naming of VCMS equipment shall be in accordance with LIGO naming standards TBD.

3.3.3. Workmanship

All details of workmanship shall be of the highest grade appropriate to the methods and level of fabrication and consistent with the requirements specified herein. There shall be no evidence of poor workmanship that would make the components unsuitable for the purpose intended. All electronic circuits, modules and wiring shall be consistent with good engineering practice and fabricated to best commercial standards.

3.3.4. Interchangeability

The VCMS shall be designed to maximize interchangeability and replaceability of mating components. Using the Line Replaceable Unit (LRU) concept, the designs shall be such that mating assemblies may be exchanged without selection for fit or performance and without modification to the section, the unit being replaced or adjacent equipment. Mature, performance proven, standard, commercially available equipment shall not be modified unless it impacts safety.

3.3.5. Safety

This item shall meet all applicable NSF and other Federal safety regulations, plus those applicable State, Local and LIGO safety requirements. A hazard/risk analysis shall be conducted in accordance with guidelines set forth in the LIGO Project System Safety Management Plan LIGO-M950046-F, section 3.3.2.

3.3.6. Human Engineering

The VCMS shall be designed and laid out in a manner consistent with good human engineering practices. Particular attention shall be paid to layouts of operator consoles/stations, work space and environmental conditions.

3.4. Documentation

3.4.1. Specifications

The following specifications shall be provided as part of the design process:

- Software Requirements Specification (SRS) for all software to be developed as part of the system.
- Interface Control Document (ICD)

3.4.2. Design Documents

The following design documents shall be provided:

- System overall design.
- System software design.

3.4.3. Engineering Drawings and Associated Lists

Engineering drawings, schematics, wire lists and cable routing lists shall be produced for the VCMS. To the greatest extent possible and practical, electronic copies shall be maintained and available on-line. All drawings shall be formatted according to LIGO standards.

3.4.4. Technical Manuals and Procedures

3.4.4.1 Procedures

Procedures shall be provided for, at minimum,

- Initial installation and setup of equipment
- Normal operation of equipment
- Normal and/or preventative maintenance
- Troubleshooting guide for any anticipated potential malfunctions
- Bypassing the isolation valve interlocks.

3.4.4.2 Manuals

The following manuals shall be provided:

- All manuals provided by commercial vendors for VCMS components.
- Manuals for all VCMS custom designed electronics and software.
- VCMS Operating Manual.

3.4.5. Documentation Numbering

All documents shall be numbered and identified in accordance with the LIGO documentation control numbering system LIGO document TBD

3.4.6. Test Plans and Procedures

All test plans and procedures shall be developed in accordance with the LIGO Test Plan Guidelines, LIGO document TBD.

3.5. Logistics

The design shall include a list of all recommended spare parts and special test equipment required.

3.6. Precedence

In the event of conflicts between this requirement document and other LIGO documents, the order of precedence shall be in accordance with the LIGO Requirement Specification Tree.

3.7. Qualification

The VCMS design shall be qualified through a series of reviews as prescribed in the LIGO Detector Implementation Plan.

Qualification of various VCMS components and subsystems shall be in accordance with Section 4 of this document.

4 QUALITY ASSURANCE (QA) PROVISIONS

4.1. General

This system shall be tested in accordance with applicable LIGO QA standards.

4.1.1. Responsibility for Tests

The LIGO CDS group shall be responsible for performing and documenting all tests associated with the VCMS.

4.1.2. Special Tests

Due to their critical nature, the isolation valve interlocks shall undergo extensive testing to ensure proper operation.

4.1.3. Configuration Management

Configuration control of specifications and designs shall be in accordance with the LIGO Detector Implementation Plan.

4.2. Quality Conformance Inspections

Design and performance requirements identified in this specification and referenced specifications shall be verified by inspection, analysis, demonstration, similarity, test or a combination thereof per the Verification Matrix, Appendix 1. Verification method selection shall be specified by individual specifications, and documented by appropriate test and evaluation plans and procedures. Verification of compliance to the requirements of this and subsequent specifications may be accomplished by the following methods or combination of methods:

4.2.1. Inspections

Inspection shall be used to determine conformity with requirements that are neither functional nor qualitative; for example, identification marks.

4.2.2. Analysis

Analysis may be used for determination of qualitative and quantitative properties and performance of an item by study, calculation and modeling.

4.2.3. Demonstration

Demonstration may be used for determination of qualitative properties and performance of an item and is accomplished by observation. Verification of an item by this method would be accomplished by using the item for the designated design purpose and would require no special test for final proof of performance.

4.2.4. Similarity

Similarity analysis may be used in lieu of tests when a determination can be made that an item is similar or identical in design to another item that has been previously certified to equivalent or more stringent criteria. Qualification by similarity is subject to Detector management approval.

4.2.5. Test

Test may be used for the determination of quantitative properties and performance of an item by technical means, such as, the use of external resources, such as voltmeters, recorders, and any test equipment necessary for measuring performance. Test equipment used shall be calibrated to the manufacture's specifications and shall have a calibration sticker showing the current calibration status.

5 PREPARATION FOR DELIVERY

Packaging and marking of equipment for delivery shall be in accordance with the Packaging and Marking procedures specified herein.

5.1. Preparation

Equipment shall be appropriately prepared. For example, vacuum components shall be prepared to prevent contamination.

5.2. Packaging

Procedures for packaging shall ensure cleaning, drying, and preservation methods adequate to prevent deterioration, appropriate protective wrapping, adequate package cushioning, and proper containers. Proper protection shall be provided for shipping loads and environmental stress during transportation, hauling and storage.

5.3. Marking

Appropriate identification of the product, both on packages and shipping containers; all markings necessary for delivery and for storage, if applicable; all markings required by regulations, statutes, and common carriers; and all markings necessary for safety and safe delivery shall be provided.

6 NOTES

APPENDIX 1 VCMS QA MATRIX

Table 23: VCMS QA Matrix

| <i>DRD Section</i> | <i>Inspect</i> | <i>Analysis</i> | <i>Demo</i> | <i>Similar</i> | <i>Test</i> |
|--|----------------|-----------------|-------------|----------------|-------------|
| 3.2.1.1.1 General | X | | | | |
| 3.2.1.1.2.1 Remote | X | | X | | |
| 3.2.1.1.2.2 Local | X | | X | | |
| 3.2.1.1.3.1 System Overview Panel | | | X | | |
| 3.2.1.1.3.2 System Trend Plots | | | X | | |
| 3.2.1.1.3.3 Use of color on displays | X | | | | |
| 3.2.1.1.3.4 Symbols | X | | | | |
| 3.2.1.1.4 VCMS Diagnostics | | | X | | X |
| 3.2.1.1.5 VCMS Start-up | | | X | | X |
| 3.2.1.1.6 Interlocks | | | X | | X |
| 3.2.1.1.9 Automatic Sequences | | | X | | X |
| 3.2.1.1.10 Alarm Management | | | X | | X |
| 3.2.1.1.11 Data Archival | | | X | | X |
| 3.2.1.1.12 On-Line Documentation | | | X | | |
| 3.2.1.2.1 General Subsystem Requirements | | | X | | X |
| 3.2.1.2.2 Interlocks | | | X | | X |
| 3.2.1.2.3 Subsystem Status | | | X | | X |
| 3.2.1.2.4 Subsystem State | | | X | | X |
| 3.2.1.2.7 Alarms | | | X | | X |
| 3.2.1.3.1.1 Control/Monitoring Signals | | | X | | |
| 3.2.1.3.1.2 Operator Displays | | | X | | |
| 3.2.1.3.1.3 Interlocks | | | X | | X |

Table 23: VCMS QA Matrix

| <i>DRD Section</i> | <i>Inspect</i> | <i>Analysis</i> | <i>Demo</i> | <i>Similar</i> | <i>Test</i> |
|---|----------------|-----------------|-------------|----------------|-------------|
| 3.2.1.3.1.4 Closed Loop Control | | | X | | X |
| 3.2.1.3.1.5 Automatic Sequences | | | X | | X |
| 3.2.1.3.1.6 Alarms | | | X | | X |
| 3.2.1.3.1.7 Data Archival | | | X | | X |
| 3.2.1.3.2.1 Control/Monitoring Signals | | | X | | X |
| 3.2.1.3.2.6 Alarms | | | X | | X |
| 3.2.1.3.2.7 Data Archival | | | X | | X |
| 3.2.1.3.3.1 Control/Monitoring Signals | | | X | | X |
| 3.2.1.3.3.2 Operator Displays | | | X | | X |
| 3.2.1.3.3.3 Interlocks | | | X | | X |
| 3.2.1.3.3.4 Closed Loop Control | | | X | | X |
| 3.2.1.3.3.6 Alarms | | | X | | X |
| 3.2.1.3.3.7 Data Archival | | | X | | X |
| 3.2.1.3.4.1 Control/Monitor Signals | | | X | | X |
| 3.2.1.3.4.2 Interlocks | | | X | | X |
| 3.2.1.3.4.4 Automatic Sequences | | | X | | X |
| 3.2.1.3.4.6 Data Archival | | | X | | X |
| 3.2.1.3.4.5 Alarms | | | X | | X |
| 3.2.1.3.5.1 Control and Monitor Signals | | | X | | X |
| 3.2.1.3.5.4 Automatic Sequences | | | X | | X |
| 3.2.1.3.5.5 Alarms | | | X | | X |
| 3.2.1.3.6.1 Signal Monitoring | | | X | | X |
| 3.2.1.3.6.2 Data Archival | | | X | | X |
| 3.2.2. Physical Characteristics | X | | | | |

Table 23: VCMS QA Matrix

| <i>DRD Section</i> | <i>Inspect</i> | <i>Analysis</i> | <i>Demo</i> | <i>Similar</i> | <i>Test</i> |
|---|----------------|-----------------|-------------|----------------|-------------|
| 3.2.3.1 Interfaces to other LIGO detector subsystems | X | | | | |
| 3.2.3.2 Interfaces external to LIGO detector subsystems | X | | | | |
| 3.2.4. Reliability | | X | | | |
| 3.2.5. Maintainability | | X | | | |
| 3.2.6. Environmental Conditions | | X | | | |
| 3.2.7. Transportability | X | | | | |
| 3.3.1. Materials and Processes | X | | | | |
| 3.3.2. Component Naming | X | | | | |
| 3.3.3. Workmanship | X | | | | |
| 3.3.4. Interchangeability | X | | | | |
| 3.3.5. Safety | X | X | | | |
| 3.3.6. Human Engineering | X | | | | |
| 3.4. Documentation | X | | | | |
| 3.5. Logistics | X | | | | |
| 3.6. Precedence | X | | | | |
| 3.7. Qualification | X | | | | |

BATCH START

March 1996

STAPLE
OR
DIVIDER

LASER INTERFEROMETER GRAVITATIONAL WAVE OBSERVATORY
- LIGO -
CALIFORNIA INSTITUTE OF TECHNOLOGY
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

Document Type LIGO-T960024-00 - CDR 3/19/96

**Vacuum Control and Monitoring
System (VCMS) Design Requirements**

R. Bork

Distribution of this draft:

This is an internal working note
of the LIGO Project.

California Institute of Technology
LIGO Project - MS 51-33
Pasadena CA 91125
Phone (818) 395-2129
Fax (818) 304-9834
E-mail: info@ligo.caltech.edu

Massachusetts Institute of Technology
LIGO Project - MS 20B-145
Cambridge, MA 01239
Phone (617) 253-4824
Fax (617) 253-7014
E-mail: info@ligo.mit.edu

WWW: <http://www.ligo.caltech.edu/>