

# LASER INTERFEROMETRIC GRAVITATIONAL-WAVE OBSERVATORY

## Recent Progress



February, 2000

Nergis Mavalvala

LIGO-G000017-00-D



# OVERVIEW

---

- ❑ **Facilities and construction complete**
- ❑ **Vacuum system complete**
- ❑ **Beam tube bakeout**
  - LIGO Hanford Observatory: completed
  - LIGO Livingston Observatory: X-arm completed; Y-arm underway
  - **Seismic isolation stacks**
  - LHO 2k and LLO complete
  - LHO 4k underway
- ❑ **All core optics polished and coated**
  - Metrology shows good results
- ❑ **Suspensions**
  - LHO 2k complete
  - LLO ~ 50%

# FACILITIES AND CONSTRUCTION

---

- ❑ **All buildings and civil construction complete**
- ❑ **All vacuum equipment installed**
- ❑ **All beam tubes ready**
- ❑ **Beam tube bakeout**
  - LHO: completed
  - LLO: X-arm completed; Y-arm underway
  - H<sub>2</sub>O partial pressures →  $< 10^{-9}$  torr
- ❑ **Vacuum status**
  - Maintaining  $< 3 \times 10^{-8}$  torr even with chambers loaded
  - Partial pressure of H<sub>2</sub>O carefully monitored/budgeted to avoid contamination of beam tube

# SEISMIC ISOLATION SYSTEM


## □ Seismic isolation stacks

- Stainless steel masses  $\Rightarrow$   $\sim 600$  kg each stage
- Helicoil springs with lossy viscoelastic layer  $\Rightarrow Q \sim 40$
- 3 stages  $\Rightarrow 1/f^6$  for  $f > 10$  Hz

## □ Stack installation

- LHO 2k and LLO complete
- LHO 4k underway

## □ First-article testing of HAM stack



## □ Water outgassing from viton seats

# CORE OPTICS

## □ All 40 optics polished and coated

### □ Polished substrates

- $\mu$ -roughness:  $< 10$  ppm scatter
- Radius of curvature:  $\delta R/R < 5\%$   
(hand selected pairs  $\Rightarrow \delta R/R < 3\%$ )

### □ Coated optics

- Point defects:  $< 2$  ppm
- Coating absorption:  $< 1$  ppm
- Surface uniformity  
**3.6 Å rms (polished)  $\Rightarrow$  5.9 Å rms (coated)**

### □ Metrology

- CSIRO and NIST (633 nm)
- 1.064 mm Veeco (Wyko) interferometer
  - compares Core Optic and reference flat
  - $1 \text{ nm}_{\text{rms}}$  surface variation accuracy
  - 3% radius of curvature accuracy


### □ Internal resonance Q factors

# SUSPENSIONS

---

- ❑ **Single wire-loop suspensions**
- ❑ **Four electromagnetic actuators**
- ❑ **Four ‘shadow’ sensors for local position sensing**
- ❑ **Installation**
  - LHO 2k complete
  - LLO ~ 50%
- ❑ **Testing**
  - PD-LED package used for shadow sensors sensitive to 1.06 mm laser light
  - Cross-coupling between principle degrees of freedom in sensors

# COMMISSIONING ACTIVITIES AT LHO



# PRE-STABILIZED LASER

---

## □ Laser

- Master Oscillator Power Amplifier
- 10 W in TEM<sub>00</sub> mode

## □ PSL functions

- Frequency stabilization
- Intensity stabilization
- Pre-modecleaner


## □ Nested loop strategy

- fixed-spacer reference cavity  $\Rightarrow 0.1 \text{ Hz}/\sqrt{\text{Hz}}$
- 12 m suspended mode cleaner cavity  $\Rightarrow 10^{-4} \text{ Hz}/\sqrt{\text{Hz}}$
- 4 km arm cavities  $\Rightarrow 10^{-7} \text{ Hz}/\sqrt{\text{Hz}}$




# PSL CHARACTERIZATION

## □ Frequency stabilization



# PSL CHARACTERIZATION (2)

## □ Intensity stabilization



# INPUT OPTICS: MODE CLEANER

---


- ❑ **EO Modulation**
- ❑ **Mode-matching telescope**
- ❑ **Suspended mode cleaner**
  - 'Small' optics: 7.5 cm diameter
  - Triangular cavity
  - Finesse designed to be 1550
- ❑ **Locks easily and stably for >24 hrs**
- ❑ **Length/frequency servo BW ~ 30 kHz**
- ❑ **Output beam angular stability**
  - Long term drift ~ 4  $\mu$ rad/hr
  - Fluctuations ~ 3  $\mu$ rad rms

# MODE CLEANER CHARACTERIZATION (2)

## □ Length stability

- Long term drift  $\sim 1 \mu\text{m/hr}$
- Fluctuations  $\sim 0.1 \mu\text{m rms}$   
(mostly at pendulum and stack eigenmodes)

### Mode Cleaner Length Fluctuations



# MODE CLEANER CHARACTERIZATION (3)

- ❑ Length measured by resonant RF sideband tuning:  $L = 15.239595 \text{ m} \pm 50 \text{ } \mu\text{m}$
- ❑ Cavity linewidth measured
  - ringdown/up and AM transfer function  $\Rightarrow \Delta f = 7.31 \text{ kHz}$   
 $\Rightarrow$  finesse,  $F = 1346$
  - $T_{in} = T_{out} = 2255 \text{ ppm}$ ,  $T_{curve} = 10 \text{ ppm}$ ,  $F = 1346$   
 $\Rightarrow$  total loss = 49 ppm/mirror
- ❑ Total transmission measured:  $0.98 \pm 4.7\%$
- ❑ Internal resonances of optics measured
  - $Q = 0.75 \text{ million}$  to  $1.29 \text{ million}$  for  $f_0 = 28.233 \text{ kHz}$  mode
- ❑ Ongoing work:
  - Operation at full power
  - Increase servo bandwidth
  - Implement intensity stabilization after MC


# 2 KM FABRY-PEROT CAVITY TEST: WHY?

---

- Exercise lock acquisition controls
- Measure frequency noise from IO mode cleaner
- Test nested loop frequency control
- Early look at optical properties (losses, radii of curvature) of core optics
- Mode matching
- Degree of excitation of suspension eigenmodes and test mass internal resonances
- Measure environmental fluctuations

# 2 KM F-P TEST: LOCKING

- Gate valves between corner and mid stations first opened Dec '99
- Laser beam on suspension cage
- Cavity locks for ~15 minute stretches



# 2 KM CAVITY LOCKING

---



- ❑ **Observe ~ 0.5  $\mu\text{m}/\text{min}$  drift during 15 minute stretches**
  - Arm cavity length drift consistent in magnitude and sign with drift in laser frequency due to reference cavity drift
  - Thermal control being implemented on ref cav
- ❑ **Length-alignment coupling as length drifts**
  - More coupling than can be accounted for by observed cross-coupling in actuators at DC
  - Possible saturations in coil drivers under investigation
  - Wavefront-sensing based alignment control next
- ❑ **Excitation of 6.75 kHz 'butterfly' mode of TM**
  - Sensitive to centering of laser beam on mirror
- ❑ **Other internal resonances also excitable, e.g. 31.25 kHz !!**
- ❑ **Internal mode Q's for several core optics measured 200,000 to 10 million**



# 2 KM F-P TEST: FIRST LOOK

## □ Correlation studies: $\mu$ -seismic peak

- Common-mode displacement of optics 2 km apart is  $\sim 2x$  smaller than each optic



- Cavity length:  $L = 2009.1096 \pm 0.01$  m  
(surveying  $\Rightarrow 2009.119$  m)
- Cavity storage time  $\approx 460$   $\mu$ sec  $\Rightarrow F \approx 216$
- Sensitivity dominated by frequency noise

# OUTLOOK FOR THE NEAR FUTURE

---

## □ LHO 2km commissioning

- Single arm test ⇒ Summer 2000
- Power-recycled Michelson ⇒ Winter 2000
- PRM with FP arm cavities ⇒ Summer 2001

## □ LLO

- Similar commissioning path
- ~3 months behind LHO schedule

## □ LHO 4km

- Early 2002

## □ Noise reduction and performance enhancement phase

## □ Science run begins 2002

