



---

# Detector Installation and Commissioning Status

Dennis Coyne  
NSF Review  
May 9, 2000




# Detector

---

- Installation
- Commissioning
- Schedule Status covered in Replan




# SIMPLE LAYOUT & TERMINOLOGY





# INSTALLATION & COMMISSIONING SEQUENCE


- Installation and Commissioning are parallel activities
  - » emphasis on early discovery of problems at integrated systems level
  - » emphasis on installation of in-vacuum components as soon as possible
- Installation
  - » 3 principal phases (continuous and parallel)
  - » Includes subsystem commissioning (testing & characterization)
- Interferometer Commissioning
  - » 4 principal phases of increasing subsystem integration & complexity





# Hanford Observatory Status Overview

- **Washington 2 km Interferometer**
    - » Seismic isolation installation is complete
    - » Laser system installed and operational
    - » All suspended optics are installed and aligned
    - » ~50% of the output optics & sensors installed; balance by 6/00
    - » Data Acquisition & Global Diagnostics System installed
    - » Most servo-control electronics installed; balance by 7/00
    - » Laser locks to the Mode Cleaner routinely & robustly
    - » Vertex Michelson has been locked
    - » Each 2 km arm cavity has been locked
  - **Washington 4 km Interferometer**
    - » Seismic isolation installation complete
- Infrastructure in place**






# Livingston Observatory Status Overview

- **Louisiana 4 km Interferometer**

- » Seismic isolation installation is complete
- » Laser system installed and operational
- » All suspended optics are assembled
  - Input optics installed and aligned
- » Mode Cleaner output optics & sensors installed
- » Data Acquisition & Global Diagnostics System installed
- » Mode Cleaner servo-control electronics installed
- » Balance of installation by 10/00
- » **Laser locks to the Mode Cleaner routinely**



LIGO-G000110-01-D

*LIGO-I Installation & Commissioning Status*




# Installation Plan

---

- **Basic Strategy:**
  - » Simultaneous installation at both observatories (optimum staff utilization)
  - » Time phased installation of subsystems (leveling load on experts)
  - » Significant participation & support from observatory staff (training)
  - » Early as possible installation of all in-vacuum components (fab/assy/install. risk reduction)
  - » Early as possible system integration & commissioning (early warning)
  - » Hanford 2km Mission: Problem finding/solving ('pathfinder')
  - » Livingston 4km Mission: Robust implementation & characterization
- **Organization:**
  - » Centralized, flat organization
  - » staff from LIGO Lab (CIT, MIT, UFL, LHO, LLO)
  - » Focused on subsystems for installation:
    - subsystem leaders from the universities
    - Observatory liaisons
  - » Separate installation & commissioning leadership



# Installation & Commissioning Organization





# Seismic Isolation Systems

- Outstanding progress:
  - » Production and delivery of components meeting or exceeding installation schedule needs (and now complete)
  - » The coarse actuation system for the BSC seismic isolation systems has been installed and tested successfully in the LVEA at both Observatories
  - » BSC seismic systems at Livingston went as quickly as any installation at Hanford indicating that the transfer of experience was successful.
- All Seismic Isolation System Installation has been completed, with the exception of the tidal compensation (fine actuation) system



HAM Door Removal  
(Hanford 4km)



# Seismic Isolation Systems


## Support Tube Installation (Hanford WBSC7)



Stack Installation  
(Hanford X-Mid)



Coarse Actuation  
System






# Input Optics (IO)

- Hanford 2 km & Livingston 4 km Input Optics (IO) Installations are complete
  - » Univ. of Florida led this subsystem installation effort
  - » The Mode Cleaner routinely holds length servo-control lock for days
  - » Mode cleaner parameters are close to design specs, including the length, cavity linewidth and visibility
  - » Further characterization is underway (optics suspension diagonalization & PSL freq. noise measurement)



LIGO-G000110-01-D



*LIGO-I Installation & Commissioning Status*




# Input Optics (IO)




Control System Racks  
(2km Interferometer)

LIGO-G000110-01-D



Input Optics Section  
(2km Interferometer)

# Input Optics (IO) Layout







# Recycling Cavity Alignment

- Initial alignment procedures proved successful!

» ~100 microradian accuracy




Projected reticule pattern & PSL beam on target in front of MMT2



# Recycling Cavity Alignment

Fold Mirror


Input Test Mass




Adjusting the Fold Mirror (FMx) Alignment

# Initial Alignment System: Optical Levers

- Optical levers have been installed, aligned & are operational for all core optics in the 2km interferometer



Input Test Mass (ITMx) Optical Lever





Transmit & Receive modules visible with spool piece removed for ITMx alignment





# Core Optics Support

- Fabrication has been completed
- Installed for the 2km:
  - » Beam Dumps (most)
  - » Recycling cavity baffles, IO baffle & cryopump baffle
  - » Pick-Off Mirrors
  - » Antisymmetric Port Pick-Off Telescope
  - » Both End Test Mass Transmission Telescopes
- Current installation for the 2km:
  - » arm cavity baffles
  - » 3 pick-off telescopes
  - » high wavefront quality viewports




LIGO-G000110-01-D



*LIGO-I Installation & Commissioning Status*




# Core Optics Support: End Test Mass Transmission Telescope





# Interferometer Sensing & Control (ISC): Readout Optics and Electronics

- All 2 km Interferometer read-out sensors and electronics will be installed by 7/00
- All 2 km Interferometer alignment control electronics are installed; nearing completion at Livingston
- Common mode length control electronics have been tested (one arm)
- Differential mode whitening/de-whitening, anti-aliasing boards & software controls to be installed on the 2 km interferometer by 7/00





# Commissioning Configurations


---

- Mode cleaner and Pre-Stabilized Laser
- Michelson interferometer
- 2km one-arm cavity

Activities at both Observatories




# LIGO BLOCK DIAGRAM





# Schematic of Configuration used to date in Commissioning





# Pre-Stabilized Laser-Mode Cleaner

---

- Suspension characterization
  - » actuation/diagonalization
  - » sensitivity of local controls to stray Nd:YAG light
  - » Qs of elements measured,  $3e5-1e6$
- Laser - Mode Cleaner control system shakedown
- Laser frequency noise measurement






# Wavefront sensing on Mode Cleaner cavity

- Alignment system function verified

MODE CLEANER  
TRANSMITTED SIGNAL



MODE CLEANER  
REFLECTED SIGNAL




TIME --->








# Michelson Interferometer

- Interference quality of the recombined beams  $> 0.99$



# Core Optic Mechanical Resonance Quality Factors


Mode		Optic	Frequency (kHz)	Q factor
	Butterfly	ITMx	6.748	$1.4 \times 10^6$
		ETMx	6.639	$2.8 \times 10^6$
		BS	3.7337	$1.85 \times 10^6$
	Drumhead	ITMx	9.395	$6 \times 10^5$
		ETMx	9.254	$7.8 \times 10^4$
		BS	5.478	$2.5 \times 10^4$
	Breathing	ITMx	14.374	$1.2 \times 10^7$
		ETMx	14.372	$5.1 \times 10^6$
		BS	11.1387	$3.6 \times 10^5$

- Measured the quality factors (Q) for internal resonances of the core optics
- Q factors are high and meet requirements



# 2 km Fabry-Perot Cavity

- Includes all interferometer subsystems
  - » many in definitive form; analog servo on cavity length for test configuration
- Ability to lock cavity improves with understanding






# 2km Fabry-Perot cavity

- models of environment
  - » temperature changes on laser frequency
  - » tidal strains changing baselines
  - » seismometer/tilt correlations with microseismic peak
- mirror characterization
  - » losses: 1-2% dip in reflected signal intensity
  - » scatter: appears to be better than requirements

Input Test Mass  
Control Signal





# 2km Fabry-Perot cavity: 1 hr stretch with Unlock-Lock Transient

Cavity  
Transmitted  
Signal



Input Test Mass  
Control Signal



# 24 hr Engineering Run

---

- A 24-hour engineering data run was conducted 4/3-4 using the 2 km x-arm
- Quite useful for detector characterization studies
  - » understanding the single arm's behavior
  - » exercising algorithms
  - » excellent opportunity for LSC members to learn more about the interferometer
- Invited any interested LSC physicist
  - » 8 non-detector scientists participated
- Data is archived on hpss at CACR:  
<http://www.srl.caltech.edu/personnel/sba/hpss/index.html>



# Data Analysis: 24 hr Engineering Run

---

- Analysis of the data is underway by many groups, e.g.
  - » University of Michigan: test and refine algorithms for
    - detection of servo instabilities
    - detection of modulating or drifting line sources
    - detecting large instrumental transients
    - quantifying linear and bi-linear correlations
  - » University of Oregon:
    - develop and test routines for on-line data reduction
    - search for correlations between environmental monitors and the laser control signals
  - » University of Florida: test and refine algorithms for
    - wavelet analysis of transients
    - data compression
    - line feature variability



# Software tools for Diagnostics

---

- Data acquisition system
  - » site-wide, synchronized, flexible
  - » reduced data sets for later study
- time series viewing tools
  - » multiple time series, trends
  - » on-line
- diagnostic analysis tools
  - » fourier transforms, coherence, etc.
  - » on-line
- Change of paradigm for this field: research performed in the control room





# Commissioning

---

- Relatively 'young' undertaking
  - » unlike (much better than) previous prototype environments
- tools, researchers quickly maturing
- learning rules for structuring the work
  - » temporary hardware setups
  - » useful software tools
  - » coordination with installation
  - » multiple shifts
- second derivative is non-zero and positive



# Installation & Commissioning Summary

---

- Mode Cleaners (MC) at both Hanford and Livingston have both been aligned and locked
  - » Detailed characterization of the Livingston Mode Cleaner (MC) is underway
- The 2 km Interferometer near Michelson has been locked
- Each arm of the 2 km Interferometer has been locked
- The 2 km long arm cavity test has been completed
  - » Lock durations of ~10 hrs
  - » a 24 hr Engineering Data Run has been completed