

LIGO near-term and second-generation sensitivities

David Shoemaker MIT R-mode Mini Workshop 2 August 00



Outline

- LIGO I: brief status and planned performance
- LIGO II: Key technical elements
- LIGO II: notions of performance
- LIGO II: notions of the timeline



Status of LIGO I

- facility infrastructure complete
- 1+0.9+0.5 interferometers complete
- all subsystems tested: no catastrophes






LIGO Livingston Observatory

LIGO Hanford Observatory

G000180-00-M


LIGO II





Commissioning: subsystems tests

- mirror suspensions, controllers
- models of environment
 - » tidal strains changing baselines
 - » seismometer/tilt correlations with microseismic peak
- laser noise, intensity fluctuations
- mirror characterization
 - » losses: 1-2% dip in reflected signal intensity
 - » scatter: appears to be better than requirements
- length and angular sensing and controls systems
- data acquisition, software tools



Time




24 hr Engineering Run

- A 24-hour engineering data run was conducted 4/3-4 using the 2 km x-arm
- Quite useful for detector characterization studies
 - » understanding the single arm's behavior
 - » exercising algorithms
 - » excellent opportunity for LSC members to learn more about the interferometer
- Invited any interested LSC physicist
 - » 8 non-detector scientists participated
- Data is archived on hpss at CACR
- to be followed with a series of engineering and then science runs



Goals for LIGO I


Performance and Facility Limits







Sensitivity of LIGO II




LIGO II



Configuration: signal recycling


- LIGO I: Power-recycled Fabry-Perot Michelson
- addition of Signal Recycling: allows adaptation of sensitivity to interesting frequency band
- make resonant, or anti-resonant, cavity for GW signal 'sidebands'
- significant development needed, underway





Laser power: to quantum limit


- optimize power given overall design
 - » shot noise decreasing as sqrt(Power)
 - » radiation pressure increasing as sqrt(Power)
- 180 W, nominally with system similar to LIGO I





Thermal Management

- 0.7 MW in arm cavities, 5 kW in central interferometer
- auxiliary optics: small beams, high intensities
- thermal focussing in Test Mass optics
 - additional heat as corrective measure **》**




HR Coating




Test Mass optics: sapphire

- LIGO I: fused silica, 10 kg
- LIGO II: sapphire, 30 kg
- thermal noise from internal modes of test mass: improved sensitivity floor
- radiation pressure: desire for greater mass
- sapphire better, but...
- requires trades with optics
- significant development
- fallback/interim (if needed): fused silica






Test Mass optics: sapphire or silica?





Suspensions: multiple pendulums


- LIGO I: simple wire loop suspension
- multiple pendulum suspensions evident path
 - » improved seismic isolation
 - » better control distribution
- fused silica suspension fibers
 - » lower loss material, MUCH less thermal noise
 - » ribbon cross-section reduces further energy stored along optic axis
- GEO to supply design, help with engineering





Isolation systems: 10 Hz cutoff

- LIGO I: lossy springs under compression, large masses: Simple Harmonic Oscillators above resonance
- want to benefit from reduced thermal noise, better sensing
- choose 10 Hz as cutoff: good compromise given other noise sources, most anticipated signals
- control band (0 Hz to 10 Hz) very important: reduced velocity for acquisition, reduced control authority at test masses
- use high-gain servo systems, low noise sensors





LIGO II Reference Design Parameters / LIGO I Comparison

Subsystem and Parameters	LIGO II Reference Design	LIGO I Implementation
Comparison With LIGO I Top Level Parameters		
Strain Sensitivity [rms, 100 Hz band]	2 x 10 ⁻²³	10 ⁻²¹
Displacement Sensitivity [rms, 100 Hz band]	8 x 10 ⁻²⁰ m	4 x 10 ⁻¹⁸ m
Fabry-Perot Arm Length	4000 m	4000 m
Vacuum Level in Beam Tube, (Vacuum Chambers)	$< 10^{-6}$, ($< 10^{-7}$) torr	< 10 ⁻⁶ torr
Laser Wavelength	1064 nm	1064 nm
Optical Power at Laser Output	180 W	10 W
Optical Power at Interferometer Input	125 W	5 W
Power Recycling Factor	80 x	30 x
Input Mirror Transmission	3%	3%
End Mirror Transmission	15 ppm	15 ppm
Arm Cavity Power Loss on Reflection	1%	3 %
Light Storage Time in Arms	0.84 ms	0.84 ms
Test Masses	Sapphire, 30 kg	Fused Silica, 11 kg
Mirror Diameter	28 cm	25 cm
Test Mass Pendulum Period	1 sec	1 sec
Seismic Isolation System	Active/Passive, 6 stage	Passive, 4 stage
Seismic Isolation System Horizontal Attenuation	10 ⁻⁸ (10 Hz)	≥ 10 ⁻⁵ (100 Hz)
Maximum Background Pulse Rate	1 per 10 years, triple interferometer coincidence	1 per 10 years, triple interferometer coincidence

G000180-00-M




Timeline

Most optimistic schedule - LIGO II funding TBD

YEAR	LIGO I	LIGO II	
2000	Installation and commissioning	R&D	
2001	Installation and commissioning	R&D	
2002	Science run	R&D, design, long lead items	
2003	Science run	R&D, design, fabrication	
2004	Additional science run	Fabrication, on-site assembly	
2005	LIGO I interferometers removed	Fabrication, on-site assembly, installation into vacuum system	
2006		Installation and commissioning	



LIGO, Built to Last



G000180-00-M

LIGO II