



---

## *Detector Installation and Commissioning*

Stan Whitcomb




NSF Operations Review

26 February 2001

*LIGO Hanford Observatory*




# LIGO Observatories





# Initial LIGO Sensitivity Goal



- Strain sensitivity  
 $< 3 \times 10^{-23} \text{ 1/Hz}^{1/2}$   
at 200 Hz
- ✦ Sensing Noise
  - » Photon Shot Noise
  - » Residual Gas
- ✦ Displacement Noise
  - » Seismic motion
  - » Thermal Noise
  - » Radiation Pressure



## *Installation/Commissioning Philosophy*

---

- Each interferometer has a specific role in commissioning
  - » 2 km Interferometer: “Pathfinder”, move quickly, identify problems, move on
  - » LLO 4 km Interferometer: Systematic characterization, problem resolution
  - » LHO 4 km Interferometer: Scheduled so that all fixes can be implemented prior to installation
- Stagger the installation and commissioning activities to make optimal use of available staff




## *Installation Status*

---


- All installation complete for LHO 2km and LLO 4km interferometers
  - » Commissioning underway
- LHO 4km interferometer
  - » Seismic isolation complete
  - » Prestabilized laser installation underway
  - » In-vacuum optics installation currently underway
- Data Acquisition/Control Network infrastructure complete at both sites
  - » Basic functionality all in place; still working on reliability, enhancements

## *Vibration Isolation Systems*

- » Reduce in-band seismic motion by 4 - 6 orders of magnitude
- » Large range actuation for initial alignment and drift compensation
- » Quiet actuation to correct for Earth tides and microseism at 0.15 Hz during observation




HAM Chamber



BSC Chamber

# Seismic Isolation – Springs and Masses




damped spring  
cross section







# Seismic System Performance



HAM stack  
in air




BSC stack  
in vacuum






## Core Optics

- Substrates:  $\text{SiO}_2$ 
  - » 25 cm Diameter, 10 cm thick
  - » Homogeneity  $< 5 \times 10^{-7}$
  - » Internal mode Q's  $> 2 \times 10^6$
- Polishing
  - » Surface uniformity  $< 1$  nm rms
  - » Radii of curvature matched  $< 3\%$
- Coating
  - » Scatter  $< 50$  ppm
  - » Absorption  $< 2$  ppm
  - » Uniformity  $< 10^{-3}$
- Successful production involved 6 companies, NIST, and the LIGO Lab
- All optics for three interferometers delivered to sites




## Core Optics Suspension and Control




- Optics suspended as simple pendulums
- Local sensors/actuators for damping and control
- Problem with local sensor sensitivity to laser light


## Pre-stabilized Laser



Custom-built  
10 W Nd:YAG Laser,  
joint development with  
Lightwave Electronics  
(now commercial product)



Cavity for  
defining beam geometry,  
joint development with  
Stanford




Frequency stabilization  
cavity



## WA 2k Pre-stabilized Laser Performance

- > 20,000 hours continuous operation
- Frequency lock typically holds for months
- Improvement in noise performance
  - » electronics
  - » acoustics
  - » vibrations





## *Control and Data System*

---

- EPICS-based distributed realtime control system
  - » ~50 realtime processors, ~20 workstations per site
  - » ~5000 process variables (switches, sliders, readings, etc) per interferometer
  - » Fiber optic links between buildings
- Data acquisition rate of 3 MB/s per interferometer
  - » Reflective memory for fast channels, EPICS for slow ones
  - » Synchronized using GPS
  - » Data served to any computer on site in realtime or playback mode using same tools
- Multiplexed video available in control room and next to the interferometer



## *Commissioning Status*


---

- LHO 2 km interferometer
  - » Identified problem with scattered light in suspension sensors during modecleaner testing – moved to lower power and continued on
  - » Early test of individual arm cavities performed before installation was complete
  - » Full interferometer locked at low input power (100 mW)
    - All longitudinal degrees of freedom controlled
    - Partial implementation of wavefront-sensing alignment control
  - » Still tuning servo loops to get design performance
- LLO 4 km interferometer
  - » Careful characterization of laser-modecleaner subsystems
  - » Single arm testing underway (discovered that there was no need for separate single arm configuration for hardware)
  - » Repetition of 2 km integrations taking much less time than (I) expected (20 times shorter to date, but probably can't continue)


# Locking an Interferometer

Requires test masses to be held in position to  $10^{-10}$ - $10^{-13}$  meter:

*“Locking the interferometer”*




# Steps to Locking the Interferometer





# Watching the Interferometer Lock






## *Engineering Runs*

---

- Means to involve the broader LSC in detector commissioning
- Engineering Runs are a key part of our commissioning plan
  - » Test interferometer stability, reliability
  - » Well-defined dataset for off-site analysis
  - » Develop procedures for later operations
- First Engineering Run (E1) in April 2000
  - » Single arm operation of 2 km interferometer with wavefront sensing alignment on all angular degrees of freedom
  - » 24 hour duration
  - » Lots of interest, seven LSC groups made arrangements for data access

## Second Engineering Run (E2)


- November 2000
  - » One week of 24/7 operation of 2 km interferometer
  - » Approximately 35 scientists participated on site
- Recombined Michelson with Fabry-Perot arms
  - » Misaligned recycling mirror to make for more robust locking
  - » Typical locked stretches 30 – 90 minutes (longest ~ 3 hours)
  - » >90% duty cycle for in-lock operation
- Organized around 14 detector investigations
  - » Earthtides, frequency noise, calibration, noise stationarity, seismic noise, noise bursts, line tracking, ...
- Major test of data acquisition system
  - » Successful interface with LDAS front-end
  - » Transferred 2 terabytes of data to Caltech archive





## E2: Recombined Michelson Robustness


Randomly chosen hour from recent engineering run






## E2: Earthtide Investigation

- Observed in earlier E1 Run
- Main cause of loss of lock in E2 run: ~200 microns p-to-p
- Tidal actuator being commissioned for continuous lock
- Common mode (both arms stretch together) and differential mode (arms stretch by different amounts)





## E2: Recombined Interferometer Spectrum



First differential arm spectrum, Nov. 2000



## *E3 Engineering Run*

---

- Scheduled for March 9-12
- **First coincidence run** between LHO 2 km interferometer (full recycled configuration) and LLO 4 km interferometer (recombined F-P Michelson)
- Again organized around investigations
- Specific goals
  - » Correlations between environmental signals
  - » Integration of data streams from two sites
  - » First operation of full recycled F-P Michelson interferometer



## *Work on Interferometer Noise*

---

Pretty much what we expected from first noise spectrum:


- Electronics noise dominant at high frequencies in E2 spectrum (due to low input power)
- Laser frequency noise dominates in mid frequency band (stabilization servos still being tuned up)
- Low frequencies seismic noise?
- Many resonant features to investigate and eliminate
- No showstoppers!





# Current Noise Spectrum

Power spectrum




Factor of 20 improvement:

- Recycling
- Reduction of electronics noise
- Partial implementation of alignment control



# Known Contributors to Noise



Identification and reduction of noise sources underway using well-established noise-hunting techniques developed on prototype interferometers




## *Progress Toward Robust Operation*

---

- ✦ Different measure of interferometer performance (in contrast with sensitivity)
  - » Interferometer lock duration goal is 40 hours
- ✦ 2 km Prestabilized Laser
  - » Two years continuous operation with ~20% loss in power (recovered in recent tune-up)
  - » Locks to reference cavity and premodecleaner for months
- ✦ Mode Cleaner
  - » Locks for weeks at a time, reacquires lock in few seconds
- ✦ Data Acquisition and Control
  - » Data Acquisition and Input Output Controllers routinely operate for days to months without problems
  - » Tools in place for tracking machine state: AutoBURT, Conlog



## Extending the Lock on a Single Arm



### ✦ Start with Y Arm

- » 12/1/99 Flashes of light
- » 12/9/99 0.2 seconds lock
- » 1/14/00 2 seconds lock
- » 1/19/00 60 seconds lock
- » 1/21/00 5 minutes lock


### • Change to X Arm

- » 2/12/00 18 minutes lock
- » 3/4/00 90 minutes lock
- » 3/26/00 10 hours lock

Result of: -automatic alignment system  
-tuning electronics  
-reduction of noise sources



# Full Interferometer Locking





## *Plan to Reach Science Run*

- Jan to mid-March
  - » LHO 2k, continued work on improving robustness of lock, some work on sensitivity
  - » LLO 4k, Lock single arm, recombined Michelson with Fabry-Perot (F-P) arms, Power Recycled Michelson (PRM)
  - » LHO 4k, installation
- March 9-12
  - » E3 (engineering run): coincidence run between full 2km interferometer and recombined Michelson with F-P arms ( possibly single arm) at LLO
- mid-March to mid-May
  - » LHO 4k, complete installation, lock modecleaner
  - » LHO 2k, suspension sensor replacement, PRM studies
  - » LLO 4k, lock full interferometer, sensitivity/robustnessearly
- May
  - » E4 run: LLO 4 km only, operating in recombined mode (possibly recycling)



## *Plan to Reach Science Run, Part 2*

---

- May - June
  - » LHO 2k, bring full interferometer back on-line, sensitivity studies
  - » LLO 4k, improve full interferometer lock, sensitivity studies
  - » LHO 4k, PRM locking (no arms yet)
- late June - early July
  - » E5 LHO 2k and LLO 4k in full recycled configuration, LHO 4k in PRM mode
- July - Sept
  - » LLO 4 k suspension sensor replacement, bring back on-line
  - » LHO 2km sensitivity studies, 4k lock full interferometer
- late Sept
  - » E6 triple coincidence run with all 3 interferometers in final optical configuration (“upper limit run”)
- Oct – early 2002
  - » Improve sensitivity and reliability
  - » Alternate diagnostic testing with engineering runs







## *Detector Upgrades*

---

- **Planned Detector Upgrades**
  - » Redesigned Damping Sensor/Actuator Heads (increased immunity from the laser light)
  - » Digital Suspension Controllers (frequency dependent diagonalization)
  - » Servo-control and diagnostic software modifications (continuous)
  - » On-line system identification (enable controls improvement)
  - » Adaptive interferometer control (for improved control robustness)




## *Detector Upgrades (continued)*

---

- Possible Future Detector Upgrades
  - » Modulated damping sensor electronics (increased immunity to laser light)
  - » Improved laser frequency stabilization servo electronics (noise reduction)
  - » Improved interferometer sensing & control servo electronics (noise reduction)
  - » Redesigned pre-mode cleaner (enable higher bandwidth control)
  - » additional physics environment monitoring (PEM) sensors (after correlation analyses indicate useful deployment)
  - » TBD -- as commissioning and characterization studies determine needs



# Initial Detector Milestones





## Increase for Full Operations

Increases for initial LIGO Detector Operations

Budget Category	Increase	FY 2002	FY 2003	FY 2004	FY 2005	FY 2006
<b>Basic Operations</b>						
* CDS Hardware Maintenance		513,800	502,434	517,507	533,032	549,023
* LDAS Maintenance		1,378,728	1,378,728	1,322,235	1,303,163	1,303,163
Outreach		249,848	257,343	265,063	273,015	281,206
Site Operations		558,485	575,240	592,497	610,272	628,580
* Telecommunications / Networking		540,500	542,200	542,200	539,500	539,500
Staff for Site LSC Support		254,678	262,318	270,187	278,293	286,642
<b>Basic Operations Totals</b>		<b>3,496,039</b>	<b>3,518,263</b>	<b>3,509,689</b>	<b>3,537,275</b>	<b>3,588,114</b>
<b>Operations Support of Advanced R&amp;D</b>						
Seismic Development		506,300	434,574			
Engineering Staff		920,868	948,494	976,949	1,006,257	1,036,445
* Simulation & Modeling Staff		282,485	293,949	305,614	317,772	330,617
<b>R&amp;D Total</b>		<b>1,709,652</b>	<b>1,677,017</b>	<b>1,282,562</b>	<b>1,324,029</b>	<b>1,367,062</b>
<b>Grand Total</b>		<b>5,205,691</b>	<b>5,195,280</b>	<b>4,792,252</b>	<b>4,861,304</b>	<b>4,955,176</b>

Covered in Observatory Operations Talk

\* Need recognized by NSF Review Panel



## *Increases for Initial LIGO Detector Operation*

---

- **Computer & Data System (CDS) Hardware Maintenance**
  - » Annual replacement and maintenance of the control room data acquisition and control hardware plus overhead
  - » installed detector computer and network infrastructure at both sites is ~\$3M; estimate 10% maintenance and replacement costs per year
  - » installed custom electronics and embedded computers is also ~\$3M; estimate 5% maintenance and replacement costs per year
- **LIGO Data Analysis System (LDAS) Equipment Maintenance**
  - » ~ \$4M of computing equipment for LDAS
  - » assume 25 percent replacement rate per year plus over-head
  - » missing budget was recommended by an NSF review panel



# Initial Detector Operations Staffing

Group	Roles	Proposed Staff	Incremental Staff
Hanford Observatory & Livingston Observatory	Maintain up-time & peak performance (continuous operator coverage)	14 Scientists 18 operations specialists 14 engineers 2 administrators	+ 4 operations specialists
	Ensure quality of detector operation & data stream		
	Maintain detector support infrastructure (computer network, labs, instruments, spares, ...)		+1 Computer Admin
	Maintain installed detector & LDAS equipment		+2 Scientist, +2 Engineer
	Physical configuration control of detector & LDAS equipment		
	Assist in software configuration control		
	Participate in detector characterization studies		
	Support subsystem upgrade installation & commissioning		
	visiting LSC observatory liaison		+2 Scientist
Data & Computing Group (LDAS & Simulation subgroups)	Maintain, enhance & configuration control LDAS software	9 Scientists 4 Graduate Students 9 Software Engineers	
	Data QA, distribution & archival		
	Provide LSC community with processed & QA'd data		
	Pipeline analysis of data stream		
	Astrophysics searches		
	Simulation & modeling		
Detector Support (CIT)	Lead commissioning	8 Scientists	
	Lead detector characterization studies		
	Instrumentation support to LDAS & Simulation		
	Train Observatory Staff		
Detector Support (MIT)	Lead commissioning	4 Scientists 2 Graduate Students	
	Lead detector characterization studies		
	Instrumentation support to LDAS & Simulation		
	Train Observatory Staff		
Technical & Engineering Support (CIT)	Lead installation	4 Engineers & Technicians	
	Support commissioning		
	Support detector characterization		
	Centralized design documentation & configuration control (HW & SW)		
	Lead re-design for upgrades & fixes		
		35 Scientists 18 Operations Specialists 27 Engineers 6 Graduate Students 2 Administrators	4 Scientists 4 Operations Specialists 2 Engineers 1 Administrator

## Summary

- Detector installation is nearly complete
- Commissioning is proceeding well
- 2001
  - » Improve sensitivity/reliability
  - » First coincidence operation
  - » Initial data run (“upper limit runs”)
- 2002
  - » Begin Science Run
  - » Interspersed data taking and machine improvements
- 2003-2006
  - » Minimum of one year of integrated data at  $10^{-21}$  sensitivity



First Lock in the Hanford Observatory control room