

Status of LIGO

Mark Barton

Aspen Winter Conference
on Gravitational Waves and Their Detection






LIGO I

interferometer

Initial LIGO Interferometer Configuration

- LIGO I configuration
- Science run begins in 2002






LIGO I

the noise floor

▪ Interferometry is limited by three fundamental noise sources

- seismic noise at the lowest frequencies
- thermal noise at intermediate frequencies
- shot noise at high frequencies


▪ Many other noise sources lurk underneath and must be controlled as the instrument is improved





LIGO Sites

*Hanford
Observatory*



*Livingston
Observatory*



LIGO Plans

schedule

- 1996** Construction Underway (mostly civil)
- 1997** Facility Construction (vacuum system)
- 1998** Interferometer Construction (complete facilities)
- 1999** Construction Complete (interferometers in vacuum)
- 2000** Detector Installation (commissioning subsystems)
- 2001** Commission Interferometers (first coincidences)
- 2002** Sensitivity studies (initiate LIGO Science Run)
- 2003+** LIGO I data run (one year integrated data at $h \sim 10^{-21}$)

- 2005** Begin LIGO II installation



Interferometers

international network

LIGO (Washington)



LIGO (Louisiana)





Construction Project

status

- **98% complete**

- **construction project will finish on the budget & schedule**


- **Hanford buildings complete**
 - » **last laboratory building**
 - **contract A&E design**

- **Livingston complete**
 - » **last laboratory building**
 - **contracting construction**


LIGO Facilities

Beam Tube Enclosure

- minimal enclosure
- reinforced concrete
- no services



Beam Tube Bakeout





LIGO

vacuum equipment





LIGO-G9900XX-00-M



Vacuum Chambers

Vibration Isolation Systems

- » Reduce in-band seismic motion by 4 - 6 orders of magnitude
- » Compensate for microseism at 0.15 Hz by a factor of ten
- » Compensate (partially) for Earth tides





Seismic Isolation Systems


Support Tube Installation



**Stack
Installation**



**Coarse
Actuation
System**







Seismic Isolation

constrained layer damped springs



Seismic Isolation







LIGO

Laser


- Nd:YAG
- 1.064 μm
- Output power > 8W in TEM00 mode





Improvements in Laser Performance

- Laser stability an important contributor to LIGO sensitivity
- Steady improvement in laser noise performance
 - » electronics
 - » acoustics
 - » vibrations






Optics

mirrors, coating and polishing

- All optics polished & coated
 - » Microroughness within spec. (<10 ppm scatter)
 - » Radius of curvature within spec. ($\delta R/R < 5\%$)
 - » Coating defects within spec. (pt. defects < 2 ppm, 10 optics tested)
 - » Coating absorption within spec. (<1 ppm, 40 optics tested)




Suspensions





Full Interferometer Locking

✦ Still a bit tenuous.....



Hanford Commissioning Time Line

Configurations and Lock Periods


- 11/99 - Beam down 2 km arm (Y)
- 12/9/99 - 0.2 s lock of Y arm cavity
- 1/14/00 - 2 s lock of Y arm
- 1/19/00 - 60 s lock of Y arm
- 1/21/00 - 5 min lock of Y arm
- 2/12/00 - 18 min lock of X arm
- 3/4/00 - 90 min lock of X arm
- 3/26/00 - 10 hr lock of X arm
- vent for installation
- 7/00 - lock of power-recycled Michelson
- 8/00 - lock of PRM + one arm
- 10/00 - 2 min full lock
- 11/00 - “E2” engineering run (1 arm only)
- 1/01 - 40 min full lock


Lock Sequence

- Well-defined series of stages:
 - Phase I - No resonance
 - Phase II - Sidebands resonant in PRM
 - Phase III - Sidebands resonant in PRM, carrier resonant in one arm
 - Phase IV - Sidebands resonant in PRM, carrier resonant in both arms
- Progress from stage to stage automated
 - Software recognises state of IFO based on estimators
 - Adjusts control parameters to move from state to state
 - Estimators derived from E2E modelling, improved with experience

Control Issues

- Key to full lock is managing sign change of determinant of control matrix
 - recognise approaching zero using estimators from modelling
 - disable selected servos temporarily, reenable with reversed sign





Pitch/Yaw Problem


- ≈ 0.5 -1 Hz oscillations in cavity power due to poor alignment control
- Interference problem with shadow sensors for local control
 - shadow sensors use IR LED/PD
 - great when IFO beam was to be green (Argon) - now a problem
 - redesign with different LED/PD and modulation for LHO 4k, retrofit to 2k, LLO
 - in the meantime, use very low gain
- Global alignment control only just being implemented
 - - wavefront sensors recently added
 - improves locking time from seconds to many minutes

New OSEMs



- New LED/PD
- Still IR but clear of 1064 nm
- Smoother coating (ZrN)
- Better PAM screw
- Better wire routing
- Simpler body design
- New modulated electronics
- Install in Hanford 4km, retrofit to 2 km and Livingston




~ JAN 22 '01 FULL LOCK LHO 2K SPOOL VIEWS OF ETMs



CONTAMINATION OR COATING?
FLAWS?



60 SECONDS



YARM TRANSMITTED

ACQUISITION



PEAK RECYCLING GAIN ≈ 12

XARM TRANSMITTED

SB POWER

AS DC

REFLECTED INTENSITY

BS PITCH

Tidal Limit



- Earth tides stretch the interferometer arms
 - Common mode effect to be cancelled by feedback to laser frequency
 - Differential effect to be cancelled by fine-actuation system
 - Neither yet implemented
- The only tidal compensation is currently the local control system
 - limited range
 - sets a natural limit of 10-40 min on lock stretches
 - locking is robust within those periods

Trend Data 420 minutes from 01-1-22-9-59-53 to 01-1-22-16-59-47

- MAX
- MEAN
- MIN



Trend Ch 2: H2:ASC-QPDY_DC

Trend Ch 4: H2:LSC-DARM_CTRL



Trend Ch 1: H2:ASC-QPDX_DC

Trend Ch 3: H2:LSC-CARM_CTRL



Installation/Commissioning Overview

- Hanford 2k
 - “Installation” more or less complete: vacuum, seismic, laser, in-vacuum hardware (mode cleaner, core optics, baffles, beamdumps etc), external optics, some LSC and ASC electronics
 - advanced commissioning: stable if noisy locks of the whole IFO!
- Livingston (4k)
 - Substantial progress: vacuum, seismic, laser, all in-vacuum hardware, lots of other stuff
 - Commissioning proceeding apace: 10 s locks of a 4 km cavity
- Hanford 4k
 - Installation held up to allow inclusion of redesigned OSEM
 - In-vacuum hardware being installed.

Data Runs

- 11/00: E2 engineering run
 - Hanford 2km IFO in single arm mode
 - Practice at round-the-clock operation
 - Wide variety of characterization tasks
- 3/01: E3 engineering run
 - Hanford 2 km, full IFO with recycling
 - Livingston 4 km, probably one arm
- Later in 2001
 - First proper coincidence runs
- 2002, 2003+
 - LIGO I Science Run, LIGO I Data Run