

LIGO ADVANCED SYSTEM TEST INTERFEROMETER

Program Status Report

Dave Ottaway, Gregg Harry, Ken Mason, Mike Zucker

LIGO Science Collaboration Meeting

LIGO Hanford Observatory

14 August, 2001



LASTI Mission


- Test LIGO components & systems at **full mechanical scale**
- Practice installation & commissioning
- Minimize delays & downtime for LIGO observatory upgrades

Specific Advanced LIGO Program Tasks ('01 - '06+):

- Qualify advanced **seismic isolation & suspension** systems and associated controls at full scale
- Develop detailed SEI/SUS **installation & commissioning** handbook
- Look for unforeseen interactions & excess **displacement noise**
- Test **LASER** and **Input Mode Cleaner** together at *full power*



Vacuum envelope, left (S) arm



People

•Local Staff

Grads - Jamie Rollins, Josh Phinney

Engineering - Ken Mason, Dan Mason

Tech support - Myron MacInnis, Fred Miller, Bob LaLiberte

Scientists - Rich Mittleman, Gregg Harry, Dave Ottaway

Lunch - David Shoemaker, Mike Zucker

•Visitors (since previous LSC meeting)

Initial SEI - Corey Gray, Hugh Radkins

Advanced SEI - Joe Giaime, Giles Hammond, Brian Lantz, Wensheng Hua, Tuck Stebbins

Advanced SUS - Norna Robertson, Calum Torrie, Janeen Romie, Phil Willems

CDS/DAQ/PSL/Initial SUS - Jay Heefner, Rick Karwoski, Paul Russel

•TODAY'S TOPICS

◇Optical configuration & PSL progress (Dave Ottaway)

◇Displacement noise model projections (Gregg Harry)


◇Hydraulic SEI pre-isolator design (Ken Mason; *companion talk later by Brian Lantz*)

◇Milestones, schedule, etc. (MZ)

◇*Note: advanced quad suspension work @ MIT will be reported next session*




New Infrastructure: DAQ, EPICS, GDS*



NEW! IMPROVED!! *Faster Pumpdowns!*

LASTI pressure vs. roughing time, dual vs. single QDP80 RP



Special BSC Cleanroom



Quad Pendulum



LASTI PSL



Status & Plan

- Accomplishments this period

- ◇ SEI base installation & leakcheck completed*
- ◇ BSC cleanroom completed, HAM cleanrooms refurbished
- ◇ pumping system augmentation completed
- ◇ CDS backbone, DAQ, EPICS systems installed & tested
- ◇ Initial SOS and PSL controls complete (except live-ammo testing)

- Coming up

- ◇ Initial 2-mirror test cavity suspension & installation: 9/01
- ◇ PSL complete & operating, “first light”: 9/01
- ◇ Test cavity program starts (cavity locking): 10/01
- ◇ Cable tray installation: 11/01
- ◇ SEI/SUS assembly “Mezzanine”: 1/02

Milestones/longer term

- ◇4Q99 / 4Q99 act: LASTI vacuum envelope commissioned ✓
- ◇1Q00sch / 3Q01 act: LASTI external structures installed (site tooling & help) ✓
- ◇2Q00sch / 4Q00 act: LASTI infrastructure design review ✓
- ◇3Q01: LASTI infrastructure completion (DAQ, CDS, PSL, test cavity, ...)
test cavity program, hydraulics, intensity stabilization, other expt's?
- ◇1Q02: HAM pathfinder installed for standalone testing *probable slip*
- ◇2Q02: MC controls SUS installed testing starts *possible slip*
- ◇3Q02: BSC pathfinder installed for standalone testing *probable slip*
- ◇4Q02: TM controls SUS installed for standalone testing
- ◇3Q03: LASTI controls test review
- ◇2Q04: LASTI noise prototype installed *not allowed to slip!*
- ◇2Q05: LASTI SUS/SEI test review
- ◇3Q05: Adv LIGO PSL/MC tests start

Pressing Issues

- Integration test of hydraulic pre-isolators

- ◇Based on LIGO I pressure, looks best to do HAM13 as soon as working prototypes are ready; can we do this & get useful data in time to influence pathfinder HAM and BSC advanced SEI deliveries? can there/will there be a LLO LIGO I retrofit?

- Short cavity test

- ◇g-parameter nearly unstable (coincidentally, close to adLIGO baseline)

- ◇tests to help relieve anxiety about cavity instability, Guoy phase separation, WFS operation with “the big spots”?

- ◇can we fit in some backlogged PSL-enabled tests (req'd for adLIGO but unassigned)?

- super-duper intensity stabilization (like $3e-9/rHz$)

- high power photodetectors


- spatial wavefront sensing

- other ideas?

Optical Configuration and Initial Experiments

LASTI Review
LSC 9
LIGO Hanford Observatory
August 8th, 2001

LASTI Configuration




- Initial test cavity included in center HAM
- Full LASTI in end HAM and BSC chamber

LASTI Features

- LIGO I style PSL
- Advance LIGO mode cleaner inc. suspensions
- Two test cavities
 - Limits frequency noise
 - Increases spot size to limit thermoelastic noise for sapphire
- Test cavity properties
 - waist size ~3.5 mm, length 16m
 - g factor ~ 0.9 , finesse ~ 2000
 - Triple suspensions (HAM) , Quad suspensions (BSC)
- Test cavity parameters realized by selecting the properties of the input mirrors

Initial In-Vacuum Suspended Cavity Test

- Aim: To commission the LASTI 10W PSL and to gain experience operating suspended marginally stable cavities inc. wavefront sensing (small Guoy phase separation)
- Initial Cavity Parameters:
 - Length ~1 m
 - Mirrors: Flat HR Mirror, 10m ROC 0.63 % T
 - Derived Cavity Parameters: $g \sim 0.9$, Finesse ~ 1000
 - I and finesse similar to full LASTI test cavities
- Suspensions are LIGO I SOS suspension



Summary of Current Status

- PSL

- Table layout design completed
- Optical assembly commenced
- Electrical installation completed
- Full commissioning to commence early Sept. 2001.
- Enclosure designed and expected delivery late Sept. 2001

- Initial Test Cavity

- Assembly of suspended mirrors to start early Sept. 2001.
- In - vacuum installation to be completed by end Sept. 2001'.

- Seismic Isolation


- Initial LIGO I HAM installation completed

Displacement noise modeling and trade studies

LASTI Progress Report
LSC 9
LIGO Hanford Observatory
August 8, 2001



Baseline Configuration



- 15 meter cavity length
- 2 cavities side-by-side
- Fused silica input couplers in HAM21 suspended from recycling mirror (3 stage) suspensions
- Sapphire ETMs in BSC00 suspended from core optics (4 stage) suspensions
- Pendulum suspensions with fused silica fibers/ribbons

Two Variants

- Different radii of curvature on mirrors
 - Changes in stability of cavity (g factor)
 - Changes in beam radius (thermal noise)
- “Conservative” approach
 - Stable cavity $g = 0.33$
 - Smaller beam $w_0 = 2.25$ mm
- “Aggressive” approach
 - Close to marginal stability $g = 0.85$
 - Larger beam $w_0 = 3.6$ mm

Parameters


- Cavity length: 15 m
- Residual gas pressure: Water at 10^{-6} torr
- Mode cleaner length: 15 m
- HAM seismic noise: 2×10^{-13} m/Hz^{1/2} @ 10 Hz
- Finesse: 2000
- Laser power: 6 W
- Frequency noise stabilization gain: $10^9 / f^2$
- Ta₂O₅/SiO₂ optical coatings, 3% and 1 ppm
- 40 kg Silica input couplers (RM) / Sapphire ETMs

Noise sources I


Noise sources that contribute to total noise

- Seismic
 - Advanced LIGO seismic isolation stacks/suspensions
- Thermoelastic thermal noise
 - Only important in sapphire mirrors
- Structural thermal noise (coating thermal noise)
 - $\text{Ta}_2\text{O}_5/\text{SiO}_2$ coatings-see talks by Rowan & Gretarsson
- Technical frequency noise
 - 5 kg mode cleaner mirrors
 - Reduced by servo from second cavity
- Shot noise

Conservative configuration



Aggressive configuration




Sources of noise II

Noise sources that do not contribute

- Fizeau noise (Noise from transmission through moving optic)
 - 5 cm Faraday isolator, $n = 1.5$
- Photothermal noise (Elastic response to photon heating)
 - Coating absorption 0.5×10^{-6}
- Thermorefractive noise (Change in n from thermal fluctuations)
 - $\text{Ta}_2\text{O}_5/\text{SiO}_2$ coatings
- Suspension thermal noise
- Residual gas noise
- Radiation pressure

Smaller noise sources




Other configurations


Under possible consideration

- Short (20 cm), nearly flat-flat cavity
 - Larger spot size reduces thermal noise
 - Measure thermoelastic dependance on w_0
 - Cavity very near unstable, hard to get finesse of 200
- Silica end mirrors (if problems develop with sapphire)
 - Reduced thermoelastic noise
 - Coating thermal noise detectable
- Flat-top beams
 - Reduces thermoelastic noise

Short cavity




Silica test mass substrates




Hydraulic SEI Pre-isolator Design


- Hydraulic actuator, pumping, and control system has been developed at Stanford.
- Implementation and testing of a 6 DOF system under a LIGO stack at MIT
- Joshua Phinney (MIT) at Stanford for 3 weeks
- Part of LIGO 2 seismic plan T000024
- Purpose of Quiet Hydraulic actuation system is to:
 - provide factor of 10 sensor correction of low frequency ground noise (.1 to 10 HZ)
 - provide sufficient dynamic range (+/- 1mm) for earth tide and seasonal drift correction




- Counterwound springs
2 pc
- Hydraulic Actuators
- Flange mount to center element
- Position sensors concentric to actuator axis




- Springs attach to support structure
- Takes stack weight and provides tension on actuator
- Uses existing piers and adapter plates



- Hard stops and top plate not shown
- Fits in place of existing course actuators
- Course actuators to consist of x and y axis dovetails kinematic z axis



- 6 DOF actuation
- Tangent to table center
- Analysis remaining



8/14/2001

SCHEDULING MILESTONES

- Joshua returns from Stanford 9/1/01
- Design and analysis complete 11/24/01
- Long lead and fabricated parts in house 2/15/02
- Mechanical and electronics assembly complete 4/1/02
- Programming and troubleshooting complete 5/15/02
- 6 DOF testing complete 7/30/02

Note:

Schedule could be accelerated to resolve problems with impulsive noise disturbing lock at LLO