

LIGO Status Report

Barry Barish

PAC Meeting - Hanford 29-Nov-01



LIGO Plans


schedule


	1996	Construction Underway (mostly civil)
	1997	Facility Construction (vacuum system)
	1998	Interferometer Construction (complete facilities)
	1999	Construction Complete (interferometers in vacuum)
1	2000	Detector Installation (commissioning subsystems)
	2001	Commission Interferometers (first coincidences)
ı	2002	Sensitivity studies (initiate LIGO I Science Run)
	2003+	LIGO I data run (one year integrated data at $h \sim 10^{-21}$)
	2006+	Begin 'advanced' LIGO installation

LIGO

laser

- Nd:YAG
- 1.064 mm
- Output power > 8W in TEM00 mode











Prestabilized Laser

frequency noise

- Simplification of beam path external to vacuum system eliminates peaks due to vibrations
- Broadband noise better than spec in 40-200 Hz region




Pre-stabilized Laser laboratory data vs e2e simulation







Interferometer

locking




Lock Acquisition data compared with e2e simulation







LIGO I Sensitivity Goal



Strain sensitivity <3x10⁻²³ 1/Hz^{1/2} at 200 Hz

LIGO

steps prior to science run

- Commissioning interferometer
 - » robust locking
 - » three interferometers
 - » sensitivity
 - » duty cycle
- Interleave engineering runs (LIGO Science Collaboration)
 - » implement and test acquisition and analysis tools
 - » characterization and diagnostics studies
 - » reduced data sets
 - » merging data streams
 - » upper limits





LIGO Laboratory goals

Overall plan

- » Bring interferometers, and data acquisition and analysis capability rapidly to the ability to collect and analyze coincidence data to address the scientific goals of LIGO.
- » Use the engineering run data to exercise the complete analysis pipeline
- » Initiate scientific running in 2002 interleaved with progressive noise and availability studies
- » Advance both the interferometer commissioning and the commissioning of our analysis capability in a mutually balanced manner



LIGO Laboratory

data runs

Definitions:

- » Engineering runs (Ex): data taking runs that are primarily motivated by the Laboratory detector improvement program
- » Science runs (Sx): intended to produce a data product for the LSC with scientific goals and resulting in publications



LIGO Laboratory

run plan

- "E7" run (December 28 two full weeks)
 - » At least one interferometer at each observatory with at least one interferometer in full recycled configuration
 - » Goal of significant locked coincidence data, but sensitivity not guaranteed
 - » Laboratory responsibility, with participation open to LSC members in the LIGO I working groups. Data available to upper limits groups
 - » Analysis goal: sensitivity curves (February), full analysis (April)
 - » if not successful, repeat the E7 run in January 2002

LIGO Laboratory

proposed run plan

- S1 run May 2002.
 - » Prime purpose to carry out the first scientific searches
 - » Joint responsibility of the Laboratory and the LSC
 - » Sensitivity goal is a two site coincidence with 3 interferometers running and the achieved scientific reach (R = Volume x time) 10x better than E6
- S2 run
 - » At least 10x improvement in scientific reach beyond S1,following completion of S1 analysis
- Interleaving of E and S runs with improved scientific reach until design sensitivity and reliability are obtained




LIGO Laboratory Budgets


operations renewal

	FY 2001 (\$M)	FY 2002 (\$M)	FY 2003 (\$M)	FY 2004 (\$M)	FY 2005 (\$M)	FY 2006 (\$M)	Total 2002-6 (\$M)
Currently funded Operations	22.92	21.63	24.32	25.05	25.87	26.65	123.52
Increase for Full Operations		2.24	4.13	3.91	3.77	3.85	17.90
Advanced R&D	2.70	1.73	2.39	2.98	3.39	3.13	13.62
R&D Equipment for LSC Research		2.4	1.86	0.70			4.96
Total Budgets	25.62	28.00	32.71	32.63	33.03	33.63	160.00

FY 2001 currently funded Operations (\$19.1M for ten months) is normalized to 12 months and provided for comparison only and is not included in totals.

LIGO Budgets







Status and Plans

Commissioning in progress

- » Emphasis on making three fully operational interferometers
- » E7 run begins at end of December
- » Improvements (seismic mitigation at LLO, …)
- » Sensitivity studies to become the focus next year

LIGO I Program

- » Series of Mock Data Challenges for LDAS
- » Preparations of Upper Limit Groups
- » S1 run about May 02

Funding

- » LIGO Operations funding FY02+ (\$160M for 5 years)
- » Penn State awarded PFC (S Finn)
- » iVDGL funded LIGO tier 2 centers at UWM and Penn State

LIGO

focus of the program

- Obtain Reliable Interferometer Operations
 - » Robust Locking
 - » Multiple Interferometers
- Achieve Good Sensitivity
 - » Improvements; limiting noise; path to design goals?
- Demonstrate Science Capability
 - » Upper Limit Run Physics Results (S1 run)
- Develop Advance LIGO
 - » Advanced R&D program
 - » Design, Costs, and International Collaboration
 - » When to propose MRE funding?