



---

# LIGO Commissioning Status


Reported on behalf of LIGO colleagues by

Fred Raab,

LIGO Hanford Observatory



# The Four Corners of the LIGO Laboratory



- Observatories at Hanford, WA (LHO) & Livingston, LA (LLO)
- Support Facilities @ Caltech & MIT campuses



# Aerial Views of LIGO Facilities



LIGO Hanford Observatory  
(LHO)


LIGO Livingston Observatory  
(LLO)





# Configuration of LIGO Observatories

- 2-km & 4-km laser interferometers @ Hanford
- Single 4-km laser interferometer @ Livingston





# LIGO Laboratory & Science Collaboration

---

- LIGO Laboratory (Caltech/MIT) runs observatories and research/support facilities at Caltech/MIT
- LIGO Science Collaboration is the body that defines and pursues LIGO science goals
  - » >300 members worldwide (including LIGO Lab personnel)
  - » Includes GEO600 members & data sharing
  - » Working groups in detector technology advancement, detector characterization and astrophysical analyses
  - » Memoranda of understanding define duties and access to LIGO data




# Chronology of Detector Installation & Commissioning

- 
- 7/98 Begin LHO detector installation
  - 2/99 Begin LLO detector installation
  - 6/99 Lock first mode cleaner
  - 11/99 Laser spot on first end mirror
  - 12/99 First lock of a 2-km Fabry-Perot arm
  - 4/00 Engineering Run 1 (E1)
  - 6/00 Brush Fire burns 500 km<sup>2</sup> of land surrounding LHO
  - 10/00 Recombined LHO-2km interferometer in E2 run
  - 10/00 First lock of LHO-2km power-recycled interferometer
  - 2/01 Nisqually earthquake damages LHO interferometers
  - 4/01 Recombined 4-km interferometer at LLO
  - 5/01 Earthquake repairs completed at LHO
  - 6/01 Last LIGO-1 mirror installed
  - 12/01 Power recycling achieved for LLO-4km
  - 1/2002 E7: First triple coincidence run; first on-site data analysis
  - 1/2002 Power recycling achieved for LHO-4km

# Observatory Facilities

---

- Hanford and Livingston Lab facilities available starting 1997-8
- 16 km beam tube with 1.2-m diameter
- Beam-tube foundations in plane ~ 1 cm
- Turbo roughing with ion pumps for steady state
- Large experimental halls compatible with Class-3000 environment; portable enclosures around open chambers compatible with Class-100
- Some support buildings/laboratories still under construction



# Beam Tube Bakeout

- Method: Insulate tube and drive ~2000 amps from end to end










# LIGO I Detector Being Commissioned

- LIGO I has evolved from design principles successfully demonstrated in 40-m & phase noise interferometer test beds
- Design effort sought to optimize reliability (up time) and data accessibility
- Facilities and vacuum system designs provide an environment suitable for the most aggressive detector specifications imaginable in future.




# Vibration Isolation Systems

- » Reduce in-band seismic motion by 4 - 6 orders of magnitude
- » Little or no attenuation below 10Hz
- » Large range actuation for initial alignment and drift compensation
- » Quiet actuation to correct for Earth tides and microseism at 0.15 Hz during observation



# Seismic Isolation – Springs and Masses




damped spring  
cross section







# Seismic System Performance



HAM stack  
in air




BSC stack  
in vacuum




# Core Optics

- Substrates:  $\text{SiO}_2$ 
  - » 25 cm Diameter, 10 cm thick
  - » Homogeneity  $< 5 \times 10^{-7}$
  - » Internal mode Q's  $> 2 \times 10^6$
- Polishing
  - » Surface uniformity  $< 1$  nm rms
  - » Radii of curvature matched  $< 3\%$
- Coating
  - » Scatter  $< 50$  ppm
  - » Absorption  $< 2$  ppm
  - » Uniformity  $< 10^{-3}$
- Production involved 6 companies, NIST, and LIGO



# Core Optics Suspension and Control




- Optics suspended as simple pendulums
- Local sensors/actuators for damping and control







# Frequency Stabilization of the Light Employs Three Stages




# Pre-stabilized Laser (PSL)



Custom-built  
10 W Nd:YAG Laser,  
joint development with  
Lightwave Electronics  
(now commercial product)



Cavity for  
defining beam geometry,  
joint development with  
Stanford




Frequency reference  
cavity (inside oven)






# Continued improvement in PSL Frequency Noise

- Simplification of beam path external to vacuum system eliminated peaks due to vibrations
- Broadband noise better than spec in 40-200 Hz region




# Interferometer Control System



- Multiple Input / Multiple Output
- Three tightly coupled cavities
- Ill-conditioned (off-diagonal) plant matrix
- Highly nonlinear response over most of phase space
- Transition to stable, linear regime takes plant through singularity
- Employs adaptive control system that evaluates plant evolution and reconfigures feedback paths and gains during lock acquisition
- But it works!




# Digital Interferometer Sensing & Control System





# Earth Tide: Largest Source of Interferometer Drift


- Actuation in end/mid- stations and on laser reference cavity
- Simple model in feed-forward removes ~80%
- Feed-back removes ~20%
- Analysis of feed-back gives non-modeled tidal and temperature effects






# Microseism

Microseism at 0.12 Hz dominates ground velocity



Trended data (courtesy of Gladstone High School) shows large variability of microseism

Reduction by feed-forward derived from seismometers





# Engineering Run 7 (E7) 14Jan02

28Dec01 –

- 
- Engineering runs test partially integrated and commissioned machines under “operational” conditions to identify needed improvements
  - E7 was first engineering run to include all 3 interferometers in coincidence and tested on-line data analysis at Hanford and Livingston
  - E7 data sets will be analyzed jointly with data sets from GEO600 and Allegro
  - E7 analysis will exercise full range of astrophysical data-analysis software




## E7 Interferometer Configurations

---

- H1: 4-km interferometer at Hanford; recombined configuration; digital suspension controllers; tidal compensation; 1-W laser power
- H2: 2-km interferometer at Hanford; full power-recycling configuration; differential-mode wave-front control; analog suspension controllers; tidal compensation ; 1-W laser power
- L1: 4-km interferometer at Livingston; recombined configuration; analog suspension controllers; microseism compensation ; 1-W laser power



# Preliminary Noise Equivalent Strain Spectra for E7







# E7 Analysis Working Groups

---

- Data from E7 is being analyzed by LSC working groups for:
  - » Detector Characterization
  - » Binary Inspirals
  - » Bursts
  - » Periodic Sources
  - » Stochastic Background
- This exercise will test analysis methodology for 1<sup>st</sup> Science Run S1 this summer and feed back results into detector commissioning and code-writing effort



## Progress since 14Jan02


---

- Common-mode feedback from arms to laser frequency is now engaged on Hanford 2-km interferometer
  - » Improved control of laser frequency noise
  - » Establishes gain hierarchy to get better-conditioned control system
- Power-recycling works on Hanford 4-km interferometer
  - » Important validation of digital suspension controllers
- Laser power increased to 6 W for Hanford 2-km interferometer; tuning up under new operating conditions



# Hanford 2km interferometer improvements after E7

- Closed feedback loop from arms to laser frequency
- Reallocation of gains within length control servo system
- laser power 1 W







# Summary

---

- First coincidence run completed
- On-line analysis systems tested at LHO and LLO
- First end-to-end test of complete data analysis ongoing
- Power-recycling demonstrated on all interferometers
- All interferometers still need many control loops to be closed and then tuned
- Working to increase immunity to high seismic noise periods (especially important at LLO)



Despite a few difficulties, science runs will start in 2002.





# Beam Tube Bakeout Results

## Postbake measurements of module X1 at Hanford

March 11-12, 1999


**Table 1: Results from gas model solution of 16.9 hour postbake accumulation ending March 12, 1999 at 10:00AM .**

| molecule         | Outgassing rate @ 10C           | pressure@ 10C             | outgassing rate @ 23C           | pressure@ 23C             |
|------------------|---------------------------------|---------------------------|---------------------------------|---------------------------|
|                  | torr liters/sec/cm <sup>2</sup> | torr                      | torr liters/sec/cm <sup>2</sup> | torr                      |
| H <sub>2</sub>   | 1.6 x 10 <sup>-14</sup>         | 1.0 x 10 <sup>-9</sup>    | 5.2 x 10 <sup>-14</sup>         | 3.4 x 10 <sup>-9</sup>    |
| CH <sub>4</sub>  | < 2 x 10 <sup>-20</sup>         | < 3.4 x 10 <sup>-13</sup> | < 8.8 x 10 <sup>-20</sup>       | < 1.5 x 10 <sup>-12</sup> |
| H <sub>2</sub> O | < 3 x 10 <sup>-19</sup>         | < 5.2 x 10 <sup>-13</sup> | < 1.3 x 10 <sup>-18</sup>       | < 2.3 x 10 <sup>-12</sup> |
| N <sub>2</sub>   | < 9 x 10 <sup>-19</sup> **      | < 1.5x 10 <sup>-13</sup>  |                                 |                           |
| CO               | < 1.3 x 10 <sup>-18</sup>       | < 1.7 x 10 <sup>-13</sup> | < 5.7 x 10 <sup>-18</sup>       | < 7 x 10 <sup>-13</sup>   |
| O <sub>2</sub>   | < 1.2 x 10 <sup>-20</sup>       | < 2.3 x 10 <sup>-14</sup> |                                 |                           |
| A                | < 2.5x 10 <sup>-20</sup>        | < 3.6 x 10 <sup>-14</sup> |                                 |                           |
| CO <sub>2</sub>  | < 6.5 x 10 <sup>-20</sup>       | < 1.2x 10 <sup>-13</sup>  | < 2.9 x 10 <sup>-19</sup>       | <5.2 x 10 <sup>-13</sup>  |




# Beam Tube Bakeout

## BEAM TUBE BAKEOUT ELECTRICAL HEATING POWER




HX2 RGA PRESSURE, AMU 2 (blk), AMU 18 (blu), AMU 28 (red), AMU 44 (green)






# ITMx Internal Mode Ringdowns



9.675 kHz;  $Q \sim 6e+5$




14.3737 kHz;  $Q = 1.2e+7$






# Pre-stabilized Laser Optical Layout






# Digital Phase Control Test on Phase Noise Interferometer





# Design for Low Background Spec'd From Prototype Operation



For Example:  
Noise-  
Equivalent  
Displacement of  
40-meter  
Interferometer  
(ca1994)



# Earth Tide: Largest Source of Interferometer Drift

