



Current LIGO Commissioning Activities

LIGO Seminar, Caltech

August 1, 2003

Daniel Sigg, LIGO Hanford Observatory

Aerial View of the LIGO Sites





LIGO Hanford Observatory

LIGO Livingston Observatory





Time Line






Major Achievements in the Last 2 Years

- ❑ Four orders of magnitude improvement in sensitivity (at 150Hz)
- ❑ All 3 interferometers operate routinely in power-recycled mode
 - Kilowatts in the arm cavities
 - Common mode control to the laser
 - Auto-alignment system / Optical levers for local damping
 - Great improvements in digital controls
 - ❖ Digital suspension controller
- ❑ First science data

Strain Sensitivity for the LLO 4km Interferometer

31 January 2003



2nd Science Run


□ Inspiral Sensitivity

- L1: ~900 kpc
- H1: ~350 kpc
- H2: ~200 kpc


□ Duty cycle

- L1: 37%
- H1: 74%
- H2: 58%
- Triple: 22%

Typical S2 Sensitivity



Noise Sources @ LLO during S2





Goals for Next Science Runs

- Low frequency noise
 - Reduce acoustic couplings (S3)
 - Reduce noise from auxiliary degrees-of-freedom (S3)
- High frequency noise
 - More light to reduce shot noise (S3)
 - Thermal compensation to make recycling cavity stable (S4)
- Duty cycle
 - Full alignment control (S3)
 - Develop seismic pre-isolator for LLO (S4)



List of Tasks (1)


- ❑ Investigate thermal lensing
- ❑ Optical gain increase of LSC photodiodes
- ❑ Reduce acoustic coupling
- ❑ Improve shot noise sensitivity
- ❑ Finish auto-alignment system
- ❑ Initial Alignment (WFS5)
- ❑ Seismic retrofit at LLO
- ❑ 2K ITMX replacement
- ❑ Fix Schnupp asymmetry
- ❑ Fix LLO recycling cavity length




List of Tasks (2)

- ❑ Tune laser, replace lossy pre-mode cleaner
- ❑ Install remote power dial
- ❑ Improve laser power stabilization
- ❑ Finish ν stabilization servos
- ❑ Reduced quadrature signal (ASI servo)
- ❑ Digital IO alignment system
- ❑ Add more length sensing channels
- ❑ RFI cleanup: linear power supplies
- ❑ Install atomic clocks for timing diagnostics
- ❑ Photon calibrator

- ❑ Optics quality is (almost all) good
- ❑ Recycling gain meets or exceeds goals
 - L1: Gain of 45- 50 seen
 - H1: Gain of 40-45
 - H2: Cause of low recycling gain (20) found and fixed
- ❑ Contrast defect meets or exceeds goals
 - L1: $P_{as}/P_{bs} = 3 \times 10^{-5}$
 - H1: $P_{as}/P_{bs} = 6 \times 10^{-4}$




2 ITMX Anti-Reflective Coating



High Power Operations

H2 Sensitivity with 50-70mA of Light




- Dynamic range problem: 1000x
- Signal in wrong quadrature dominant!
- Use multiple detectors at anti-symmetric port
- Need protection for photodetectors
- Need protection for suspension wires!

Recycling Cavity Degeneracy



- RF sideband efficiency is very low
 - H1 efficiency: ~6% (anti-symmetric port relative to input)
 - lack of ITM thermal lens makes $g_1 \cdot g_2 > 1$ (unstable resonator)

Bad mode overlap!




LIGO Optical Gain Increase for LSC Photodiodes

- Dynamic range problem: 1000x
 - Locking $\sim 100 \mu\text{A}$ / running $\sim 100 \text{ mA}$
 - Separate PDs for locking (low power) and running (high power)
 - Remote dial for laser power



AS Port




AS

ASI Servo

- AS quadrature signal dominant!
- Multiple AS port detectors
 - H1: $P_{AS} = 500\text{-}600 \text{ mW} \Rightarrow 4 \text{ detectors}$
 - L1: $P_{AS} = \sim 20\text{-}30 \text{ mW} \Rightarrow 1 \text{ detector}$

Adaptive Feedback Control for Power Increase







Thermal Lensing

No mode overlap improvements seen at AS port!?

H2/L1:
Thermal Compensation


LIGO-G030348-00-D

H1 Thermal Heating: 03-5-27-7-15-0 to 03-5-27-9-14-59



Thermal Compensator Proposal



- ❑ Laser: 10-30W CW TEM₀₀ CO₂ (10.6μm)
- ❑ Ge AOM:
 - Intensity stabilization
 - Power selection
- ❑ Reflective mask:
 - Intensity profile
 - Astigmatism compensation
- ❑ Relay optics:
 - Adjust focus
 - Adjust pattern size
 - Adjust position
- ❑ Visible pilot laser



Radiation Pressure

□ Not a small effect!

Mode cleaner length shift (2kW)



**Arm cavity angular shift
2cm de-centering at 5kW**

Alignment Instabilities in High Power Optical Cavities


- Misaligned cavity & de-centered beams

- Torque depends on alignment

- Purely geometrical

- Misalignment displaces beams on optics


- Torque depends on alignment



Acoustic Noise Coupling


- Peaks occur in 80-1000 Hz band, at a level 10-100x the design sensitivity
- Source for H1/H2 coincidences(?)

**Acoustic
Excitations**



Acoustic Mitigation

- ❑ Acoustic enclosures around output tables
- ❑ Reduce couplings
 - Float optics tables
 - Simplify beam path
 - New stiffer periscope
- ❑ Reduce source
 - Muffle fan noise at electronics crates
 - Racks on isolation legs
 - Move racks
 - Reduce HVAC noise
 - Insulate mechanical room



Output Mode Cleaner(?)

- Small fixed spacer triangular cavity
 - Thermally controlled
 - In vacuum on seismic isolation
- Advantages:
 - Reduces light level (higher order modes are filtered out)
 - Solves acoustic coupling problem
 - Reduces fringe offsets coming from higher order modes
 - Reduces back scattering problems
 - Most likely reduces quadrature signal problem
- Disadvantages:
 - Fairly huge effort!
 - Photodetectors not readily accessible, must be vacuum compatible
 - Thermal control slow to acquire





Auto-Alignment System



WFS OFF

WFS ON

Arm Cavity Power



Anti-symmetric Port Power




Initial Alignment Using Wavefront Sensors

Step 1:

1. Lock X-Arm;
2. Lock cavity axis:
 - ❖ WFS5 -> ITM pitch/yaw;
 - ❖ WFS1 -> ETM pitch/yaw;
 - ❖ UGF ~1Hz;
3. Lock input beam:
 - ❖ QPDX -> MMT3 pitch/yaw;
 - ❖ UGF ~100mHz;
4. WFS relief;
5. TM biases recorded for ETMX, ITMX and MMT3.


□ Step 2: other arm






Initial Alignment: Results for Y Arm

Time series **Transmitted Power**




T0=23/07/2003 20:56:47 Avg=1

Time series **QPDY error point**




T0=23/07/2003 20:56:47 Avg=1

Time series **WFS1 error points**



LIC T0=23/07/2003 20:56:47 Avg=1

Time series **WFS5 error points**





C T0=23/07/2003 20:56:47 Avg=1

Atomic Clocks & Photon Calibrator

Proposed system:


- Central atomic clock
- Timing distributed to all buildings over fiber
- Check local GPS clocks
- Portable rubidium clock
- Required precision: 10 μ s
- Synchronize photon calibrator







Daily Variability of Seismic Noise

RMS motion in 1-3 Hz band




Active Seismic Isolation

Hydraulic External Pre-Isolator (HEPI)





Active Seismic Isolation: How it Works





Active Seismic Isolation: Preliminary Results




- Good performance:
- Motions of $2e-9 m/\sqrt{Hz}$
 - Match of trans&ratio indicates limits are loop gain and correction match.



- ❑ Strong threshold effect
- ❑ Benefits of active seismic pre-isolator unclear

Seismometer Readings at MX in 1–3 Hz band vs Wind Speed





Summary

Currently ongoing efforts:

- ❑ High power operations
- ❑ Acoustic mitigation
- ❑ Full alignment control
- ❑ Seismic pre-isolator development

S3 in November/December