

LIGO Detector Performance

Michael E. Zucker

LIGO Livingston Observatory

NSF Review of the LIGO Laboratory


17 November, 2003 at LIGO Livingston Observatory


- Michelson interferometer with Fabry-Perot arm cavities
- Arm cavity storage time

$$\tau \sim 1/2\pi f_{GW}$$
- Recycling mirror matches losses, enhances effective power by $\sim 50x$

Price to pay: **linear readout** only if


- 5 mirror separations are integer half-wavelength multiples (within $\sim 10^{-13}$ m)
- all mirror normals are precisely aligned (within $\sim 10^{-8}$ rad)
- dilemma: mirrors "free" inertially at GW frequencies, "static" in an RMS sense






example: cavity length sensing & control topology

- Array of sensors detects mirror separations, angles
- Signal processing derives stabilizing forces for each mirror, filters noise
- 5 main length loops shown; total ~ 25 degrees of freedom
- Operating points held to about 0.001 \AA , $.01 \text{ \mu rad RMS}$
- Typ. loop bandwidths from ~ few Hz (angles) to $> 10 \text{ kHz}$ (laser wavelength)



Guided Lock Acquisition

- Fast sensors monitor circulating powers, RF sidebands in cavities
- Sequencing code digitally switches feedback state at proper transition times
- Loop gains are actively scaled (every sample) to match instantaneous carrier & sideband buildups
- Designed by Matt Evans (PhD thesis)




- "Fundamental" limits (with then-current technology) determined design goals
 - **seismic** at low frequencies
 - **thermal** at mid frequencies
 - **shot noise** at high frequencies

■ Facility limits much lower to allow improvement as technology matures


■ Other "technical" noise not allowed above 1/10 of these (by design, anyway...)

BUT

■ Didn't start out near design sensitivity




- ❑ 3 interferometers at once: **challenges** & **opportunities**
 - Shortage of **people** (perpetually) & **hardware** (at least initially), BUT...
 - Can still "try out" proposed improvements & iterate designs on one machine at a time
 - Can run investigations on several phenomena at once without interference
- ❑ Installation and early commissioning **staggered**, specific roles for each:
 - First interferometer, LHO 2km: 'Pathfinder' – move quickly, identify problems, move on
 - LLO 4km (L1) interferometer: systematic characterization, problem resolution
 - LHO 4km (H1) interferometer: wait for updated/revised systems at the start
- ❑ Strategy has matured & evolved over the last 2 years
 - H1 implemented new digital suspension controls while others did noise studies
 - L1 needed to adapt control systems for higher local seismic velocities
 - Beginning to focus on stability and robustness for long-term operations
 - Higher investment in periodically synchronizing all 3 machines to latest revisions
- ❑ Interferometers are now **comparable in sensitivity**
 - Noise and stability improvements "leap-frog," with rapid propagation after debugging
 - Expert site operators & staff provide continuity, support, local knowledge
- ❑ Interferometer operation (Engineering & Science runs) alternate with commissioning & upgrades
- ❑ Scheduling includes GEO, TAMA, ALLEGRO




Strain Sensitivity for the LLO 4km Interferometer

31 January 2003

LIGO-G030014-00-E



Noise Sources @ LLO during S2



- ❑ Increased effective laser power
 - Now detecting full AS port power on each IFO (multiple PD's)
 - Also increased input power – beginning to see expected thermal lensing
 - Still factor of 3-5 to go in input power
- ❑ Mitigated **acoustic coupling** at detection ports
 - Combination of improved acoustic isolation; reduction of acoustic sources; reduction of physical coupling mechanisms
- ❑ Continued implementation of **wavefront sensor (WFS)** alignment
 - Propagated enhanced S2-era stability of H1 to other two machines
 - (full high-bandwidth implementation remains for post-S3)
- ❑ Fixed accumulated in-vacuum problems
 - Adjusted optic separations (~ 2 cm) on H1 and L1
 - Bad AR coating on one H2 test mass (replaced w/spare)
 - Installed baffles to prevent laser-cutting our suspensions wires
 - Very time-consuming due to degassing cycle
- ❑ Major upgrade to **realtime feedback controls code**
 - Adaptive gains to accommodate power up & thermal lens onset

- ❑ Primary sources:

- Building HVAC
- Electronics cooling fans


- ❑ Installed acoustic enclosures on dark ports

- ❑ Removed microphonic optics

- opened to 2" clear aperture at critical locations
- EO shutters removed at ISCT4 and ISCT1
- stiffened & damped beam delivery periscopes


- ❑ Results:

- ~10x from optics rework ~10x from acoustic enclosure)
- *No acoustic peaks* left in S3 spectra
- H1 - H2 correlations substantially reduced !



with acoustic injections at ISCT4

S2





Displacement Spectra

with injections

with acoustic injections at ISCT4 and ISCT1


S3






WFS OFF

Arm Cavity Power






WFS ON

Arm Cavity Power




Anti-symmetric Port Power






Start of S3: All 3 LIGO Interferometers at Extragalactic Sensitivity

Displacement spectral density



H1 Calibrated AS_Q spectrum:10/25/03




Summary Science Run Metrics


RUN ⇒	GOAL ("SRD")		S1		S2		S3*	
IFO ⇓	<i>BNS RANGE</i> (kpc)	<i>DUTY FACTOR</i>	<i>BNS RANGE</i> (kpc)	<i>DUTY FACTOR</i>	<i>BNS RANGE</i> (kpc)	<i>DUTY FACTOR</i>	<i>BNS RANGE</i> (kpc)	<i>DUTY FACTOR</i>
L1	14,000	90%						
H1	14,000	90%						
H2	7,000	90%						
3-way		75%						

***PRELIMINARY--RUN IN PROGRESS**

L1 got a slow start...




RMS motion in 1-3 Hz band



- Stability & uptime
 - Seismic retrofit at LLO ⇒ L1
 - Adapt WFS controls for radiation pressure torques
 - WFS bandwidth upgrade (wean off optical levers)
 - Possible wind noise mitigation for LHO
- Sensitivity
 - Thermal compensation system (TCS) ⇒ H1 test
 - Higher *effective* laser power (power & sideband overlap)
 - Laser & input optics efficiency improvement
 - Output mode cleaner (OMC) [possibly]
 - Finish acoustic mitigation
 - Enclosures for other output ports
 - Relocate electronics racks remotely ⇒ L1 test
 - Electronics cleanup: EMC upgrade ⇒ L1 test
 - Custom low-noise DAC's, other electronics upgrades



- ❑ Spiky impulsive seismic noise in 1-3 Hz band
 - Related to human activity – mostly lumber industry
 - Dominant frequencies accidentally coincide with isolator resonances
 - Impedes IFO locking during weekdays
- ❑ Large & variable microseism
 - Ocean waves excite double frequency (DF) surface waves on land
 - Fraction to several microns RMS; frequency: ~ 0.15 - 0.25 Hz
 - Wavelength ~ kilometers → L1 arm length change **several microns**
- ❑ Strategy for recovering full-time duty at LLO
 - Active **Hydraulic External Pre-Isolator** system
 - 6 D.O.F active stabilization of seismic supports (**External Pre-Isolator**)
 - Prototype demonstrated at Stanford and MIT
 - Now in full production for January installation start at LLO





K. Mason, MIT

- ❑ Static load is supported by precision coil springs
- ❑ Bellows hydraulic pistons apply force without sliding friction, moving seals
- ❑ Laminar-flow differential valves control forces
- ❑ Working fluid is glycol/water formula (soluble, nonflammable)
- ❑ Stabilized “power supply” is remote hydraulic pump with “RC” filtering & pressure feedback control
- ❑ Fits in space now used for adjusters in existing system

Hydraulic External Pre-Isolator (HEPI)






HEPI prototype performance on MIT testbed:

- Residual motion $2e-9$ m/\sqrt{Hz} at critical frequencies
- Robust and fault tolerant
- Leak-free & clean
- Meets immediate LLO requirements
- *Exceeds* advanced LIGO requirements

H2 Sensitivity with 50-70mA of Light



Power improvements:

- Locking dynamic range 1000:1 (run/acquire PD's)
- Huge signal in wrong quadrature (?!) (I servo)
- Blend multiple detectors at anti-symmetric port
- Protect photodetectors on lock loss (fast shutters)
- Protect suspension wires on misalignment (baffles, watchdogs)


Open Issues:

- Laser output & beam delivery efficiency
- Sideband coupling & sideband/carrier overlap inadequate

Recycling Cavity Degeneracy


- ❑ 'Frontal modulation' scheme depends on efficient coupling
 - Local oscillator field generated at laser, coupled into recycling cavity (not co-resonant in arm cavities)
 - Recycling cavity is **nearly degenerate** ($ROC_{[cold]} \sim 15$ km, length ~ 9 m)
 - Original "point design" depends on specific, balanced **thermal lensing**
- ❑ RF sideband efficiency found to be very low
 - H1 efficiency: $\sim 6\%$ (anti-symmetric port relative to input)
 - incorrect/insufficient ITM thermal lens makes $g_1 \cdot g_2 > 1$ (unstable resonator)


⇒ Bad mode overlap!




Thermal Lensing

H1 Thermal Heating: 03-5-27-7-15-0 to 03-5-27-9-14-59







- ❑ 10W CW TEM₀₀ CO₂ Laser (10.6μm)
- ❑ Ge AOM:
 - Intensity stabilization
 - Power selection
- ❑ Reflective mask:
 - Intensity profile (+, - 'lensing' possible)
 - Astigmatism correction
- ❑ Relay optics:
 - Focus
 - Pattern size
 - Position
- ❑ Visible pilot laser
 - Steering & alignment



- ❑ *Design near complete; parts on order for January test on H1*

- ❑ Not a small effect!
- ❑ Misaligned cavities & de-centered beams
 - Torque depends on alignment
- ❑ Strategy: **modify controls**
 - Powers and beam centroids already sensed
 - Enhanced alignment "Plant model " to include light as a **dynamic mechanical component**
 - Design calculations, code prototype under development

Mode cleaner length shift (2kW)



**Arm cavity angular shift
2cm de-centering at 5kW**

Over 4 decades sensitivity improvement since "first light"

Now within a decade of design sensitivity at 150 Hz

(of course, that's the longest mile!)

Tag-team commissioning strategy has helped turn burden of 3 concurrent machines into an advantage

Astrophysically interesting sensitivity on **ALL 3 INSTRUMENTS**

(and data rate's still ahead of analysis pipelines)

L1 Seismic Retrofit is crucial for improving uptime

Thermal Compensation, other high power upgrades to reduce noise

S4 run: longer duration, better uptime, and lower noise