



eLIGO/advLIGO FI update

Antonio Lucianetti, K.L. Dooley, R. Martin, L. F. Williams, M.A. Arain, V. Quetschke, G. Mueller, D.B. Tanner, and D.H. Reitze University of Florida, Gainesville, FL

Ligo-Virgo Meeting, Hannover, Oct. 2007

G070675-00-R





FI for eLIGO

LIGO



eLIGO/advLIGO FI configuration



- Faraday Rotator
 - Two 22.5^o TGG crystals with a reciprocal 67.5^o QR
- Calcite wedge polarizers (superior to TFPs)
- Thermal lens compensation with dn/dT material (deuterated dihydrogen phosphate, or 'DKDP')





Problems we have encountered



- TGG and DKDP crystals:
 - surface damage
 - improper AR coatings

SOLUTION: New vendor (NG)

Magnet





Diameter ~ 200 μm

FI magnet ring failure

LIGO Characterization of individual TGGs



Result from 6th order polynomial fit:

Max TGG rotation angle (crystal #2): 24.03 deg +/- 0.01 deg

Thermal lens created by TGG and DKDP







LIGO

Thermal Lensing in 'y-direction'



LIGO COMSOL Simulation (radiation enabled on faces and edges)



Parameters: TGG radius = 10.3 mm Laser beam radius = 1.5 mm

The time constants of thermal lensing are in the order of seconds

LIGO COMSOL Simulation (radiation enabled on faces and edges)

30 W incident power Time from t = 0s to t = 3600s (60min) with a line every 60s (1min)



7

Laser beam radius = 1.5 mm

the pumped face (point [0,0,0])

LIGO Faraday Isolator performance Isolation ratio (CWPs)





Decrease in isolation ratio under vacuum as time went on
Could be recovered by < 2 degree rotation of waveplate

LIGO Faraday isolator performance Effect of vacuum



- $P_L = 25 W$
- DKDP between CWPs



LIGO Faraday isolator performance thermal drift (CWPs)

Refl beam thermal drift intrinsic to FI

ELIGO FI Schedule

LLO

- Assembly, final test and measurements of the FI will be done in the clean optics lab at the LIGO Livingston Observatory
- Installation of the FI for LLO will start on Nov 13, 2007.
- Integration and commissioning of the FI and Input Optics with PSL is planned to start on June 3, 2008.

LHO

- Installation of the FI at LHO is planned to start in December 2007 or January 2008.
- Integration and commissioning of the FI and Input Optics with PSL is planned to start on Feb. 19, 2008.

Conclusions

- Initial LIGO FI measurements reveal that isolation requirements for E-LIGO are very relaxed → 20 dB will work well
- Obtained 43 dB isolation ratio with CWPs in vacuum Decrease in isolation ratio under vacuum should be recovered by < 2 degree rotation of waveplate. Intrinsic thermal drift of the reflected beam was
 < 50 microradians for the horizontal and vertical axes
- Performance is expected to improve with Northrop Grumman crystals (TGG/DKDP) and new precision mount for DKDP with tip/tilt positioning