



Status of Virgo


A. Viceré

INFN-Firenze – Università di Urbino






Virgo Sensitivity Evolution during VSR1



Progress in the sensitivity during the run...



Effect on the BNS horizon




- Significant improvement coming from noise mitigation in 50-1000Hz band
 - Due mostly to actuator noise reduction, magnetic coupling mitigation and work on supposedly acoustic noise sources, during the weekly commissioning breaks
- Horizon at the end of the run frequently up about 4.5 Mpc
 - ◆ Even somewhat better (dream horizon) when an electrical cut turned off some acoustic noise sources: work underway to identify the precise culprits
- More improvement is believed possible with more commissioning work




VSR1 locked segments & duty cycle

Good fraction of long lock periods




Science mode = 81%
(locked mode 84%)





Commissioning is restarting



- Post-run calibration/parameter checks done over 1-15th Oct period
- Now attack control and “mystery” noises
 - ◆ Priority to fix problems that would stay with us in Virgo+
 - ◆ Install as soon as available the thermal compensation system
- More details in Edwige's Tournefier talk, Tuesday afternoon



From VSR1 to Virgo+

- Target

 - ◆ ***Virgo+ online at the same time of eLIGO (i.e. mid-2009) with a sensitivity useful for joint analysis***

- Post VSR1/spring 2008:

 - ◆ Commissioning activity at low and intermediate frequency

- mid 2008

 - ◆ Install the selected parts of the Virgo+ upgrade in a few bunches

- 2009

 - ◆ Global commissioning

 - ◆ Start the second Virgo Science Run (VSR2) around mid 2009

- 2010+


 - ◆ Possibly interrupt the run for including V+ elements not introduced in first place and which can retire risk from Advanced Virgo

 - ◆ Keep running until ready for AdV installation in time to join Advanced LIGO



Virgo+ definition

- 2nd Virgo+ review held on Oct. 16-17
- Most modifications in good shape
- To be installed first half of 08
 - ◆ Thermal Compensation System
 - ◆ Increase of the laser power
 - ◆ New electronic
- Monolithic suspension sounds too late for the start of VSR2
 - ◆ Considering to start with the existing mirror/suspension
 - ◆ Keep developing the Mon. suspension for installation during V+
 - ◆ Suspension with steel wires is a backup option
- **More information in Michele Punturo's talk, afternoon today**





Data taking during Virgo+ preparation

- Keep the priority for detector improvement and commissioning.
 - ◆ Perform short commissioning runs to assess the detector, though
- Take each opportunity to collect data in “astrowatch” mode.
 - ◆ Unattended night shifts, unattended week-ends *when possible*
 - ◆ The length of the short data taking not driven by the data analysis needs
 - ◆ All science mode data can be kept for reanalysis
 - For externally triggered searches
 - For CW analysis if deemed interesting by the CW search group
- The DA council may want to review the consequences of these plans
 - ◆ Very concrete questions like
 - Do we share automatically science mode data, if any, during V+/eLIGO preparation?
 - Or do we exchange only data around interesting ext/triggers?



Advanced Virgo

- Goal
 - ◆ Sensitivity 10 times beyond Virgo design
 - ◆ Back online at 2013-2014 horizon
- Main foreseen changes
 - ◆ Higher laser power
 - ◆ Signal recycling
 - ◆ Heavier mirrors
 - ◆ Better coatings
 - ◆ Beam geometry
- Major progress recently
 - ◆ Advanced Virgo Conceptual Design being released
 - » What goes in AdV and why
 - ◆ First “cost estimate and project execution plan” (PEP) being released
 - ◆ Documents to be reviewed by funding institutions this November
- More details in Giovanni Losurdo's talk this afternoon



Other news

- Collaboration composition

- » The Padova/Trento group has joined the Virgo Collaboration

- EGO Council approved funds for post-doctoral fellows dedicated to DA


- ◆ 6 two-year position reinforcing Virgo labs involved in DA (2 Burst, CBC: 1 CW, SB)

- The Einstein Telescope (E.T.) Design Study proposal negotiated!

- ◆ Joint European proposal (GEO + Virgo)

- ◆ Underground, 30km beam pipe, Advanced suspension, Low thermal noise...

- ◆ 3.0 M€ from European Union over 3 years. **Contract signed in the coming days**



DS: Design Study, PCP: Preparatory Construction Phase