

Science & Integration Meeting

Agenda

-
- Detector & R&D
 - » NPRO stabilization results (LIGO-G960244-00-D) Mason/Savage
 - » Interferometer acquisition modeling results Sievers
 - » FMI wavefront sensing results Mavalvala/Sigg
 - » PNI status & plans Fritschel
 - » 40m recycling status Logan/Spero
 - » Core Optics Status: REO coating performance analysis Jungwirth
 - » FFT modeling (20 min) Kells
 - » DAQ prototype plan for 40m Bork/Barker



NPRO Stabilization Results


R. Abbott, A. Abramovici, A. Dominjon, J. Mason, R. Savage

NPRO-PSL Goals

- Test stabilization techniques on a Nd:YAG laser.
 - » Head start on LIGO IR-PSL (10 Watt Nd:YAG laser, Interim Design Review at Lightwave on 12/18/96)
 - » Feed conceptual design of IR-PSL (DRR 3/24/97)
- Deliver a low-power, stabilized Nd:YAG laser to MIT group for the PNI IR conversion - January 1997.
- *NPRO-PSL Design Requirements* - LIGO-T960082-00-D
 - » Relative power fluctuations $< 1 \times 10^{-8}/\text{Hz}^{1/2}$ above 100 Hz
 - » Frequency fluctuations $< 10\text{mHz}/\text{Hz}^{1/2}$ 100 Hz to 4 kHz
- *NPRO-PSL Conceptual Design* - LIGO-T960089-00-D



Nd:YAG Laser: NPRO Stabilization




open loop transfer function

- Power stabilized - loop transfer function - Source 10 mV ~~peak~~

Gain on PSP

- with capacitance on the 96 output of PSPD -

dB dB



At 500 Hz

gain = 18 dB


and we have seen 17 dB
of suppression outside the loop!

8/30/96 11:37:26

now seeing a 17dB suppression
outside the loop!

Closed loop

Same config. ls
for 19:56 plot.



8/29/96 20:05:37

$$\frac{\Delta P}{P} \text{ at } 500 \text{ Hz} \sim 4.1 \cdot 10^{-8} \frac{\text{W rms}}{\text{W Hz}}$$

PSPD $V_{PSPD} = 20.5V$

TL. $V_TL = 1.22V$

Frequency Stabilization for the NPRO Nd:YAG PSL


R. Abbott, J. Mason, R. Savage

- Demonstration of frequency stabilization using Lightwave Model 126 Nd:YAG NPRO laser
 - » Interim 1064 nm light source until 10W Nd:YAG developed
 - To be incorporated into the PNI
 - To be incorporated into the 40 m (depending on schedule)
 - » Model 126 to be used as master oscillator in 10 W MOPA under development
 - Frequency stabilization to be applied to master oscillator



A first pass at frequency stabilization

- In the beginning, there existed requirements
 - » 1 mHz/rtHz from 100 Hz to 4 kHz
 - » Fixed length reference cavity
- A first pass solution (A. Abramovici, R. Savage)
 - » A scheme for frequency stabilization devised
 - » Laser characterized
 - » Servos designed and built
 - Slow/Fast loop controller built by CDS
 - Pockels cell controller to be existing LLSPA controller
- Testing (J. Mason, R. Savage)
 - » Pockels cell left out to expedite testing of S/F controller
 - Modeling predicted lock possible with lower bandwidth
 - » Difficulty encountered trying to lock up the fast loop



A second pass at frequency stabilization

- Simplify!
 - » Locking achieved using an SR560 and the slow controller
 - Lower gain than needed, but allowed more careful characterization of the plant, and observation of locking behavior
- Rethink
 - » New model built in Matlab
 - » New requirements set (Match Detector Subs. Req. Doc.)
 - Higher frequency noise allowed, 10 mHz/rtHz
 - Lower bandwidth O.K. (300 kHz from 1 MHz)
- Redo
 - » New servo design proposed based on Matlab model
 - 40 nV/rtHz input referred noise spec'd, 8.9 nV/rtHz predicted
 - New layout provides for test inputs and monitor outputs
 - Pockels cell loop designed to be included with new controller
 - Mixer and traps included on the board




10/16/96 12:00
JEM


X=100kHz $\Delta X=90.0\text{kHz}$
Ya=12.9127 $\Delta Ya=7.323\text{ dB}$

FREQ RESP
Yb=13.2728 $\Delta Yb=6.973\text{ dB}$

CURVE FIT




10/18/96 3:00-3:30:
JEM





- G/F GAINS
BLUE: FAST 1 ($\times 81$)
SLOW .7
- GREEN FAST 4 ($\times 260$)
SLOW 10
- USES $310 \text{ ft}^2/\sqrt{\text{Hz}}$

$$\frac{260}{81} \rightarrow 10.2 \text{ dB}$$



NPRO FREQ. STAB. SERVO





Current status and future plans

- Where we're at
 - » New controller being built - expected completion 12/16
 - » AOM frequency shifting path laid out and testing has begun
- What's to be done
 - » Installation and testing of new controller
 - » Frequency shifter path implemented (w/o analyzer cavity)
 - » Documentation
 - » Delivery to MIT in mid-January
 - » Frequency noise measurements made outside the loop done at MIT using the PNI

