

LIGO Laboratory / LIGO Scientific Collaboration

LIGO- E1100296

LIGO

October 20th, 2012

**aLIGO BSC-ISI, Pre-integration Testing report,
Phase I (post-assembly)**

E1100296 – V1

Vincent Lhuillier

Distribution of this document:
Advanced LIGO Project

This is an internal working note
of the LIGO Laboratory

California Institute of Technology
LIGO Project – MS 18-34
1200 E. California Blvd.
Pasadena, CA 91125
Phone (626) 395-2129
Fax (626) 304-9834
E-mail: info@ligo.caltech.edu

LIGO Hanford Observatory
P.O. Box 1970
Mail Stop S9-02
Richland WA 99352
Phone 509-372-8106
Fax 509-372-8137

Massachusetts Institute of Technology
LIGO Project – NW22-295
185 Albany St
Cambridge, MA 02139
Phone (617) 253-4824
Fax (617) 253-7014
E-mail: info@ligo.mit.edu

LIGO Livingston Observatory
P.O. Box 940
Livingston, LA 70754
Phone 225-686-3100
Fax 225-686-7189

Table of contents:

Introduction..... 4

I. Pre-Assembly Testing..... 5

- Step 1 - CPS Test and calibration – E1100369..... 5
- Step 2 - GS13 – Inspection/Assembly – E1000058 – E1100740 5
- Step 3 - L4C – Inspection/Assembly – E1000136 – E1100740 5
- Step 4 - T240 – Inspection/Assembly - E1100326 – E1100740..... 6
- Step 5 - Actuators - T0900564 - T1100234 – E1100741..... 6

II. Tests to be performed during assembly 7

- Step 1 - Test stand level 7
- Step 2 - Actuators Inventory 7
- Step 3 - Sensors Inventory 7
- Step 4 - Electronics Inventory..... 9
- Step 5 - Check level of Stage 0 after top-bottom plate assembly 9
- Step 6 - Check gaps under the blade posts..... 9
- Step 7 - Blade post shim thickness 10
- Step 8 - Blade 0-1 post launch angle 10
- Step 9 - Gap checks on actuators 10
- Step 10 - Mass budget..... 11
- Step 11 - Lockers adjustment..... 12
- Step 12 – Cables inventory – E1100822..... 13
- Step 13 - Cable routing 14

III. Tests to perform after assembly 14

- Step 1- Geophones pressure readout..... 14
- Step 2- Set up sensors gap – Locked vs unlocked position 15
- Step 3 - Measure the Sensor gap..... 16
- Step 4- Performance of the limiters 16

 - Step 4.1 - Test N°1 - Push “in the general coordinates Z/RZ” 16
 - Step 4.2 - Test N°2 – Push “locally” 16
 - Step 5 - Sensors Powespectra 17
 - Step 6 - Coil Driver, cabling and resistance check 20
 - Step 7- Actuators Sign and range of motion (Local drive)..... 21

 - Step 7.1 - Actuators sign..... 21
 - Step 7.2 - Range of motion - Local drive..... 21
 - Step 8 - Vertical Sensor Calibration 22
 - Step 9 - Vertical Spring Constant 22
 - Step 10 - Static Testing (Tests in the local basis) 23
 - Step 11- Static Testing - In the general coordinate basis (Static test - CPS)..... 24

 - Step 11.1 – Change of basis matrices from Cartesian to Local 24
 - Step 11.2 – Base change matrices from Cartesian to Cartesian..... 25
 - Step 12 - Linearity test..... 26
 - Step 13 – Transfer functions – Local to Local..... 28
 - Step 14 - Symmetrization – Calibration..... 35
 - Step 15 – Change of base – Cartesian to Cartesian - Simulations 35
 - Step 16- Transfer functions - Cartesian to Cartesian - Measurements 38
 - Step 17 - Lower Zero Moment Plan 38



- Step 17.1 - Stage 1 - LZMP 38
- Step 17.2 - Stage 2 - LZMP 38
- 38
- Step 18- Damping Loops – Transfer function – Simulations 39
- Step 18.1 - Damping Loops – Stage 2 39
- Step 18.2 - Damping Loops – Stage 1 39
- Step 19- Damping Loops – Powerspectra..... 39
- Step 20- Isolation Loops – for one unit per site..... 39
- IV. BSC-ISI testing Summary..... 40

Introduction

The BSC-ISI testing is performed in three phases:

- 1) BSC-ISI, Pre-integration Testing, Phase I (post-assembly)
- 2) BSC-ISI, Pre-integration Testing, Phase II: Tests done after Transport (and possible storage), during mating phase with Suspensions, before insertion.
- 3) BSC-ISI, Integration Phase Testing: Procedure and results related to the commissioning in the chamber.

This document presents the series of tests (Phase I) performed on the ISI-BSC2 in the LVEA.

The testing procedure document E1000486-v5 was used.

All results are posted on the SVN at:

<https://svn.ligo.caltech.edu/svn/seismic/BSC-ISI/H2/Data/BSC2/>

The following type of document can be found in the SVN:

- Excel spreadsheet (.xls)
- Data location
- Figures location
- Masses distribution scheme (ppt)

CPS Stage 2	CPS S/N	ADE board serial #
H1	12520	13230
H2	12541	13418
H3	12448	13450
V1	12569	13238
V2	12577	13439
V3	12561	13452

Table 3 - Capacitive position sensors' inventory – Stage 2

Geophones GS13	Serial Number	POD
H1	852	54
H2	834	70
H3	540	50
V1	770	64
V2	725	55
V3	762	12

Table 4 - GS13 inventory

Geophones L4C	Serial Number	POD
H1	1092	92
H2	811	36
H3	804	53
V1	918	115
V2	1093	18
V3	809	43

Table 5 - L4C inventory

Geophones T240	Serial Number	POD
1	117	15
2	121	501
3	123	3

Table 6 - T240 inventory

Test result:

Passed: X

Failed: ___

Waived : ___

▪ **Step 4 - Electronics Inventory**

Write down in the table below all serial numbers all the electronic equipment:

Hardware	Ligo reference	S/N
Interface Chassis Pod 1	D1002432	S1102228
Interface Chassis Pod 2	D1002433	S1102230
Interface Chassis Pod 3	D1002434	S1102229
Anti-aliasing Chassis	D1002693	S1103404
Anti-aliasing Chassis	D1002693	S1103405
Anti-image Chassis	D1002693	S1103402
Binary Input Chassis	D1001726	S1101284
	D1001726	S1101280
Binary Output Chassis	D1001728	S1101319
T240 Interface Pod 1	D1002694	S1103177
T240 Interface Pod 2	D1002694	S1103181
T240 Interface Pod 3	D1002694	S1103180
Anti-image Chassis	D1000305	S1103502
Coil driver Pod 1	D0902744	S1103564
Coil driver Pod 2	D0902744	S1103563
Coil driver Pod 3	D0902744	S1103356

Table 7 - Electronic equipment

Note: The electronic rack used to test BSC2 (unit #3) is the BSC8 electronic rack.

Test result: Passed: X Failed: ___ Waived : ___

▪ **Step 5 - Check level of Stage 0 after top-bottom plate assembly**

Note: This test has not been performed

Test result: Passed: ___ Failed: ___ Waived : X

▪ **Step 6 - Check gaps under the blade posts**

Test result: Passed: X Failed: ___ Waived : ___

▪ **Step 7 - Blade post shim thickness**

This table shows the shims thickness installed under the lockers.

Stage 0-1		Stage 1-2	
Lockers	Shim thickness (mil)	Lockers	Shim thickness (mil)
Corner 1	121	Corner 1	121
Corner 2	114	Corner 2	133
Corner 3	117	Corner 3	125

Table 8 - Shims thickness

Acceptance criteria: Both D0901805 Stage 0-1 Locker Shims & D0902551 Stage 1-2 Locker Shims goes from .110” up to .130” with an increment of .001”.

Test result: Passed: X Failed: ___ Waived : ___

▪ **Step 8 - Blade 0-1 post launch angle**

This test has not been performed on LLO Unit 2.

Test result: Passed: ___ Failed: ___ Waived : X

▪ **Step 9 - Gap checks on actuators**

Test result: Passed: X Failed: ___ Waived : ___

▪ **Step 10 - Mass budget**

Note: The initial version (V1) of the blade spacers was used. Consequently, the additional payload is expected to be lower than design due to the “relative overall softness” of the ISI.

The figure below presents the location of the masses on both stages. Two vibration absorbers were installed in corner 1 and 2 vibration absorbers were installed in corner 3. Masses on stage 2 are resting on Viton pads.




Figure 1: Masses distribution

Stage 1:

The stage 1 payload is reported in the table below:

Stage 1		
Location	Weight (lb)	Weight (Kg)
C1-1		0.0
C1-2	30	13.6
C2-1		0.0
C2-2	7.5	3.4
C3-1		0.0
C3-2	30	13.6
Total	67.5	30.6

Table 9 - Payload Stage 1

Nominal payload on stage 1: 109Kg – 240lb

Additional payload on stage 1 is 70.9 kg (172lb) less than expected.

Nominal mass of stage 1=916Kg - 2019lb

Stage 2:

The stage 2 payload is reported in the table below:

Mass Type	Quantity	Weight	Unit	Weight (lb)
D972213	3	610	lb	1830
D0972215	1	233	lb	233
D071200 - type 1	3	1.1	lb	3.3
D071200 - type 2	6	2.2	lb	13.2
D071200 - type 3	8	4.5	lb	36
D071200 - type 4	9	7.9	lb	71.1
D071200 - type 5	0	15.6	lb	0
D071200 - type 6	6	27.2	lb	163.2
				2349.8

Table 10 - Payload Stage 2

Nominal payload: 1183.4Kg – 2609lb

Total nominal mass of Stage 2: 2913.9Kg – 6424lb

Additional stage 2 payload is 260lb lighter than the design.

Stage 2 additional payload 10% lighter than nominal => Stage 2 is 9% lighter than nominal.

Payload on stage 0-1 blades is 432lb lighter than design (5%).

Test failure Mitigation: The blade stiffness is lower than design but in good agreements with the mass budget (see section III.7.2). The rigid body mode frequencies should be close from nominal.

Test result: Passed: Failed: X Waived :

- *Step 11 - Lockers adjustment*

Test result: Passed: X Failed: Waived :

▪ *Step 12 – Cables inventory – E1100822*

The final Class A cables have been used for the testing of this Unit.

DCC Number	Description	Length (in)	Serial Number	Location
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106933	ST1 - V2 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106935	ST1 - V3 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106937	ST1 - H3 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106941	ST1 - H2 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106943	ST2 - H2 - ext
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107086	ST1 - V2
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107092	ST1 - H1
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107094	ST1 - H2
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107097	ST1 - V3
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107109	ST1 - V1
D1100150	2-wire, 14awg 2 pins to 3-pin F	40	S1107113	ST1 - H3
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107161	ST2 - V1
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107168	ST2 - V3
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107175	ST2 - V2
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107179	ST2 - H1
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107181	ST2 - H3
D1100151	2-wire, 14awg 2 pins to 3-pin F	60	S1107196	ST2 - H2
D1100152	25-pin F-to-25-pin F	110	S1107242	ST1 - T240 - C1
D1100152	25-pin F-to-25-pin F	110	S1107250	ST1 - T240 - C3
D1100152	25-pin F-to-25-pin F	110	S1107262	ST1 - T240 - C2
D1100153	25-pin F-to-25-pin F	80	S1107300	ST1 - L4C - C1 - ext
D1100153	25-pin F-to-25-pin F	80	S1107301	ST1 - L4C - C2 - ext
D1100153	25-pin F-to-25-pin F	80	S1107302	ST1 - L4C - C3 - ext
D1100153	25-pin F-to-25-pin F	80	S1107303	ST2 - GS13 - C3 - ext
D1100153	25-pin F-to-25-pin F	80	S1107304	ST2 - GS13 - C1 - ext
D1100153	25-pin F-to-25-pin F	80	S1107306	ST2 - GS13 - C2 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1107019	ST2 - V2 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1107011	ST2 - V1 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1107003	ST2 - H3 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106991	ST2 - H1 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106988	ST1 - V1 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1106987	ST2 - V3 - ext
D1100148	2-wire, 14awg 3-pin M to 3-pin F	80	S1107010	ST1 - H1 - ext
D1100154	25-pin M-to-two 9-pin F straight	48	S1107375	ST1 - L4C - C2
D1100154	25-pin M-to-two 9-pin F straight	48	S1107339	ST1 - L4C - C1
D1100154	25-pin M-to-two 9-pin F straight	48	S1107377	ST1 - L4C - C3
D1100155	25-pin M-to-two 9-pin F straight	120	S1107417	ST2 - GS13 - C2
D1100155	25-pin M-to-two 9-pin F straight	120	S1107401	ST2 - GS13 - C3
D1100155	25-pin M-to-two 9-pin F straight	120	S1107396	ST2 - GS13 - C1

▪ **Step 5 - Sensors Powerspectra**

The geophones powerspectra have been measured and can be found in the SVN:

/seismic/BSC-ISI/H2/BSC2/Data/Figures/Spectra/Undamped/

-

/seismic/BSC-ISI/H2/BSC2/Data/Spectra/Undamped

- LLO_ISI_BSC3_ASD_m_LOC_CPS_T240_L4C_GS13_2012_09_24_205825.mat
- LLO_ISI_BSC3_ASD_m_L4C_GS13_Stage_Tilted_2012_10_01.mat

Stage locked – unlocked

The powerspectra are measured in two different configurations:

- Stage 1 locked – Stage 2 locked
- Stage 1 unlocked – Stage 2 unlocked

seismic/BSC-ISI/H2/BSC2/Data/Spectra/Undamped/

- [LHO_ISI_BSC2_ASD_m_LOC_CPS_T240_L4C_GS13_2012_10_16_153749.mat](#)
- [LHO_ISI_BSC2_ASD_m_LOC_CPS_T240_L4C_GS13_2012_10_18_155138.mat](#)

seismic/BSC-ISI/H2/BSC2/Data/Figures/Spectra/Undamped/

- [LHO_ISI_BSC2_ASD_CT_LOC_CPS_T240_L4C_GS13_2012_10_16_153749.fig](#)
- [LHO_ISI_BSC2_ASD_CT_LOC_CPS_T240_L4C_GS13_2012_10_18_155138.fig](#)
- [LHO_ISI_BSC2_ASD_m_LOC_CPS_T240_L4C_GS13_2012_10_16_153749.fig](#)
- [LHO_ISI_BSC2_ASD_m_LOC_CPS_T240_L4C_GS13_2012_10_18_155138.fig](#)




Figure 2: Spectra Stage 1 Locked Stage 2 Locked




Figure 3: Spectra Stage 1 Unlocked Stage 2 Unlocked

Note: All sensors are working properly. However, the noise floor of the stage CPS in corner 2 is pretty high above 10Hz. It is probably a grounding issue. Consequently, the problem will be assessed once the ISI will in the chamber.

Stage Tilted

The powerspectra are measured when the ISI is unlocked a mass is placed on stage 2 to tilt Stage 1 and Stage 2.

The six configurations are the following in six different configurations:

- Mass placed in the actuator pocket at corner 1
- Mass placed in the pocket under the blade 0-1 at corner 1
- Mass placed in the actuator pocket at corner 2
- Mass placed in the pocket under the blade 0-1 at corner 2
- Mass placed in the actuator pocket at corner 3
- Mass placed in the pocket under the blade 0-1 at corner 3

/seismic/BSC-ISI/H2/BSC2/Data/Spectra/Undamped/

- [LHO ISI BSC2 ASD m L4C GS13 Stage Tilted 2012 10 18.mat](#)

seismic/BSC-ISI/H2/BSC2/Data/Figures/Spectra/Undamped/

- [LHO ISI BSC2 Tilted ASD CT LOC ST1 L4C 2012 10 18.fig](#)
- [LHO ISI BSC2 Tilted ASD CT LOC ST2 GS13 2012 10 18.fig](#)
- [LHO ISI BSC2 Tilted ASD m LOC ST1 L4C 2012 10 18.fig](#)
- [LHO ISI BSC2 Tilted ASD m LOC ST2 GS13 2012 10 18.fig](#)




Figure 4 - ST1 L4C – Tilted




Figure 5 - ST1 GS13 – Tilted

Test result:

Passed: X

Failed:

Waived :

○ *Step 11.2 – Base change matrices from Cartesian to Cartesian*

The static tests results are reported in the SVN at :

/seismic/BSC-ISI/H2/BSC2/Data/Static_Tests/

[LHO ISI BSC2 Offset Cartesian Drive 20121018.mat](#)

		Sensors					
		ST1 - X	ST1 - Y	ST1 - Z	ST1 - RY	ST1 - RY	ST1 - RZ
Actuators	ST1 - X	1501	5	5	-4	2	5
	ST1 - Y	-3	1500	2	-6	21	-8
	ST1 - Z	-4	7	641	5	-9	9
	ST1 - RX	27	415	8	2645	-174	9
	ST1 - RY	-386	29	2	164	2641	-3
	ST1 - RZ	4	-5	-2	-21	-2	2870

Table 17 - Static test Cartesian drive – Cartesian to local – Stage 1

		Sensors					
		ST2 - X	ST2 - Y	ST2 - Z	ST2 - RY	ST2 - RY	ST2 - RZ
Actuators	ST2 - X	1218	-5	-4	3	15	28
	ST2 - Y	0	1242	6	-17	5	3
	ST2 - Z	-4	1	966	-19	11	6
	ST2 - RX	-57	263	-22	3459	292	7
	ST2 - RY	-263	-46	3	-282	3488	-7
	ST2 - RZ	57	16	-8	32	-17	2249

Table 18 - Static test Cartesian drive – Cartesian to local – Stage 2

Acceptance criteria:

- Main couplings readout must be positive
- Comparison with the reference tables:
 - Main coupling differences mustn't exceed 200 counts
 - Cross coupling differences mustn't exceed 50 counts

Test result:

Passed: X

Failed: __

Waived : __

▪ **Step 12 - Linearity test**

The “Linearity test” was performed twice (rearranging the cables). The second time, all corners seemed to respond similarly.

The linearity test data can be found in the SVN at:

- /seismic/BSC-ISI/H2/BSC2/Data/Linearity_Test/
- [LHO ISI BSC2 Linearity Test 2012 10 11.mat](#)
- [LHO ISI BSC2 Linearity test 20121018.mat](#)

The linearity test figures can be found in the SVN at:

- /seismic/BSC-ISI/H2/BSC2/Data/Figures/Linearity_Test/
- [LHO ISI BSC2 Linearity test 20121011.fig](#)
- [LHO ISI BSC2 Linearity test 20121018.fig](#)




Figure 6 - Linearity Test

Slope – Offset:

		Slope	Offset	Average slope	Variation from average(%)	
Stage 1	ST1 - H1	0.538	-374	0.5370	0.19	
	ST1 - H2	0.535	-752		-0.37	
	ST1 - H3	0.538	-1695		0.19	
Stage 2	ST1 - V1	0.425	-1281	0.4277	-0.62	
	ST1 - V2	0.430	-160		0.55	
	ST1 - V3	0.428	-374		0.08	
	ST2 - H1	0.313	1048		0.3080	1.62
	ST2 - H2	0.298	-862			-3.25
	ST2 - H3	0.313	-366			1.62
Stage 2	ST2 - V1	0.382	1416	0.3797	0.61	
	ST2 - V2	0.373	1303		-1.76	
	ST2 - V3	0.384	370		1.14	

Table 19 - Slopes and offset of the triplet Actuators - BSC-ISI – Sensors

		Slope	Offset	Average slope	Variation from average(%)	
Stage 1	ST1 - H1	0.539	-177	0.5380	0.44	
	ST1 - H2	0.536	-856		-0.24	
	ST1 - H3	0.539	-1667		0.37	
Stage 2	ST1 - V1	0.428	1225	0.4289	0.17	
	ST1 - V2	0.430	-595		0.56	
	ST1 - V3	0.428	-2601		0.11	
	ST2 - H1	0.315	1230		0.3095	2.25
	ST2 - H2	0.301	942			-2.29
	ST2 - H3	0.313	-1643			1.51
Stage 2	ST2 - V1	0.382	11842	0.3797	0.71	
	ST2 - V2	0.373	4597		-1.65	
	ST2 - V3	0.383	-6160		0.98	

Table 20 - Slopes and offset of the triplet Actuators - BSC-ISI – Sensors

Acceptance criteria:

- Horizontal and vertical slopes of the triplet actuators x BSC-ISI x sensors: Average slope +/- 2.5%

Test result:

Passed: X

Failed:

Waived :

▪ **Step 13 – Transfer functions – Local to Local**

Note: two vibration absorbers were installed in corner 1 and 2 vibration absorbers were installed in corner 3. No TMDs were installed on the stage 0-1 blades.

Data files measurement of local to local transfer functions in SVN at:

seismic/BSC-ISI/H2/BSC2/Data/Transfer_Functions/Measurements/Undamped/

- LHO_ISI_BSC2_Data_L2L_10mHz_100mHz_ST1_ST2_20121016-203156.mat
- LHO_ISI_BSC2_Data_L2L_100mHz_700mHz_ST1_ST2_20121015-233530.mat
- LHO_ISI_BSC2_Data_L2L_700mHz_10Hz_ST1_ST2_20121016-045827.mat
- LHO_ISI_BSC2_Data_L2L_10Hz_100Hz_ST1_ST2_20121015-200821.mat
- LHO_ISI_BSC2_Data_L2L_100Hz_500Hz_ST1_ST2_20121016-184636.mat
- LHO_ISI_BSC2_Data_L2L_500Hz_1000Hz_ST1_ST2_20121016-172146.mat

Script file for processing and plotting local to local transfer functions in SVN at:

/seisvn/seismic/BSC-ISI/H2/BSC2/Scripts/Control_Scripts

- Step_1_TF_L2L_10mHz_1000Hz_LLO_ISI_BSC2.m

Figures of local to local transfer functions (Main couplings) in SVN at:

/seismic/BSC-ISI/H2/BSC2/Data/Figures/Transfer_Functions/Measurements/Undamped/

- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST1_ACT_to_ST1_CPS_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST1_ACT_to_ST1_L4C_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST1_ACT_to_ST1_T240_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST1_ACT_to_ST2_CPS_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST1_ACT_to_ST2_GS13_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST2_ACT_to_ST1_L4C_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST2_ACT_to_ST1_T240_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST2_ACT_to_ST2_CPS_2012_10_16.fig](#)
- [LHO_ISI_BSC2_TF_L2L_Raw_from_ST2_ACT_to_ST2_GS13_2012_10_16.fig](#)

Measured of local to local transfer functions in the SVN at:

/svncommon/seisvn/seismic/BSC-ISI/H2/BSC2/Data/Transfer_Functions/Simulations/Undamped

[LHO_ISI_BSC2_TF_L2L_Raw_2012_10_16.mat](#)

Note 1: The transfer functions are measured from the Output filter bank (excitation variable) to the input (IN1) of the input filter bank. The transfer functions presented below are raw transfer functions without any electronic compensation of the sensor electronic. The actuator and the coil driver electronic compensation are introduced in these transfer functions.

Note 2: The L4Cs are out of phase (should be -90 before 1Hz). A minus sign is added in the calibration filters that convert count to nm/s.

Note 3: The first resonance of the test stand can be seen at 19.6Hz on Stage 1 CPS.

Note 4: The first resonance of the structure observed on stage 1 by the L4C is around 220Hz.

Note 5: There is a poor coherence on the GS13 transfer functions. It can be explained by the weak drive of the fine actuators. Moreover, the stage 2 of the ISI is strongly excited by the fans of the clean rooms. These two factors strongly affect the quality of the measurements.

Note 6: Some saturation of the T240s during the measurements explains the “wobbles” in the transfer function in the [700mHz; 10Hz] frequency band.

Note 7: On the ST1 CPS transfer functions, resonances seen by V1 and V3 seem to be slightly higher than resonances in the V2 direction ([100Hz; 200Hz] frequency band).

Note 8: On the ST1 L4C transfer functions, resonances seen by V2 seem to be slightly higher than resonances in the other vertical directions.




Figure 7: TF L2L Raw - ST1 Act to ST1 CPS




Figure 8: TF L2L Raw - ST1 Act to ST1 L4C




Figure 9: TF L2L Raw - ST2 Act to ST2 CPS




Figure 10: TF L2L Raw - ST2 Act to ST2 GS13

Comparison between the BSC2 and BSC8

BSC2 and BSC8 transfer functions are compared in similar conditions.

- BSC2: High test stand – 4 Vibration absorbers on stage 1 – No TMDs – Stage 2 dummy payload resting on Viton pads
- BSC8: High test stand – No Vibration absorbers on stage 1 – No TMDs – Stage 2 dummy payload not resting on Viton pads

Comparison between the transfer functions of BSC8 and BSC2 can be found in the SVN at: seismic/BSC-ISI/H2/BSC2/Data/Figures/Transfer_Functions/Comparisons/L2L/

- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST1 ACT H to ST1 CPS H 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST1 ACT H to ST1 L4C H 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST1 ACT V to ST1 CPS V 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST1 ACT V to ST1 L4C V 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST2 ACT H to ST2 CPS H 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST2 ACT H to ST2 GS13 H 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST2 ACT V to ST2 CPS V 20110722 vs 20121016.fig](#)
- [LHO ISI BSC8 vs BSC2 Comparison TF L2L ST2 ACT V to ST2 GS13 V 20110722 vs 20121016.fig](#)

Note 1: The rigid body mode of BSC2 and BSC8 are at the same frequencies

Note 2: BSC2 and BSC8 transfer functions were measured with two different sample rates

Note 3:

- Stage 1 L4C TF Horizontal are similar
- Difference in the Stage 1 L4C TF Vertical are visible in the [200;300]Hz frequency band

- Most of the stage 2 resonances are reduced by the addition of Viton pads under the keel masses
- Stage 2 GS12 Horizontal TFs are similar except for H2. The resonances seen between [700;800]Hz will be less visible in the Cartesian basis

Note 4: The phase difference in the ST2-GS13 transfer functions is probably coming from the masses installed on Viton on the top of stage 2.




Figure 11 – Comparison BSC6 vs BSC2 – ST1 ACT Horizontal – ST1 L4C Horizontal




Figure 12 - Comparison BSC6 vs BSC2 – ST1 ACT Vertical – ST1 L4C Vertical




Figure 13 -- Comparison BSC6 vs BSC2 – ST2 ACT Horizontal – ST2 GS13 Horizontal




Figure 14 - Comparison BSC6 vs BSC2 – ST2 ACT Vertical – ST2 GS13 Vertical

Test result:

Passed: X

Failed:

Waived :




Figure 15 – Transfer functions in the Cartesian basis – ST1 CPS




Figure 16 - Transfer functions in the Cartesian basis – ST1 T240




Figure 17 - Transfer functions in the Cartesian basis – ST1 L4C




Figure 18 - Transfer functions in the Cartesian basis – ST1 T240

IV. BSC-ISI testing Summary

This is the third “aLigo BSC-ISI” tested at LHO. The testing procedure document E1000483-v5 was used. Tests were done during in October 2012.

The LHO ISI-BSC2 is validated per the tests presented in this report. All results are posted on the SVN at:

<https://svn.ligo.caltech.edu/svn/seismic/BSC-ISI/H2/BSC2/Data>

FAILED AND WAIVED TESTS

1- List of tests that failed/waived and won't be redone

- **Step II.10 – Mass budget** – The mass of the payload is slightly lower than the design
- **Step III.9 – Spring constant** – The blades are slightly softer than the design. However, the blade softness and the payload are in good agreements. It doesn't have any effect on the rigid body modes of the ISI.

2- List of tests that failed/waived, that need to be re-done during phase 2

3- List of tests skipped that won't be performed because not feasible during phase II (i.e. stage 0 leveling)

- **Step II.5** – Check level of Stage 0 after top-bottom plate assembly
- **Step II.8** – Blade 0-1 Post Launch Angle – No need for this test, the budget mass looks good and we already reposition the Blades after noticing a gap between the Blade and its Spacer on Stage 0-1 (see comment on Step 9 – Vertical Spring Constant).

4- List of tests skipped that we won't do because they are not essential (i.e. redundant with another test)

- **Step III.3 – Measure the Sensor gap** - This test was not performed. The sensor gaps have not been measured. These sensors have already been checked at LASTI. Moreover, risks of scratching the target are so high that we preferred not performing this test. In the future, this test will be removed from the testing procedure.
- **Step III.8 – Vertical sensor calibration** - The test is not realized in a proper way to evaluate accurately the calibration of the vertical CPS.

5- Lists of tests skipped that needs to be done during phase II.

- **Step III.14 – Symmetrization – Calibration**
- **Step III.16 – Transfer functions – Cartesian to Cartesian - Simulations**
- **Step III.17 – Lower Zero Moment Plan**
- **Step III.18.1 – Damping Loops – Stage 2**
- **Step III.18.2 – Damping Loops – Stage 1**
- **Step III.20 – Isolation loops**