

LIGO Laboratory / LIGO Scientific Collaboration

LIGO- E1100307

*LIGO*January 31th, 2013

**aLIGO BSC-ISI Unit 4, Pre-integration Testing report,
Phase I (post-assembly)**

E1100307 – V2

Adrien Le Roux, Celine Ramet

Distribution of this document:
Advanced LIGO Project

This is an internal working note
of the LIGO Laboratory

California Institute of Technology
LIGO Project – MS 18-34
1200 E. California Blvd.
Pasadena, CA 91125
Phone (626) 395-2129
Fax (626) 304-9834
E-mail: info@ligo.caltech.edu

LIGO Hanford Observatory
P.O. Box 1970
Mail Stop S9-02
Richland WA 99352
Phone 509-372-8106
Fax 509-372-8137

Massachusetts Institute of Technology
LIGO Project – NW22-295
185 Albany St
Cambridge, MA 02139
Phone (617) 253-4824
Fax (617) 253-7014
E-mail: info@ligo.mit.edu

LIGO Livingston Observatory
P.O. Box 940
Livingston, LA 70754
Phone 225-686-3100
Fax 225-686-7189

Table of contents:

- Introduction..... 4
- I. Pre-Assembly Testing..... 5
 - Step 1 - CPS Test and calibration – E1100369..... 5
 - Step 2 - GS13 – Inspection/Assembly – E1000058 – E1100740 6
 - Step 3 - L4C – Inspection/Assembly – E1000136 – E1100740 8
 - Step 4 - T240 – Inspection/Assembly - E1100326 – E1100740..... 11
 - Step 5 - Actuators - T0900564 - T1100234 – E1100741..... 14
- II. Tests to be performed during assembly 15
 - Step 1 - Test stand level 15
 - Step 2 - Actuators Inventory 15
 - Step 3 - Sensors Inventory 15
 - Step 4 - Electronics Inventory..... 17
 - Step 5 - Check level of Stage 0 after top-bottom plate assembly 18
 - Step 6 - Check gaps under the blade posts..... 18
 - Step 7 - Blade post shim thickness 18
 - Step 8 - Blade 0-1 post launch angle 19
 - Step 9 - Gap checks on actuators 19
 - Step 10 - Mass budget..... 20
 - Step 11 - Lockers adjustment..... 24
 - Step 12 – Cables inventory – E1100822..... 25
 - Step 13 - Cable routing 25
- III. Tests to perform after assembly..... 26
 - Step 1- Geophones pressure readout..... 26
 - Step 2- Set up sensors gap – Locked vs unlocked position 27
 - Step 3 - Measure the Sensor gap..... 28
 - Step 4- Performance of the limiters 28
 - Step 4.1 - Test N°1 - Push “in the general coordinates Z/RZ” 28
 - Step 4.2 - Test N°2 – Push “locally” 29
 - Step 5 - Sensors Powespectra 29
 - Step 6 - Coil Driver, cabling and resistance check 34
 - Step 7- Actuators Sign and range of motion (Local drive)..... 35
 - Step 7.1 - Actuators sign..... 35
 - Step 7.2 - Range of motion - Local drive..... 35
 - Step 8 - Vertical Sensor Calibration 36
 - Step 9 - Vertical Spring Constant 37
 - Step 10 - Static Testing (Tests in the local basis) 39
 - Step 11- Static Testing - In the general coordinate basis (Static test - CPS)..... 42
 - Step 11.1 – Change of basis matrices from Cartesian to Local 42
 - Step 11.2 – Base change matrices from Cartesian to Cartesian..... 44
 - Step 12 - Linearity test..... 46
 - Step 13 – Transfer functions – Local to Local..... 49
 - Step 14 - Symmetrization – Calibration..... 59
 - Step 15 – Change of base – Cartesian to Local - Simulations 59
 - Step 16- Transfer functions - Cartesian to Cartesian - Measurements 59
 - Step 17 - Lower Zero Moment Plan 59



- Step 17.1 - Stage 1 - LZMP 59
- Step 17.2 - Stage 2 - LZMP 59
- Step 18- Damping Loops – Transfer function – Simulations 59
- Step 18.1 - Damping Loops – Stage 2 59
- Step 18.2 - Damping Loops – Stage 1 59
- Step 19- Damping Loops – Powerspectra..... 59
- Step 20- Isolation Loops – for one unit per site..... 62
- IV. BSC-ISI testing Summary..... 62

Introduction

The BSC-ISI testing is performed in three phases:

- 1) BSC-ISI, Pre-integration Testing, Phase I (post-assembly)
- 2) BSC-ISI, Pre-integration Testing, Phase II: Tests done after Transport (and possible storage), during mating phase with Suspensions, before insertion.
- 3) BSC-ISI, Integration Phase Testing: Procedure and results related to the commissioning in the chamber.

This document presents the series of tests (Phase I) performed on the ISI-BSC4 (ITMX) in the High Bay before its move to the X-end (Test stand). These tests were done in January 2013.

This is the fourth “aLigo BSC-ISI” built and tested with the “aLigo electronic” at the LLO site. The testing procedure document E1000486-v3 was used.

All results are posted on the SVN at:

<https://svn.ligo.caltech.edu/svn/seismic/BSC-ISI/X2/Data/BSC4/>

The following type of document can be found in the SVN:

- Excel spreadsheet (.xls)
- Data location
- Figures location
- Masses distribution scheme (ppt)

▪ **Step 2 - GS13 – Inspection/Assembly – E1000058 – E1100740**

GS13 are tested and podded at LLO.

The list of installed sensors used for testing (phase I) are reported in step II.3.

All the data related to GS-13 post podding testing can be found in the SVN at :
 /svn/seismic/Common/Data/aLIGO_GS13_TestData/PostMod_TestResults_PDFs




Figure 1: Huddle Test Transfer Function of the Horizontal GS-13 SN 836, 851 & 866 after aLIGO modifications




Figure 2: Huddle Test Transfer Function of the Vertical GS-13 SN 729, 732 & 748 after aLIGO modifications




Figure 3: Driven Transfer Function of the Vertical GS-13 SN 729, 732 & 748 after aLIGO modifications

E1000058 and E1100740 spreadsheets provide the status of each individual GS-13 at LLO site for HAM-ISI and BSC-ISI and the installation location of the geophones.

Test result: Passed: X Failed: ___ Waived : ___

▪ **Step 3 - L4C – Inspection/Assembly – E1000136 – E1100740**

L4C are tested and podded at LLO. The list of installed sensors used for testing (phase I) are reported in step II.3.

All the data related to L4C post podding testing can be found in the SVN at :
/svn/seismic/Common/Data/aLIGO_L4C_TestData/TestResults_PDFs/




Figure 4: Huddle Test Transfer Function of the Horizontal L4-C SN 945, 969 & 1100




Figure 5: Huddle Test Transfer Function of the Vertical L4-C SN 933, 1075 & 1088

Step 4 - T240 – Inspection/Assembly - E1100326 – E1100740

T240 are tested and podded at LLO. We haven't had to replace the T240s on this Unit, and these are the ones with the new Voltage Regulator, it seems that they are working fine and keep the pressure sensor from dying. The list of installed sensors used for testing (phase I) are reported in step II.3.

All the data related to T240 post podding testing can be found in the SVN at : seismic/Common/Data/aLIGO_T240_TestData/AsReceived_TestResults_PDFs.




Figure 6: Huddle Test Transfer Function of the X, Y & Z axis of the T240 SN 106




Figure 7: Huddle Test Transfer Function of the X, Y & Z axis of the T240 SN 130




Figure 8: Huddle Test Transfer Function of the X, Y & Z axis of the T240 SN 145

E1100326 and E1100740 spreadsheets provide the status of each individual T240 at LLO site for BSC-ISI and the installation location of the geophones.

Test result: Passed: X Failed: Waived :

CPS Stage 1-2	CPS S/N	ADE board serial #
H1	13457	12522
H2	13437	12510
H3	12944	12524
V1	13453	12585
V2	13526	12570
V3	13451	12543

Geophones GS13	Serial Number	POD
H1	866	44
H2	851	63
H3	836	78
V1	729	66
V2	748	73
V3	732	74

Table 3 - GS13 inventory

Geophones L4C	Serial Number	POD
H1	969	12
H2	1100	84
H3	945	108
V1	933	140
V2	1075	59
V3	1088	95

Table 4 - L4C inventory

▪ *Step 10 - Mass budget*

The figure below presents the location of the masses on both stages.




Figure 9: Masses distribution

Stage 1:

Stage 1		
Location	Weight (lb)	Weight (Kg)
C1-1	0	0.00
C1-2	15	6.80
C1-3	34.22	15.52
C2-1	0	0.00
C2-2	0	0.00
C2-3	22.86	10.37
C3-1	0	0.00
C3-2	0	0.00
C3-3	32.22	14.61
Total	104.3	47.31

Table 8 - Payload Stage 1

Nominal payload: 108.9Kg – 240lb
 Added masses are 61Kg – 135lb lighter than expected.
 Total mass of stage 1=924Kg - 2037lb

Stage 2:

12/18/2012	D972213	D972215	D0901075		D071200							lbs	kgs
			5 kg	10 kg	00	01	02	03	04	05	06		
	610	230	11	22	0.6	1.1	2.2	4.5	7.9	15.6	27.2		
A	1											610	276.69
B	1											610	276.69
C	1											610	276.69
D		2										460	208.65
E-1												0	0.00
E-2												0	0.00
E-3												0	0.00
F1								1			2	90.1	40.87
F2						1			1		2	94.6	42.91
F3					1		1				1	72.8	33.02
Stage 2	3	2	0	0		1	1	1	1		5	2547.5	1155.53

Table 9 - Payload Stage 2

Nominal payload: 1183.4Kg – 2609lb

The added masses is 27.9Kg – 61.5lbs lighter than expected.

Total nominal mass of Stage 2: 2913.9Kg – 6424lb

Error on the nominal overall mass of stage 2: 27.9/2913.9=0.96%

Summary:

Unit 4				
	Plan	7/18/2012	% diff from Plan	Mass Diff from Plan
Stage 1	108.86	47.31	-56.54	-61.55
Stage 2	1183.42	1155.53	-2.36	-27.90
Total	1292.28	1202.84		



LLO Unit 1, 2 & 3 Results:

		Unit 1				
	Plan	Original	3/1/2012	3/9/2012	% Diff from Plan	Mass Diff from Plan
Stage 1	108.86	148.10	19.50	36.29	-66.67	-72.57
Stage 2	1183.42	989.42	1089.07	1096.83	-7.32	-86.59

		Unit 2		
	Plan	6/12/2012	% diff from Plan	Mass Diff from Plan
Stage 1	108.86	60.06	-44.83	-48.81
Stage 2	1183.42	1071.93	-9.42	-111.49

		Unit 3		
	Plan	8/13/2012	% diff from Plan	Mass Diff from Plan
Stage 1	108.86	39.46	-63.75	-69.40
Stage 2	1183.42	1161.33	-1.87	-10.66

LLO Unit 4 is the second one to use these Silver Plated Eastwood Bolts for the Spring Blades and the first Unit to use the new version of the Angled Spacers for Stage 0-1 Blades; we can see the benefits of these two changes especially on Stage 2! See [E1300057](#) for more details.

Previous Units Results:

	Plan	LHO Unit 1	LHO Unit 2	LLO Unit 1	LLO Unit 2	LLO Unit 3	Avg (4 1st Units)	STD	LLO Unit 4
Stage 1	108.86	35.6	58.6	36.29	60.06	39.46	46.00	10.97	47.31
Stage 2	1183.42	1082.4	1059.5	1096.83	1071.93	1161.33	1094.40	35.64	1155.53
Stage 1	130.10	-24.75	23.86	-23.29	26.95	-16.59	-2.76	% of Diff/LLO Unit 4	
Stage 2	2.41	-6.33	-8.31	-5.08	-7.23	0.50	-5.29		

Note: This Unit is the second one to use these Silver Plated Eastwood Bolts for the Spring Blades and the first Unit to use the new version of the Angled Spacers for Stage 0-1. Since the Silver Plating allows a better friction with the Nitronic of the Barrel Nuts, we decided to go back to the initial torque value for these bolts: 110 ft.lbs.

By comparing LLO Unit 4 to LLO Unit 3, we can see the effects of the new angled spacers for the Stage 0-1 Blades: we have a slightly better mass budget on Stage 1 and almost no changes on Stage 2. The mass budget on Stage 1 is still very light compared to the original plan, but if we compare it with the Previous Units built at LHO & LLO, we can see that this Unit is in the general tendency:

▪ **Step 12 – Cables inventory – E1100822**

The final Class A cables have been used for the testing of this Unit.

	Type of Cable	Corner 1	Corner 2	Corner 3
St 0-1 V Actuators	Pigtail	D1100150 – S1107074	D1100151 – S1107172	D1100151 – S1107210
	Extension	D1100148 – S1107057	D1100148 – S1106974	D1100148 – S1106959
St 0-1 H Actuators	Pigtail	D1100150 – S1107111	D1100151 – S1107176	D1100151 – S1107195
	Extension	D1100148 – S1107058	D1100148 – S1106964	D1100148 – S1107055
St 1-2 V Actuators	Pigtail	D1100150 – S1107137	D1100150 – S1107122	D1100151 – S1107191
	Extension	D1100148 – S1106952	D1100148 – S1107059	D1100148 – S1106973
St 1-2 H Actuators	Pigtail	D1100150 – S1107123	D1100150 – S1107076	D1100151 – S1107189
	Extension	D1100148 – S1106968	D1100148 – S1107000	D1100148 – S1106963
LAC	Pigtail	D1100154 – S1107365	D1100154 – S1107368	D1100155 – S1107404
	Extension	D1100152 – S1107257	D1100153 – S1107273	D1100153 – S1107276
GS-13	Pigtail	D1100154 – S1107358	D1100155 – S1107383	D1100155 – S1107406
	Extension	D1100153 – S1107281	D1100153 – S1107271	D1100153 – S1107270
T240		D1100152 – S1107233	D1100153 – S1107272	D1100153 – S1107274

Note: Some changes might occur later in the cabling.

Test result: Passed: X Failed: ___ Waived: ___

▪ **Step 13 - Cable routing**

The final Class A cables have been used for the testing of this Unit.

The cabling has been done following [E1101027 aLIGO BSC-ISI Cable Routing Manual](#).

Test result: Passed: X Failed: ___ Waived : ___

▪ *Step 2- Set up sensors gap – Locked vs unlocked position*

During this step, sensors gap are adjusted. This step considers that the lockers have been finely setup during assembly.

May-2012

Sensors	Table locked		Table unlocked		Difference locked - unlocked	
	Offset (Mean)	Std deviation	Offset (Mean)	Std deviation	Offset (Mean)	mil
ST1 - H1	-119.37	15.008	-733.13	50.415	613.76	0.73
ST1 - H2	-277.82	14.101	-208.96	29.449	-68.86	-0.08
ST1 - H3	-224.65	15.81	-513.31	43.301	288.66	0.34
ST1 - V1	-194.16	20.377	-641.79	66.417	447.63	0.53
ST1 - V2	-85.145	21.912	1.7822	47.457	-86.93	-0.10
ST1 - V3	271.76	24.126	-1293.2	54.045	1564.96	1.86
ST2 - H1	1093.8	42.521	2991.7	64.122	-1897.90	-0.56
ST2 - H2	132.34	47.741	-309.12	52.909	441.46	0.13
ST2 - H3	-1244.6	51.017	1940	33.704	-3184.60	-0.95
ST2 - V1	-178.92	50.288	-1510.9	163.33	1331.98	0.40
ST2 - V2	56.767	34.039	-2345	120.28	2401.77	0.71
ST2 - V3	-226.7	47.272	1228.9	149.56	-1455.60	-0.43

Table 10 - Capacitive position sensors readout after gap set-up

Acceptance criteria:

- In the locked position, all mean values must be lower than 400 counts for stage 1 CPS and 1600 counts for stage 2 CPS (a bit less than .0005”).
- In the locked position, all standard deviations below 25 counts for stage 1, 100 counts for stage 2
- Absolute values of the difference between the unlocked and the locked table must be below:
 - Stage 1**
 - 1600 cts for horizontal sensors (~0.002”)
 - 1600 cts for vertical sensors (~0.002”)
 - Stage 2**
 - 6500 cts for horizontal sensors (~0.002”)
 - 6500 cts for vertical sensors (~0.002”)
- Considering the acceptance criteria of step 2, all mean values must be lower than
 - Stage 1**
 - 2000 cts for horizontal sensors (~0.0025”)
 - 2000 cts for vertical sensors (~0.0025”)
 - Stage 2**
 - 8000 cts for horizontal sensors (~0.0025”)
 - 8000 cts for vertical sensors (~0.0025”)

Test result: Passed: X Failed: ___ Waived : ___

▪ *Step 3 - Measure the Sensor gap*

Test Failure mitigation:

This test was not performed. The sensor gaps have not been measured. These sensors have already been tested at LASTI. Moreover, risks of scratching the target are so high that we preferred not performing this test. In the future, this test will be removed from the testing procedure.

Test result: Passed: Failed: Waived : X

Step 4- Performance of the limiters

○ *Step 4.1 - Test N°1 - Push “in the general coordinates Z/RZ”*

Sensors	CPS read out		Calculated after calibration	
	"-Z" (Counts)	"+Z" (Counts)	"-Z" (mil)	"+Z" (mil)
ST1 - V1 - ST2 LCK	-17116.0	15810.0	-20.4	18.8
ST1 - V2 - ST2 LCK	-15398.0	16816.0	-18.3	20.0
ST1 - V3 - ST2 LCK	-15987.0	15027.0	-19.0	17.9
ST2 - V1 - ST1 LCK	-32768.0	32767.0	-9.8	9.8
ST2 - V2 - ST1 LCK	-32768.0	32767.0	-9.8	9.8
ST2 - V3 - ST1 LCK	-32768.0	32767.0	-9.8	9.8

Sensors	CPS read out		Calculated after calibration	
	"-RZ" (Counts)	"+RZ" (Counts)	"-RZ" (mil)	"+RZ" (mil)
ST1 - H1 - ST2 LCK	14961.0	-15253.0	17.8	-18.2
ST1 - H2 - ST2 LCK	15460.0	-16374.0	18.4	-19.5
ST1 - H3 - ST2 LCK	16175.0	-15284.0	19.3	-18.2
ST2 - H1 - ST1 LCK	-26732.0	25631.0	-8.0	7.6
ST2 - H2 - ST1 LCK	-25449.0	29416.0	-7.6	8.8
ST2 - H3 - ST1 LCK	-29918.0	25839.0	-8.9	7.7

Test result: Passed: X Failed: Waived :

Stage locked – unlocked

The powerspectra are measured in four different configurations:

- Stage 1 locked – Stage 2 locked
- Stage 1 unlocked – Stage 2 locked
- Stage 1 locked – Stage 2 unlocked
- Stage 1 unlocked – Stage 2 unlocked

The series of plots below present calibrated powerspectra:

- The de-whitening filters are suppressed






Figure 10: Spectra Stage 1 Locked Stage 2 Locked



Measurement length: 2525s
Sample window: 50s
Overlap: 50%
Frequency resolution: 20mHz
Averages: 100
Measurement start (GPS): 1042319100

Figure 11: Spectra Stage 1 Unlocked Stage 2 Locked



Measurement length: 2525s
Sample window: 50s
Overlap: 50%
Frequency resolution: 20mHz
Averages: 100
Measurement start (GPS): 1042305425

Figure 12: Spectra Stage 1 Locked Stage 2 Unlocked






Figure 13: Spectra Stage 1 Unlocked Stage 2 Unlocked

Stage Tilted

The powerspectra are measured when the ISI is unlocked a mass is placed on stage 2 to tilt Stage 1 and Stage 2.

The six configurations are the following in six different configurations:

- Mass placed in the actuator pocket at corner 1
- Mass placed in the pocket under the blade 0-1 at corner 1
- Mass placed in the actuator pocket at corner 2
- Mass placed in the pocket under the blade 0-1 at corner 2
- Mass placed in the actuator pocket at corner 3
- Mass placed in the pocket under the blade 0-1 at corner 3



- *Step 7- Actuators Sign and range of motion (Local drive)*
 - *Step 7.1 - Actuators sign*

Test result: Passed: X Failed: Waived :

- *Step 7.2 - Range of motion - Local drive*

In this step, range of motion of the two stages is checked when applying a local drive (30000 counts) on actuators.

Sensor readout (counts)	Negative drive	no drive	Positive drive	Amplitude count	mil
ST1 - H1	-16121	-691	16163	32284	38
ST1 - H2	-16208	-183	16045	32253	38
ST1 - H3	-16621	-425	16231	32852	39
ST1 - V1	-15216	-425	14413	29629	35
ST1 - V2	-13483	1393	16302	29785	35
ST1 - V3	-16274	-1279	13711	29985	36
ST2 - H1	-7143.4	2994	13106	20249	6
ST2 - H2	-10449	-407	9648.5	20098	6
ST2 - H3	-8075.3	1990	12039	20114	6
ST2 - V1	-13510	-1476	10560	24070	7
ST2 - V2	-15044	-2686	9621	24665	7
ST2 - V3	-10964	1246	13361	24325	7

Table 12 - Range of motion - Local drive

Acceptance criteria:

- Amplitude must be at least 32000 counts (+/-0.02") for H Stage 1 CPS
- Amplitude must be at least 29000 counts (~0.010") for V Stage 1 CPS
- Amplitude must be at least 19000 counts (+/-0.02") for H Stage 2 CPS
- Amplitude must be at least 23000 counts (~0.010") for V Stage 2 CPS
- Signs of actuators drive and sensors read out have to be the same

Note: The motion of the platform can be computed. For a 30000 counts drive in the +Z direction, the platform should move by 12.6 mil on Stage 1 and 3.6mil on Stage 2.

In the Cartesian basis, the platform should move (calculation) by:

Stage 1 - Platform move for 32K counts drive: 12.63 mil
 Stage 2 - Platform move for 32K counts drive: 3.59 mil

Test result: Passed: X Failed: Waived :

▪ **Step 9 - Vertical Spring Constant**

This test is realized by loading the ISI when one stage is locked and using the capacitive position sensors as reference.

The stiffness measurements of the spring are reported in the tables below. The nominal blade stiffness are:

- Stage 1: 1241lb/in
- Stage 2: 1465lb/in

Blade Stage 0-1

Stage 2 Locked & Stage 1 Unlocked. Stage 1 is loaded with 3 x 10Kg masses and the measurements are repeated three times (by rotating the masses).

	No load	Load 15 Kg	Load 30Kg	Diff 1	Diff 2
V1	-171.84	0.00	-15333.00	171.84	-15161.16
V2	1562.90	0.00	-13389.33	-1562.90	-14952.23
V3	-916.36	0.00	-15787.67	916.36	-14871.31

-14994.9 count
 -17.85107143 mil
 -1233.899702 lb/in
 0.572143263 %

The blades from stage 0 to stage 1 are too soft by 0.57%.

Blade Stage 1-2

Stage 1 Locked & Stage 2 Unlocked. Stage 2 is loaded with 3 x 5Kg masses and the measurements are repeated three times (by rotating the masses).

	No load	Load	Diff
V1	-271.77	-26255.00	25983.23
V2	-1889.80	-27340.67	25450.87
V3	2486.20	-23418.67	25904.87

25779.65 count
 7.67 mil
 1422.874879 lb/in
 2.875434856 %

The blades from stage 1 to stage 2 are too soft by 2.88%.

Note:

A dirty assembly was built at LASTI for fit-check and testing purpose before the first assembly at LHO & LLO. During balancing, the total added mass on top of stage 2 to simulate the payload was far from nominal. Investigations on the blades stiffness showed an extra softness of the blade of both stages. But the mass deduction to compensate this extra softness didn't explain the difference with the nominal payload. In order to be closer to the nominal payload, the angles of the blade spacers were corrected (correction equivalent to +253lb on stage 0-1 blade and +507lb on stage 1-2 blade). These discrepancies between the initial design and assembly can be explained by:

- Inaccuracy in Solidworks estimation. It might underestimate masses of actual components (metal parts, hardware, instruments...)
- Measurement errors of the blade stiffness
- Machining errors (launch angles, assembly stack up...)
- Extra compliance due to the stages deformation

After these first results, a second version of D1100570 Stage 0-1 Angled Blades Spacer has been issued in order to 25 lbs per corner to the ISI (total correction of $253+75=328$ lbs on Stage 0-1 and 507 lbs on Stage 1-2).

This is the fourth Unit built at LLO, but the first one using the new version of the Angled Spacers for the Stage 0-1 Blades and the second one to use Silver Plated Eastwood SHCS to clamp the Spring Blade which allows a better friction coefficient and thus for the same torque value more clamping force than with the previous Stainless Eastwood Bolts. Since our first Unit, we also use oversized .5015" dowel pins, with the Blade brought as far back as possible to guarantee repeatability.

The very good results on the Mass Budget and on this Vertical Spring Constant Test show us that switching from the Stainless to the Silver Plated Bolts was the right decision, and that the new version of the angled spacers makes the mass budget a little bit better on Stage 1!

Facts:

- Nominal load on Stage 0-1 blades is 8240 lb (per initial design estimation)
- -0.57% of 8240 lb is -47 lbs.
- +328 lb are compensated per ST1 - launch angle correction (E1100284, line 9 & D1100570-V2)
- So we should be at $+328-111.24= 217$ lb over nominal (98kg).

But in reality, we are 89 kg too light, so we have $89 + 98 = 187$ kg unexplained!

But we have to keep in mind that every blade is different (see E1300057) so we will have more information as soon as we have the mass budget for BSC Unit 5.

Test result:Passed: X Failed: Waived :

▪ **Step 10 - Static Testing (Tests in the local basis)**

The table below shows the main and the cross-coupling when the actuators are driven in the local basis:

The static tests results are reported in the SVN at :

/seismic/BSC-ISI/X2/BSC4/Data/Static_Tests/

- LLO_ISI_BSC4_Offset_Local_Drive_20130114.mat

		Sensors					
		ST1 - H1	ST1 - H2	ST1 - H3	ST1 - V1	ST1 - V2	ST1 - V3
Actuators	ST1 - H1	4327.1	1744.5	1745.3	21.859	-12.8	28.735
	ST1 - H2	1762.7	4385.5	1765.7	5.4	-19.8	-7.4
	ST1 - H3	1729.6	1731.1	4264.3	0.1874	1.9792	-1.7
	ST1 - V1	86.428	-144.4	109.14	3486.5	-648.9	-591.6
	ST1 - V2	91.112	15.286	-172.56	-620.5	3480.5	-646.4
	ST1 - V3	-124.88	105.42	56.207	-616.7	-625.4	3531.3

Table 13 - Static test - Local to local - Stage 1

		Sensors											
		ST1 - H1 (min, max)		ST1 - H2 (min, max)		ST1 - H3 (min, max)		ST1 - V1 (min, max)		ST1 - V2 (min, max)		ST1 - V3 (min, max)	
Actuators	ST1 - H1	4333.0	4462.0	1716.0	1780.0	1744.7	1794.0	-15.0	29.0	-23.2	-7.0	-9.3	19.8
	ST1 - H2	1715.0	1770.8	4224.0	4393.3	1705.0	1786.2	-15.5	8.5	-22.5	46.2	-17.3	7.0
	ST1 - H3	1734.0	1748.5	1716.0	1759.7	4246.0	4363.1	-17.8	2.4	-5.3	6.1	8.8	65.4
	ST1 - V1	33.3	79.0	-184.6	-151.6	75.4	119.1	3481.0	3587.0	-665.0	-616.5	-650.4	-588.0
	ST1 - V2	91.0	132.0	34.0	87.0	-178.3	-135.0	-631.0	-597.3	3385.0	3560.3	-695.8	-615.0
	ST1 - V3	-159.1	-102.0	93.0	128.0	31.0	79.1	-664.1	-591.0	-636.0	-570.0	3347.0	3803.9

Table 14: Static Test – Local to Local – Stage 1 Results (min & max) from the previous BSC Units

		Sensors					
		ST2 - H1	ST2 - H2	ST2 - H3	ST2 - V1	ST2 - V2	ST2 - V3
Actuators	ST2 - H1	2388.1	356.61	365.76	-16.3	-60.4	-51.0
	ST2 - H2	354.34	2328.3	371.85	22.239	-37.87	23.671
	ST2 - H3	353.44	345.87	2387.4	-52.6	-30.0	23.763
	ST2 - V1	73.807	107.33	-171.11	2800.1	354.13	-34.4
	ST2 - V2	-190.79	63.926	134.79	-25.78	2968.3	263.97
	ST2 - V3	108.04	-195.3	81.412	362.97	-43.6	2818.9

Table 15 - Static test - Local to local - Stage 2

		Sensors											
		ST2 – H1 (min, max)		ST2 - H2 (min, max)		ST2 - H3 (min, max)		ST2 - V1 (min, max)		ST2 - V2 (min, max)		ST2 - V3 (min, max)	
Actuators	ST1 - H1	2316.0	2439.3	349.5	383.5	337.0	371.0	-33.6	18.0	-77.9	50.1	-64.9	36.0
	ST1 - H2	324.0	366.4	2338.0	2454.7	336.3	373.0	-65.8	27.0	-85.9	62.3	-81.4	51.4
	ST1 - H3	311.0	406.5	341.5	411.4	2313.9	2390.7	-77.1	31.0	-79.7	59.4	-134.8	53.9
	ST1 - V1	65.0	107.4	115.7	142.3	-220.0	-203.1	2769.6	3018.1	213.4	349.0	-106.4	59.5
	ST1 - V2	-244.0	-153.0	50.3	180.9	94.0	127.0	-161.4	15.1	2599.9	2937.0	225.5	400.9
	ST1 - V3	78.5	163.2	-229.2	-152.6	41.0	97.0	250.7	349.0	-140.0	-27.4	2707.1	2960.0

Table 16: Static Test – Local to Local – Stage 2 Results (min & max) from the previous BSC Units

Acceptance criteria:

- Main couplings readout must be positive
- Comparison with the reference tables:
 - o Main coupling differences mustn't exceed 200 counts
 - o Cross coupling differences mustn't exceed 50 counts

Reference tables for acceptance criteria:

		Sensors					
		ST1 - H1	ST1 - H2	ST1 - H3	ST1 - V1	ST1 - V2	ST1 - V3
Actuators	ST1 - H1	4380	1750	1750	0	0	0
	ST1 - H2	1750	4380	1750	0	0	0
	ST1 - H3	1750	1750	4380	0	0	0
	ST1 - V1	50	-170	90	3500	-650	-650
	ST1 - V2	90	50	-170	-650	3500	-650
	ST1 - V3	-170	90	50	-650	-601	3500

Table - Main couplings – Static – Stage 1

		Sensors					
		ST2 - H1	ST2 - H2	ST2 - H3	ST2 - V1	ST2 - V2	ST2 - V3
Actuators	ST2 - H1	2401	360	360	0	0	0
	ST2 - H2	360	2401	360	0	0	0
	ST2 - H3	360	360	2377	0	0	0
	ST2 - V1	80	130	-200	3050	330	0
	ST2 - V2	-200	80	130	0	2950	330
	ST2 - V3	130	-200	80	330	0	2950

Table - Main couplings – Static – Stage 2

Test result:

Passed:

Failed: X

Waived :

- *Step 11- Static Testing - In the general coordinate basis (Static test - CPS)*
 - *Step 11.1 – Change of basis matrices from Cartesian to Local*

The table below shows the main and the cross-coupling when the actuators are driven in the Cartesian basis:

The static tests results are reported in the SVN at :

/seismic/BSC-ISI/X2/BSC4/Data/Static_Tests/

- LLO_ISI_BSC4_Offset_Cartesian_Drive_20130114.mat

		Sensors					
		ST1 - H1	ST1 - H2	ST1 - H3	ST1 - V1	ST1 - V2	ST1 - V3
Actuators	ST1 - X	1716.3	-875	-853.83	21.54	-13	32.784
	ST1 - Y	21.679	1537.7	-1448.5	23.556	-18	-9
	ST1 - Z	4.5122	0	-12.245	760.51	739.72	784.73
	ST1 - RX	-31.002	132.76	-168.25	-2877	2448.7	453.69
	ST1 - RY	-151.78	112.26	94.193	-1117	-1921	3113.4
	ST1 - RZ	3154.2	3207.5	3146.5	33	5.2366	33.838

Table 17 - Static test cartesian drive – Cartesian to local – Stage 1

		Sensors											
		ST1 - H1 (min, max)		ST1 - H2 (min, max)		ST1 - H3 (min, max)		ST1 - V1 (min, max)		ST1 - V2 (min, max)		ST1 - V3 (min, max)	
Actuators	ST1 - X	1733.6	1803.0	-868.3	-839.0	-862.0	-812.0	-26.0	23.0	-17.0	0.4	-26.1	32.5
	ST1 - Y	-32.0	22.0	1493.0	1527.9	-1505.1	-1463.8	-15.6	14.3	-11.4	55.2	-46.6	-14.0
	ST1 - Z	-33.0	8.0	-19.0	0.6	-27.5	16.0	728.5	772.0	709.0	758.3	711.0	824.0
	ST1 - RX	-18.0	40.0	126.0	189.0	-165.0	-137.0	-2937.0	-2877.0	2408.0	2470.0	413.8	486.0
	ST1 - RY	-196.5	-162.0	77.0	111.0	64.2	120.0	-1185.9	-1119.0	-1955.6	-1871.0	2959.0	3310.0
	ST1 - RZ	3162.0	3230.0	3124.0	3229.0	3166.0	3213.3	-20.5	18.0	-32.9	23.0	-27.0	43.6

Table 18 - Static test cartesian drive – Cartesian to local – Stage 1 Results (min & max) from the previous BSC Units

Actuators	Sensors					
	ST2 - H1	ST2 - H2	ST2 - H3	ST2 - V1	ST2 - V2	ST2 - V3
ST2 - X	712.49	-1322	680.53	42.631	-37	16.831
ST2 - Y	1182.3	30.329	-1152.8	51.446	1.9756	52.988
ST2 - Z	26.909	16.105	20.951	1068.2	1034	1104.4
ST2 - RX	-249.56	30.163	271.32	-2362	2480.1	-56
ST2 - RY	168.06	-266	152.93	-1384	-1438	2882.1
ST2 - RZ	1795.8	1792.8	1770.8	45.987	-6	16.588

Table 19 - Static test cartesian drive – Cartesian to local – Stage 2

Actuators	Sensors											
	ST2 - H1 (min, max)		ST2 - H2 (min, max)		ST2 - H3 (min, max)		ST2 - V1 (min, max)		ST2 - V2 (min, max)		ST2 - V3 (min, max)	
ST2 - X	665.0	716.0	-1389.8	-1312.0	653.0	676.0	-63.0	31.0	-79.0	16.0	-77.7	44.0
ST2 - Y	1144.0	1198.0	-52.5	18.0	-1193.9	-1137.0	-89.0	42.0	-136.0	10.0	-103.0	15.0
ST2 - Z	-3.0	19.9	-15.5	12.1	-33.0	14.0	1017.9	1133.0	939.0	1135.0	929.0	1104.0
ST2 - RX	-312.0	-276.0	-25.0	45.5	243.5	288.0	-2572.0	-2398.0	2289.0	2574.0	-153.7	-49.0
ST2 - RY	116.6	200.0	-405.4	-303.0	116.0	189.0	-1595.0	-1474.0	-1513.4	-1123.3	2644.0	2972.0
ST2 - RZ	1738.0	1797.0	1715.0	1822.0	1728.0	1792.0	-101.0	46.0	-122.0	8.0	-66.0	47.5

Table 20 - Static test cartesian drive – Cartesian to local – Stage 2 Results (min & max) from the previous BSC Units

Reference table static test Cartesian to local:

Actuators	Sensors					
	ST1 - H1	ST1 - H2	ST1 - H3	ST1 - V1	ST1 - V2	ST1 - V3
ST1 - X	1800	-820	-820	0	0	0
ST1 - Y	0	1500	-1500	0	0	0
ST1 - Z	0	0	0	772	750	700
ST1 - RX	0	160	-160	-2950	2450	450
ST1 - RY	-200	110	70	-1150	-2000	3050
ST1 - RZ	3200	3200	3200	0	0	0

Table 21 - Reference table - Cartesian to Local - Stage 1

Actuators	Sensors					
	ST2 - H1	ST2 - H2	ST2 - H3	ST2 - V1	ST2 - V2	ST2 - V3
ST2 - X	700	-1350	650	0	0	0
ST2 - Y	1200	0	-1150	0	0	0
ST2 - Z	0	0	0	1100	1100	1100
ST2 - RX	-300	0	300	-2500	2500	-50
ST2 - RY	200	-300	200	-1500	-1400	3000
ST2 - RZ	1800	1800	1800	40	40	40

Table 22 - Reference table - Cartesian to Local - Stage 2

Acceptance criteria:

- Comparison with the reference tables:
 - o Differences mustn't exceed 100 counts

Test result: Passed: Failed: X Waived :

o *Step 11.2 – Base change matrices from Cartesian to Cartesian*

The static tests results are reported in the SVN at :

/seismic/BSC-ISI/X2/Data/BSC4/Static_Tests/

- LLO_ISI_BSC4_Offset_Cartesian_Drive_20130114.mat

		Sensors					
		ST1 - X	ST1 - Y	ST1 - Z	ST1 - RX	ST1 - RY	ST1 - RZ
Actuators	ST1 - X	1714.8	-13	-11.115	-6	9.5858	-3
	ST1 - Y	-29.448	1721.4	-20.893	-7.292	2.3264	43.309
	ST1 - Z	-14.057	-2	738.79	1.4764	14.353	-3
	ST1 - RX	-16.232	351.42	-13.933	2995.3	-2	-18
	ST1 - RY	-376.48	5.3214	9.8948	-9	3012.8	13.484
	ST1 - RZ	-16.835	23.335	7.5343	-5	14.112	3297.8

Table 23 - Static Test - Cartesian to Cartesian – Stage 1

		Sensors											
		ST1 - X (min, max)		ST1 - Y (min, max)		ST1 - Z (min, max)		ST1 - RX (min, max)		ST1 - RY (min, max)		ST1 - RZ (min, max)	
Actuators	ST1 - X	1715.0	1772.1	-12.4	9.0	-7.0	10.9	-13.5	6.0	-20.6	1.0	-2.0	59.0
	ST1 - Y	-9.1	8.7	1720.0	1747.0	-12.4	11.0	-10.0	31.2	-54.3	3.0	-4.0	24.4
	ST1 - Z	-15.0	10.2	-8.7	17.0	729.0	775.0	-25.0	15.0	-27.0	58.0	-14.9	0.0
	ST1 - RX	-6.0	40.8	351.9	380.0	-25.0	7.0	2985.0	3058.0	-23.5	19.0	-15.0	29.0
	ST1 - RY	-387.0	-342.0	-5.6	16.0	-19.7	67.0	-5.0	25.0	2901.0	3188.0	-5.1	12.0
	ST1 - RZ	-18.0	24.0	-4.0	19.0	-27.0	16.0	-6.0	19.5	-2.0	20.0	3276.0	3346.1

Table 24 - Static Test - Cartesian to Cartesian – Stage 1 Results (min & max) from the previous BSC Units

		Sensors					
		ST2 - X	ST2 - Y	ST2 - Z	ST2 - RX	ST2 - RY	ST2 - RZ
Actuators	ST2 - X	1313.1	19.528	48.317	-33	28.469	27.534
	ST2 - Y	-14.554	1342	-53.351	-45	24.789	22.249
	ST2 - Z	-4.6986	5.5833	1048.3	-20	46.518	19.72
	ST2 - RX	-3.6804	4.1961	23.614	4184.2	-46	15.74
	ST2 - RY	-23.98	-7	5.6494	-51	4190.3	22.662
	ST2 - RZ	-14.849	-1	12.875	-39	12.72	2580.6

Table 25 - Static Test - Cartesian to Cartesian – Stage 2

▪ **Step 12 - Linearity test**

The linearity test figure are reported in the SVN at :

/seismic/BSC-ISI/X2/BSC4/Data/Figures/Linearity_Test/

- LLO_ISI_BSC4_Linearity_test_20130114.fig
- LLO_ISI_BSC4_Linearity_test_20130114.pdf




Figure 16 - Linearity Test

Slope – Offset:

		Slope	Offset	Average slope	Variation from average (%)
Stage 1	ST1 - H1	0.61628	-746.6	0.6168	-0.08
	ST1 - H2	0.62607	-331.1		1.51
	ST1 - H3	0.60793	-425.8		-1.43
	ST1 - V1	0.49528	-117.2	0.4994	-0.82
	ST1 - V2	0.49952	1578.7		0.03
	ST1 - V3	0.50328	-782.3		0.79
Stage 2	ST2 - H1	0.34045	2689.9	0.3390	0.42
	ST2 - H2	0.33844	-576.1		-0.17
	ST2 - H3	0.33820	1628.2		-0.24
	ST2 - V1	0.40258	-275.3	0.4083	-1.41
	ST2 - V2	0.41373	-1877.3		1.32
	ST2 - V3	0.40868	2292.8		0.09

Table - Slopes and offset of the triplet Actuators - BSC-ISI - Sensors

▪ **Step 13 – Transfer functions – Local to Local**

Data files measurement of local to local transfer functions in SVN at:

/svncommon/SeiSVN/seismic/BSC-ISI/X2/BSC4/Data/Transfer_Functions/Measurements/Undamped

- LLO_ISI_BSC4_Data_L2L_10mHz_100mHz_ST1_ST2_20130115-022315.mat
- LLO_ISI_BSC4_Data_L2L_100mHz_700mHz_ST1_ST2_20130114-210021.mat
- LLO_ISI_BSC4_Data_L2L_700mHz_10Hz_ST1_ST2_20130115-044616.mat
- LLO_ISI_BSC4_Data_L2L_10Hz_100Hz_ST1_ST2_20130114-182328.mat
- LLO_ISI_BSC4_Data_L2L_100Hz_500Hz_ST1_ST2_20130114-170335.mat
- LLO_ISI_BSC4_Data_L2L_500Hz_1000Hz_ST1_ST2_20130114-155906.mat

Script file for processing and plotting local to local transfer functions in SVN at:

/seisvn/seismic/BSC-ISI/X2/Scripts/Control_Scripts

- Step_1_TF_L2L_10mHz_1000Hz_LLO_ISI_BSC2.m

Figures of local to local transfer functions (Main couplings) in SVN at:

/seisvn/seismic/BSC-ISI/X2/BSC3/Data/Figures/Transfer_Functions/Measurements/Undamped

- LLO_ISI_BSC4_TF_L2L_Raw_from_ST1_ACT_to_ST1_CPS_2013_01_15.fig
- LLO_ISI_BSC4_TF_L2L_Raw_from_ST1_ACT_to_ST1_L4C_2013_01_15.fig
- LLO_ISI_BSC4_TF_L2L_Raw_from_ST2_ACT_to_ST2_CPS_2013_01_15.fig
- LLO_ISI_BSC4_TF_L2L_Raw_from_ST2_ACT_to_ST2_GS13_2013_01_15.fig

Measured of local to local transfer functions in the SVN at:

/svncommon/seisvn/seismic/BSC-ISI/X2/BSC4/Data/Transfer_Functions/Simulations/Undamped

- LLO_ISI_BSC4_TF_L2L_Raw_10mHz_1000Hz_2013_01_15.mat

Note 1: The transfer functions are measured from the Output filter bank (excitation variable) to the input (IN1) of the input filter bank. The transfer functions presented below are raw transfer functions without any electronic compensation of the sensor electronic. The actuator and the coil driver electronic compensation are introduced in these transfer functions.

Note 2: The L4Cs are out of phase (should be -90 before 1Hz). A minus sign is added in the calibration filters that convert count to nm/s.

Note 3: We don't see any resonance of the Test Stand at 16Hz on Stage 1 CPS like LHO did.

Note 4: The first high frequency resonance observed on stage 1 by the L4C is at 216.4Hz. The next resonance is observed at 247.8Hz. The first mode of the blade has been measured at ~250Hz at LASTI, but it shouldn't be the Blades' resonances thanks to the Tuned Mass Dampers (tuned at 253 ± 4 Hz) already installed on Stage 0-1 Blades on this Unit.

Note 5: There is a poor coherence on the GS13 transfer functions. It can be explained by the weak drive of the fine actuators. Moreover, the stage 2 of the ISI is strongly excited by the fans of the clean rooms. These two factors strongly affect the quality of the measurements. Also, we might have an issue with the GS-13 gain because they were saturating a lot, which can also explain the poor quality of the signal.

Note 6: On the ST2-ACT to ST2-GS13 transfer functions, the first high frequency resonances are observed at 120Hz (electric noise, harmonic of 60Hz?) and 141Hz.

BSC-ISI - LLO - BSC4 - January 15th, 2013 - Test Stand HighBay - Undamped




Figure 17: TF L2L Raw - ST1 Act to ST1 CPS

BSC-ISI - LLO - BSC4 - January 15th, 2013 - Test Stand HighBay - Undamped





Figure 18: TF L2L Raw - ST1 Act to ST1 L4C



BSC-ISI - LLO - BSC4 - January 15th, 2013 - Test Stand HighBay - Undamped




Figure 19: TF L2L Raw - ST2 Act to ST2 CPS

BSC-ISI - LLO - BSC4 - January 15th, 2013 - Test Stand HighBay - Undamped





Figure 20: TF L2L Raw - ST2 Act to ST2 GS13



We then also decided to compare these results with previous Units (LHO BSC8 & LLO BSC2).




Figure 21: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8– H ST1 Actuator to ST1 CPS




Figure 22: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – H ST1 Actuator to ST1 L4C




Figure 23: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – V ST1 Actuator to ST1 CPS




Figure 24: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – V ST1 Actuator to ST1 L4C




Figure 25: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – H ST2 Actuator to ST2 CPS




Figure 26: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – H ST2 Actuator to ST2 GS13




Figure 27: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – V ST2 Actuator to ST2 CPS




Figure 28: TF L2L Comparison between LLO BSC 4 & LLO BSC 3 & LHO BSC 8 – V ST2 Actuator to ST2 GS13

By comparing LLO BSC 4 to LHO BSC 8 & LLO BSC 3, we can conclude that BSC 4 is in the general trend of the previous BSCs built!

Test result: Passed: X Failed: Waived :

Due to schedule pressure, it was decided it was reasonable to postpone the following tests. They will be performed during Phase II.

- ***Step 14 - Symmetrization – Calibration***

Not performed

- ***Step 15 – Change of base – Cartesian to Local - Simulations***

Not performed

- ***Step 16- Transfer functions - Cartesian to Cartesian - Measurements***

Not performed

- ***Step 17 - Lower Zero Moment Plan***

- ***Step 17.1 - Stage 1 - LZMP***

Not performed

- ***Step 17.2 - Stage 2 - LZMP***

Not performed

- ***Step 18- Damping Loops – Transfer function – Simulations***

- ***Step 18.1 - Damping Loops – Stage 2***

Not performed

- ***Step 18.2 - Damping Loops – Stage 1***

Not performed

- ***Step 19- Damping Loops – Powerspectra***

Data files measurement of damping Power Spectra in SVN at:

/svncommon/SeiSVN/seismic/BSC-ISI/X2/BSC4/Data/Spectra/Damping

- LLO_ISI_BSC4_ASD_m_L4C_GS13_Undamped_vs_Damping_2013_01_17_142539.mat

Figures of local to local transfer functions (Main couplings) in SVN at:

/seisvn/seismic/BSC-ISI/X2/BSC4/Data/Figures/Spectra/Damping

- LLO_ISI_BSC3_ASD_CT_CART_ST1_L4C_Undamped_vs_Damping_2012_10_04_090654.fig
- LLO_ISI_BSC3_ASD_m_CART_ST1_L4C_Undamped_vs_Damping_2012_10_04_090654.fig
- LLO_ISI_BSC3_ASD_CT_CART_ST2_GS13_Undamped_vs_Damping_2012_10_04_090654.fig
- LLO_ISI_BSC3_ASD_m_CART_ST2_GS13_Undamped_vs_Damping_2012_10_04_090654.fig




Figure 29: LLO ISI BSC4 ASD CT CART Stage 1 L4C Undamped vs Damping




Figure 30: LLO ISI BSC4 ASD m CART Stage 1 L4C Undamped vs Damping




Figure 31: LLO ISI BSC4 ASD CT CART Stage 2 GS 13 Undamped vs Damping




Figure 32: LLO ISI BSC4 ASD m CART Stage 2 GS 13 Undamped vs Damping

Test result:

Passed: X

Failed:

Waived :

- *Step 20- Isolation Loops – for one unit per site*

Not performed

IV. BSC-ISI testing Summary

This is the fourth “aLigo BSC-ISI” tested at LLO. The testing procedure document E1000483-v3 was used. Tests were done during January 2013.

The ISI-BSC4 is waiting for official validation. All results are posted on the SVN at:
<https://svn.ligo.caltech.edu/svn/seismic/BSC-ISI/X2/BSC4/Data>

FAILED AND WAIVED TESTS

- 1- **List of tests that failed/waived and won't be redone**
- 2- **List of tests that failed/waived, that need to be re-done during phase 2**
 - **Step III. 10 & 11 Static Testing** – These tests fail but not by much and looking at the average values obtained from the previous Units, we can conclude that the criteria is maybe a little bit too strong.
- 3- **List of tests skipped that won't be performed because not feasible during phase II (i.e. stage 0 leveling)**
 - **Step II.5** – Check level of Stage 0 after top-bottom plate assembly
 - **Step II.8** – Blade 0-1 Post Launch Angle – No need for this test, the budget mass looks good and we already reposition the Blades after noticing a gap between the Blade and its Spacer on Stage 0-1 (see comment on Step 9 – Vertical Spring Constant).
- 4- **List of tests skipped that we won't do because they are not essential (i.e. redundant with another test)**
 - **Step III.3 – Measure the Sensor gap** - This test was not performed. The sensor gaps have not been measured. These sensors have already been checked at LASTI. Moreover, risks of scratching the target are so high that we preferred not performing this test. In the future, this test will be removed from the testing procedure.
 - **Step III.8 – Vertical sensor calibration** - The test is not realized in a proper way to evaluate accurately the calibration of the vertical CPS.
- 5- **Lists of tests skipped that needs to be done during phase II or III.**
 - **Step III.14 – Symmetrization – Calibration**
 - **Step III.15 – Change of bases – Cartesian to local - Simulations**
 - **Step III.16 – Transfer functions – Cartesian to Cartesian - Simulations**
 - **Step III.17 – Lower Zero Moment Plan**
 - **Step III.18.1 – Damping Loops – Stage 2**
 - **Step III.18.2 – Damping Loops – Stage 1**
 - **Step III.20 – Isolation loops**

The ISI-BSC will be moved from the HighBay to the LVEA test stand as soon as it has been approved.