

*LIGO Laboratory / LIGO Scientific Collaboration*

[LIGO- E1100847](#)

*LIGO*

Mar 18th, 2014

**aLIGO BSC-ISI, Pre-integration Testing report,  
Phase II (before and after cartridge install)**

E1100847– V1

Jim Warner

Distribution of this document:  
Advanced LIGO Project

This is an internal working note  
of the LIGO Laboratory

**California Institute of Technology**  
LIGO Project – MS 18-34  
1200 E. California Blvd.  
Pasadena, CA 91125  
Phone (626) 395-2129  
Fax (626) 304-9834  
E-mail: [info@ligo.caltech.edu](mailto:info@ligo.caltech.edu)

**Massachusetts Institute of Technology**  
LIGO Project – NW22-295  
185 Albany St  
Cambridge, MA 02139  
Phone (617) 253-4824  
Fax (617) 253-7014  
E-mail: [info@ligo.mit.edu](mailto:info@ligo.mit.edu)

**LIGO Hanford Observatory**  
P.O. Box 1970  
Mail Stop S9-02  
Richland WA 99352  
Phone 509-372-8106  
Fax 509-372-8137

**LIGO Livingston Observatory**  
P.O. Box 940  
Livingston, LA 70754  
Phone 225-686-3100  
Fax 225-686-7189

**Table of contents:**

1. Phase IIA.....	3
2. Phase IIB.....	4
1. Hardware changes.....	4
1. CPS – E1100369.....	4
2. GS13 – E1100740.....	4
3. L4C – E1100740.....	4
4. T240 – E1100740.....	4
5. Cables – E1100822.....	4
6. Misc.....	4
2. Electronic Inventory.....	4
3. Models Modifications.....	4
4. Mass distribution.....	5
5. Basic functionalities just after installing the BSC-ISI on the teststand.....	5
1. Pressure sensors.....	5
i. Spectra.....	6
ii. Actuators-cables resistance.....	6
iii. Offsets CPS Unlocked vs locked .....	7
iv. Offset local drive.....	7
v. Offset Cartesian drive.....	7
vi. Range of motion.....	8
vii. Linearity test.....	9
6. Transfer functions.....	9
3. Conclusion Phase II-b.....	13

## ***Introduction***

The BSC-ISI testing is performed in three phases:

- 1) BSC-ISI, Pre-integration Testing, Phase I (post-assembly, in the staging building)
- 2) BSC-ISI, Pre-integration Testing, Phase II: Final tests done before insertion in the chamber
- 3) BSC-ISI, Integration Phase Testing: Procedure and results related to the commissioning in the chamber.

The ISI-BSC2 was moved from the Staging building to the VEA test stand July 2013.

This document presents results of tests (Phase II) performed on the ISI-BSC2 (BS) before installation in the chamber.

All results are posted on the SVN at:

<https://svn.ligo.caltech.edu/svn/seismic/BSC-ISI/H1/BS/>

The following type of document can be found in the SVN:

- Excell spreadsheet (.xls)
- Data location
- Figures location
- Masses distribution scheme (ppt)

### **1. Phase II-A**

Data for the tests on the floor in the LVEA couldn't be found. It may have been overwritten or lost when testing for ITMX was started. All of the required tests were performed once the cartridge was installed in the chamber, so the ISI has been shown to be healthy, regardless. All data in this report is from testing in the chamber.

## **2. Phase II-B**

### **1. Hardware changes**

#### **1. CPS – E1100369**

CPS have not been replaced since phase I testing in the staging building.

#### **2. GS13 – E1100740**

GS13 have not been replaced since phase I testing in the staging building.

#### **3. L4C – E1100740**

L4C have not been replaced since phase I testing in the staging building.

#### **4. T240 – E1100740**

T240 have not been replaced since phase I testing in the staging building.

#### **5. Cables – E1100822**

Further information can be found in E1100822.

#### **6. Misc**

No hardware changes since phase I testing in the staging building.

### **2. Electronic Inventory**

This table reports the electronic equipment used in the LVEA.

### **3. Models Modifications**

The model was updated and recompiled since MEDM screens were modified

**4. Mass distribution**


The Payload for this chamber was not recorded before closing. My recollection was that it was not visually different from other chambers.

**Test result:** Passed:     Failed:     Waived:   X  

**5. Basic functionalities just after installing the BSC-ISI in the chamber**

**1. Pressure sensors**

All pressure sensors are working.



**Table 1 - Geophones Pressure sensors**

**Test result:** Passed:   X   Failed:     Waived:    

**Spectra**

Spectra of the instrument can be found in the SVN at:  
 seismic/BSC-ISI/H1/BS/Data/Spectra/Undamped/

- [H1 ISI BSC2 ASD CT LOC CPS T240 L4C GS13 2020 07 24 4 7:9:.mat](#)

seismic/BSC-ISI/H1/BS/Data/Figures/Spectra/Undamped/

- [H1 ISI BSC2 ASD CT LOC CPS T240 L4C GS13 2020 07 24 4 7:9:.fig](#)




Figure 1 - Spectra inboard instruments - ISI Unlocked

Test result: Passed: X Failed:     Waived:    

**2. Actuators-cables resistance**

Not done. Can be completed outside the chamber if needed.

Test result: Passed:     Failed:     Waived: X



▪ Offsets CPS Unlocked vs locked

Sensors	Table locked		Table unlocked		Difference locked - unlocked	
	Offset (Mean)	Std deviation	Offset (Mean)	Std deviation	Offset (Mean)	mil
ST1 - H1	240	7	58	28	182	.21
ST1 - H2	153	6	-68	18	221	.26
ST1 - H3	-36	5	-93	26	57	.07
ST1 - V1	-710	6	-979	24	269	.32
ST1 - V2	661	10	880	23	219	.25
ST1 - V3	-16	12	-42	23	26	.03
ST2 - H1	302	143	161	40	141	.041
ST2 - H2	-631	129	-684	51	53	.015
ST2 - H3	-243	119	-206	33	37	.011
ST2 - V1	-1532	123	-1539	64	7	.002
ST2 - V2	-579	123	-559	60	20	.006
ST2 - V3	-221	76	-118	66	103	.03

Table 2 - Locked vs Unlocked Position

Test result: Passed: X Failed: \_\_\_ Waived: \_\_\_

i. Offset local drive

Skipped due to time.

Test result: Passed: \_\_\_ Failed: \_\_\_ Waived: X

ii. Offset Cartesian drive

Skipped due to time.

Test result: Passed: \_\_\_ Failed: \_\_\_ Waived: X

**iii. Range of motion**

The range of motion of the table is measured by pushing on the table in a direction collinear to the CPS. The Static tests results can be found on the SVN at:

<https://svn.ligo.caltech.edu/svn/seismic/BSC->

ISI/H1/BS/Data/Static\_Tests/H1\_ISI\_BSC2\_Range\_Of\_Motion\_20130419.mat

<b>Sensor readout (counts)</b>	<b>Negative drive</b>	<b>no drive</b>	<b>Positive drive</b>	<b>Amplitude count</b>	<b>mil</b>
<b>ST1 - H1</b>	-15516	36	16493	<b>32008</b>	<b>38</b>
<b>ST1 - H2</b>	-15211	-43	16907	<b>32118</b>	<b>38</b>
<b>ST1 - H3</b>	-16688	-161	15523	<b>32211</b>	<b>38</b>
<b>ST1 - V1</b>	-14177	-993	12175	<b>26352</b>	<b>31</b>
<b>ST1 - V2</b>	-12396	850	14099	<b>26495</b>	<b>31</b>
<b>ST1 - V3</b>	-13327	-159	13004	<b>26331</b>	<b>31</b>
<b>ST2 - H1</b>	-9618	238	10079	<b>19697</b>	<b>5.9</b>
<b>ST2 - H2</b>	-10400	-696	9003	<b>19403</b>	<b>5.8</b>
<b>ST2 - H3</b>	-9958	-200	9547	<b>19505</b>	<b>5.8</b>
<b>ST2 - V1</b>	-13200	-1581	10005	<b>23205</b>	<b>6.9</b>
<b>ST2 - V2</b>	-12259	-663	10919	<b>23178</b>	<b>6.9</b>
<b>ST2 - V3</b>	-11931	-222	11467	23399	6.9

Table 3 - Range of motion - Actuator drive in the LVEA

Test result:

Passed:  X

Failed:  \_\_\_


Waived:  \_\_\_



**iv. Linearity test**

Measurements data can be found in the SVN at:

SeiSVN/seismic/BSC-ISI/H1/BS/Data/Linearity\_Test/H1\_ISI\_BSC2\_Linearity\_test\_20130417.mat



**Figure 2. Linearity Test**

Test result: Passed:  X  Failed:  \_\_\_  Waived:  \_\_\_

**6. Transfer functions and Comparison with measurements done in the staging building.**

**1. At the end station**

Measurements data can be found in the SVN at:

SeiSVN/seismic/BSC-ISI/H1/BS/Data/Transfer\_Functions/Measurements/Undamped:

- H1\_ISI\_BSC2\_Data\_L2L\_10mHz\_100mHz\_ST1\_ST2\_20130418-205201.mat
- H1\_ISI\_BSC2\_Data\_L2L\_100mHz\_700mHz\_ST1\_ST2\_20130418-161906.mat
- H1\_ISI\_BSC2\_Data\_L2L\_700mHz\_10Hz\_ST1\_ST2\_20130418-223504.mat
- H1\_ISI\_BSC2\_Data\_L2L\_10Hz\_100Hz\_ST1\_ST2\_20130418-134213.mat
- H1\_ISI\_BSC2\_Data\_L2L\_100Hz\_500Hz\_ST1\_ST2\_20130418-122201.mat
- H1\_ISI\_BSC2\_Data\_L2L\_500Hz\_1000Hz\_ST1\_ST2\_20130418-111719.mat

Once the data are processed, they can be found in the SVN at:

[/seismic/BSC-ISI/H1/BS/Data/Transfer\\_Functions/Simulations/Undamped/](#)  
[- H1\\_ISI\\_BS\\_TF\\_L2L\\_Raw\\_2013\\_04\\_18.mat](#)

The transfer functions can be found in the SVN at:

seismic/BSC-ISI/H1/BS/Data/Figures/Transfer\_Functions/Measurements/Undamped/

- [H1 ISI BS TF L2L Raw from ST1 ACT to ST1 CPS 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST1 ACT to ST1 L4C 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST1 ACT to ST1 T240 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST1 ACT to ST2 CPS 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST1 ACT to ST2 GS13 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST2 ACT to ST1 L4C 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST2 ACT to ST1 T240 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST2 ACT to ST2 CPS 2013 04 18.fig](#)
- [H1 ISI BS TF L2L Raw from ST2 ACT to ST2 GS13 2013 04 18.fig](#)




Figure 3 - TF ST1 ACT to ST1 CPS




Figure 2 - TF ST1 ACT to ST1 T240






Figure 3 - TF ST1 ACT to ST1 L4C

BSC-ISI - LHO - BSC2 - April 18<sup>th</sup>, 2013 - Cartridge - BS damped - In Air



**Figure 4 - TF ST2 ACT to ST2 CPS**

BSC-ISI - LHO - BSC2 - April 18<sup>th</sup>, 2013 - Cartridge - BS damped - In Air



**Figure 5 - TF ST2 ACT to ST2 GS13**

Test result:

Passed:  X

Failed:    

Waived:

