



Auxiliary Optical Systems - AOS

Stray Light Control and Viewports – SLC

Eric Gustafson, Lisa Austin (Lead) and Michael Smith
(Cognizant Optical Engineer)


aLIGO NSF Review
LIGO Hanford Observatory

April 11-13, 2012

LIGO-G1200154-v8




Stray Light Control - SLC




LIGO-G1200154-v8

Stray Light Control Functions

- Control stray light scatter in the interferometer using baffles, beam dumps, and attenuators
- Reduce scattered light displacement noise




Ghost beams





LIGO Stray Light Control Requirements

- Total stray light displacement noise $< 1/10$ Thermal noise (Coatings and suspensions)



LIGO-G1200154-v8



Stray Light Control Design Concept

- Oxidized, polished SS, low BRDF stable surface baffles
- Small, Core Optic wedge angles simplify/consolidate many baffles and beam dumps in the recycling cavities
 - » Cavity Mirror Wedge angles
 - ITM, 0.076 deg vertical wedge angle causes ghost beams to separate from the main beam in the vicinity of PR2 and SR2 for interception with beam dumps
 - BS, 0.074 deg horizontal wedge angle provides the ITMX Hartmann beam in vicinity of SR2
- Suspended baffles reduce scattered light displacement noise for critical scattering paths
 - » Arm Cavity Baffle (ACB), ITM Elliptical Baffle, Manifold/Cryopump Baffle
 - » Output Faraday Isolator
- ACB catches narrow and wide-angle scatter from ITM and ETM
- ACB photodetectors aid initial alignment and measure scattered light from TM
- Mode Cleaner Tube Baffle mitigates recycling cavity scatter and errant beams





Scattered Light Control Development Accomplishments - I

- Measured vibration of suspended Output Faraday Isolator (OFI) and Arm Cavity Baffle (ACB) with eddy current-damping at Caltech and LASTI - meet SLC displacement noise requirement
- Measured the BRDF of oxidized, polished stainless steel baffles and beam dumps for stable, low BRDF surfaces



Mode Cleaner Tube
baffles for recycling
cavities




Arm cavity baffle design mitigates
wide-angle scatter from Test Mass




Scattered Light Control Development Accomplishments – II

- Completed Installations:


Fold Mirror Elliptical Test Plate – BSC8, LHO



Arm Cavity Baffle – BSC8, LHO



Mode Cleaner Tube Baffles, LLO



LIGO-G1200154-v8

OFI in Squeezer test at LHO




Scattered Light Control Development Accomplishments – II


Oxidized stainless steel processing



Air Cavity Baffle in swing back position



Assembly and vibration testing of prototype, suspended Manifold/ Cryopump Baffle at Caltech




OFI
1st article
assembly

LIGO-G1200154-v8




Stray Light Control Development Status

- All designs and drawings are complete
- Completed Final Design Reviews
 - » Arm Cavity Baffle
 - » Mode Cleaner Tube Baffle
 - » Manifold Cryopump Baffle
 - » Signal Recycling Cavity Baffles and Beam Dumps
 - » ITM Elliptical Baffle




SRC - SRM HR Baffle



SRC - SR2 Scraper Baffle

LIGO-G1200154-v8




SRC - HAM Scraper Baffle



Stray Light Control Project Plans and Organization

- Project Plans
 - » Baffles and Beam Dumps for Michelson Integration ready – April 2012
 - » All Baffles and Beam Dumps for aLIGO Installation – complete by November 2012
- Project Organization - Caltech
 - » Team Leader – Lisa Austin
 - » Cognizant Engineer – Michael Smith
 - » Coordinator – Nichole Washington
 - » Suspensions Testing - Virginio Sannibale
 - » Mechanical Designer - Heidi Kelman
 - » Mechanical Designer – Manuel Ruiz
 - » Mechanical Designer – Tim Nguyen





Scattered Light Control LIGO-India Impact

- Arm Cavity Baffle
 - » Two hole baffle option no longer required
 - » Re-evaluation of baffle weight for spring blades
 - » Re-configure ACB in H2-BSC8 for move to H1-BSC1
- Reduced scope
 - » H2 Baffles no longer required – Manifold Flat, Fold Mirror Beam Dumps and Fold Mirror Elliptical
- Manifold Cryopump Baffles will not be provided.



Scattered Light Control Challenges, Risks, and Mitigations

- Delivering SLC in time for the Michelson Integration
 - » On critical path to meet Installation Schedule
- On-time delivery of procurements
 - » Continuous monitoring of manufacturing progress
- No remaining known risks



Stray Light Control Near Term Activities

- Procurements – April 2012
 - » Signal Recycling Cavity Baffles
 - » Manifold Cryopump Baffles
 - » Remaining Arm Cavity Baffles
- Completed Final Design Review – April 2012
 - » Remaining SLC baffles and beam dumps
- Installation Underway
 - » Signal Recycling Cavity Baffles – LLO
 - » Output Faraday Isolator - LLO
 - » Mode Cleaner Tube Baffles - LHO
- Developing installation procedures
- Modifying tooling for installation variations between sites - Done



Viewport Functions

- Provide optical viewports for the passage of optical beams in and out of the vacuum region(s) of the Interferometer.
 - » Optical lever beams
 - » Chamber illumination beams
 - » Video camera beams
 - » Optical beams for interferometer sensing and control
 - » Hartmann Sensor beams
 - » Photon Calibrator beams
 - » Septum Viewports
- Double glass safety viewports for high power beams
- Provide safety covers for all installed viewports




Viewport (VP) Requirements

- Video camera VP—transmit visible light spectrum
- Chamber illumination VP—uncoated viewports
- OpLev VP—635 nm, similar to iLIGO
- Septum Plate (to isolate input and output HAM chambers) VP— similar to eLIGO
- ISC and Hartmann VP—super-polished, low scattering, $< 1/10$ wave , special AR coatings
 - » Hartmann AR coating: 800nm – 1080nm
 - » ISC AR coating: 532nm and 1064nm
- Safety covers to protect viewports during installation and commissioning
- High Power double glass design; High Power, Reducer & Septum Safety covers



Viewport Design Concept

- Reuse iLIGO VP wherever possible
- New O-ring-sealed 6.0 inch VP for Interferometer Sensing and Control, and Hartmann beams
- Wedged Septum VP similar to eLIGO design
- Additional standard catalog VPs needed for new Mode Cleaner Tube VPs
- Double glass for high power VP
- Special AR coatings for Video, ISC, and Hartmann beams



LIGO-G1200154-v8






Viewport Development Accomplishments

- Analyzed VP scattered light for Hartmann beams
- Determined new viewport locations in mode cleaner tubes using ZEMAX beam layout
- Established proper names for all viewports according to LIGO naming convention & created a catalog of VP requirements and part numbers for all subsystems
- Developed specification for 6.0 inch ISC/Hartmann VP
- New – Develop/modify Safety Covers for High Power VPs, Septum VPs, and VPs with flange reducers
- Completed VP Final Design Review
- Implemented over-pressure and leak testing of VPs at LLO & LHO
- Set up testing facility at Caltech for measuring VP coatings

Viewport Development Status

- Drawings and assemblies for custom 6.0 inch VP and Septum VPs - complete
- Final Design Review - complete
- VP Procurements on schedule for installation– complete
- Assembly and Test of LHO custom VP for one arm test – complete
- Assembly of LLO custom VP for SMI – complete
- Over-pressure and leak testing facility at LLO & LHO - complete
- Testing facility at Caltech for measuring VP coatings – complete




LIGO-G1200154-v8

Testing fixtures



Viewport Project Plans and Organization

- Project Plans
 - » On schedule for deployment of three aLIGO IFOs
- Project Organization
 - » Leader – Lisa Austin
 - » Cognizant Optical Engineer – Michael Smith
 - » Coordinator – Nichole Washington – Caltech
 - » Assembly – Daphen Pino - Caltech
 - » Installation Leads –
Thomas Vo – Hanford
Chris Guido– Livingston



LIGO-G1200154-v8



Viewport Challenges, Risks, and Mitigations

- Viewport damage during over pressure testing
 - » Fixture redesigned to eliminate stress to support ring.
- Other VPs mostly catalog items
 - » No known technical or schedule risks



Viewport LIGO-India Impact

- No impact on design, cost or schedule.



AOS SLC Schedule Highlights

Activity ID	Activity Name	Start	Finish	FY2008	FY2009	FY2010	FY2011	FY2012
LIGO LIGO Lab Program - AdvL Current		01-Oct-09 A	17-Sep-12					
LIGO.3 Advanced LIGO Development		01-Oct-09 A	30-Mar-12					
LIGO.3.07 Auxiliary Optics (AOS)		01-Oct-09 A	30-Mar-12					
LIGO.3.07.3 AOS Design		01-Oct-09 A	30-Mar-12					
LIGO.3.07.3.3 AOS Final Design		01-Oct-09 A	30-Mar-12					
LIGO.3.07.3.3.1 AOS Stray Light Control (SLC)		01-Oct-09 A	15-Mar-12					
LIGO.3.07.3.3.9 AOS Viewports		22-Mar-11 A	30-Mar-12					
LIGO.4 Advanced LIGO Project		10-Feb-10 A	17-Sep-12					
LIGO.4.07 Auxiliary Optics Systems (AOS)		10-Feb-10 A	17-Sep-12					
LIGO.4.07.4 AOS Fabrication		10-Feb-10 A	17-Sep-12					
LIGO.4.07.4.1 AOS Stray Light Control Fabrication		10-Feb-10 A	17-Sep-12					
LIGO.4.07.4.1.1 AOS Output Faraday Isolator (OFI) Suspension Assembly		10-Feb-10 A	27-Apr-12					
LIGO.4.07.4.1.2 AOS Baffles & Beam Dumps		14-Feb-11 A	17-Sep-12					
LIGO.4.07.4.A AOS Viewports		10-Jun-11 A	04-Apr-12					

- **SLC Scope of Work – Includes the Output Faraday Isolator, Baffles and Beam Dumps, and Viewports.**
- **Schedule Highlights: All Final Designs were completed as of March 2012. All procurement and assembly are anticipated to be complete in September 2012.**



AOS SLC Critical Path

Activity ID	Activity Name	Predecessors	Successors	Start	Finish	Total Float	Free Float	FY2012
AO-P52010	AOS FAB SLC: RFQ thru Award Manifold/Cryo Baffles/Dumps		AO-A53640	18-Feb-11 A	06-Apr-12	-46	0	
AO-A53620	AOS FAB SLC: L1 Fab/Receive/Deliver AC Baffles & BDs (BSC1,3,4,5)	AO-A52010	AO-A53630, AO-M59790, AO-A53610, AO-P51910, IN-L1-P3545, IN-L1-P3645, IN-L1-P1305, IN-L1-P3930	21-Oct-11 A	15-May-12	-33	34	
AO-F40750D	AOS FAB VP: L1 Ship, C&B, Assemble Viewports SMI Lot 1	AO-F40750B	AO-M59970, IN-L1-P2105, IN-L1-P3930	27-Feb-12 A	23-Mar-12	-58	14	
AO-P52050	AOS FAB SLC: RFQ thru Award Balance of Baffles/Dumps (BDs)	AO-D51540, AO-M40733E	AO-P52060, AO-A53670	16-Mar-12	06-Apr-12	-36	0	
AO-A53650	AOS FAB SLC: H2 Fab/Receive/Deliver Remaining Manifold/Cryo BDs	AO-A52030, AO-A53640	AO-A53660, IN-H2-FI2260, AO-M59810, IN-H2-FI2590	09-Apr-12	14-Sep-12	-24	0	
AO-A53640	AOS FAB SLC: L1 Fab/Receive/Deliver Manifold/Cryo BDs	AO-A52030, AO-P52010	AO-A53660, AO-A53650, AO-M59790, IN-L1-P3800	09-Apr-12	13-Jul-12	-46	0	
AO-A53670	AOS FAB SLC: L1 Fab/Receive/Deliver Balance of BDs	AO-P52050	AO-A53690, AO-A53680, AO-P52070, IN-L1-P3105, IN-L1-P3205, IN-L1-P3444, AO-M59790, IN-L1-P3930	09-Apr-12	24-Apr-12	-36	0	
AO-A53680	AOS FAB SLC: H2 Fab/Receive/Deliver Remaining Balance of BDs	AO-A53670, AO-P52060	AO-A53690, IN-H2-FI2260, IN-H2-FI1175, IN-H2-IF2445, IN-H2-FI2030, IN-H2-FI1105, IN-H2-FI1520, AO-M59790, IN-L1-P3930	25-Apr-12	20-Jun-12	-25	0	

- Manifold Cryopump Baffles were impacted by introduction of Oxidation Process and other design changes.
- Arm Cavity Baffle - L1 lessons learned from BSC 8.
- Viewports - L1 SMI assembly is in process.
- Balance of Beam Dumps Final Design was recently completed.

LIGO-G1200154-v8



AOS SLC Tracking Milestones

Activity ID	Activity Name	Baseline Target Dates	Current Dates (Feb-12)	Schedule Change (Days)	NSF Reporting Dates
AO-M59750	AOS FAB: AOS Production Begins	23-Sep-10	27-Sep-10 A	-4	N/A
AO-M47100	AOS FAB SLC: Stray Light Control Production Begins	1-Oct-10	27-Sep-10 A	4	N/A
AO-M59790	AOS FAB SLC: Stray Light Control Fab Complete L1	2-Mar-12	13-Jul-12	-94	N/A
AO-M59810	AOS FAB SLC: Stray Light Control Fab Complete H2	27-Apr-12	14-Sep-12	-97	N/A
AO-M59820	AOS FAB SLC: Stray Light Control Fab Complete H1	7-Jun-12	14-Sep-12	-70	N/A
AO-M47110	AOS FAB TMS: TransMon Suspension Production Begins	24-May-11	2-May-11 A	16	N/A
AO-M59880	AOS FAB TMS: L1 - TransMon Suspension Fab Complete	21-Jun-12	30-Aug-12	-50	N/A
AO-M59920	AOS FAB TMS: H2 - TransMon Suspension Fab Complete	21-Jun-12	29-Aug-12	-48	N/A
AO-M59960	AOS FAB TMS: H1 - TransMon Suspension Fab Complete	17-Sep-12	21-Nov-12	-49	N/A
AO-M47120	AOS FAB: Initial Alignment (IAS) System Production Begins	26-Jan-11	31-Jan-11 A	-3	N/A
AO-M471XX	AOS FAB: IAS Production Complete - Site 1	7-Oct-11	6-Apr-12	-126	N/A
AO-M471XY	AOS FAB: IAS Production Complete - Site 2	7-Feb-12	6-Apr-12	-42	N/A
AO-M47130	AOS FAB: Optical Lever System Production Begins	23-Sep-10	8-Nov-10 A	22	N/A
AO-M59900	AOS FAB: Optical Lever Sys. Fab Complete	8-Nov-11	3-Jun-13	-397	N/A
AO-M47150	AOS FAB: Viewports Production Begins	18-Jul-11	9-Jun-11 A	27	N/A
AO-M471XZ	AOS FAB: Viewports Production Complete	28-Mar-12	4-Apr-12	-5	N/A
AO-M47160	AOS FAB: TCS Production Begins for Ring Heater (RH)	10-Nov-10	15-Dec-10 A	-23	N/A
AO-M47180	AOS FAB TCS: Production Begins for HWS	9-Nov-11	1-Aug-11 A	56	N/A
AO-M47190	AOS FAB TCS: Production Begins for CO2P In-Vac	1-Mar-11	1-Mar-11 A	0	N/A
AO-M47210	AOS FAB TCS: Production Begins for CO2P In-Air	16-Nov-12	2-Mar-12	183	N/A
AO-M59800	AOS FAB TCS: Thermal Compensation System Complete L1	18-Apr-12	1-Nov-12	-139	N/A
AO-M59830	AOS FAB TCS: Thermal Compensation System Complete H2	6-Jul-12	23-Jan-13	-132	N/A
AO-M59840	AOS FAB TCS: Thermal Compensation System Complete H1	11-Jan-13	8-Mar-13	-40	N/A
AO-M47170	AOS FAB: Photon Calibrator Production Begins	2-Feb-12	21-Feb-12 A	-12	N/A
AO-M59910	AOS FAB: Photon Calibrator Complete	9-May-13	14-May-13	-2	N/A
AO-M50030	AOS: Auxiliary Optics Subsystem Finish	10-Jan-12	3-Jun-13	-373	N/A
	= Completed activity			Schedule Change	
	= NSF Reporting Milestones			Negative indicates later than planned	
	= Schedule slippage of 40 days or more. Requires explanation.			Positive indicates earlier than planned	
	= Schedule slippage resulting in negative total float up to 1 month. Requires explanation.				
	= Schedule slippage resulting in negative total float greater than 1 month. Requires immediate mitigating action.				

- SLC Schedule delays caused by design changes and delayed completion of Final Designs.

LIGO-G1200154-v8



AOS SLC Performance and Variances

Cost Performance to Date: February 2012										
Auxiliary Optics Systems (K\$)	BCWS	BCWP	ACWP	SV	CV	SPI	CPI	BAC	EAC	VAC
4.07.1 AOS - Management	105	105	138	0	-33	1.00	0.76	202	202	0
4.07.1.2 AOS - Fabrication Management	83	83	28	0	55	1.00	0.55	209	209	0
4.07.4 AOS - Fabrication	3,010	3,010	3,186	0	-175	1.00	0.94	4,089	4,089	0
4.07.4.1.1 AOS - Output Faraday Isolator Suspension Assembly	290	282	281	-7	1	0.97	1.00	290	294	(3)
4.07.4.1.2 AOS - Baffles and Beam Dumps	1,099	671	685	-428	-13	0.61	0.98	1,611	1,645	(34)
4.07.4.2.1 AOS - TCS Ring Heater Production	195	167	249	-27	-81	0.86	0.67	195	220	(125)
4.07.4.2.2 AOS - TCS Hartmann wave-front Sensor Production	206	52	81	-154	29	0.25	0.04	301	445	(143)
4.07.4.2.3 AOS - TCS CO2 Projection Laser Production	896	277	261	-619	15	0.31	1.06	1,429	1,380	48
4.07.4.2.4 AOS - TCS Phase Camera & Bulls Eye Sensor Production	0	0	0	0	0	0.00	0.00	55	0	55
4.07.4.5 AOS - Transmission Monitor Suspension Fabrication	778	209	215	-568	-5	0.27	0.97	778	819	(41)
4.07.4.5.1 AOS - Transmission Monitor Sus First Article Procure	69	69	69	0	0	1.00	1.00	69	69	0
4.07.4.5.3 AOS - Transmission Monitor Suspension Procurement	260	86	86	-174	0	0.33	0.00	260	260	0
4.07.4.6 AOS - Initial Alignment System (IAS) Procure/Fab	255	247	263	-7	-16	0.97	0.94	255	278	(23)
4.07.4.7 AOS - Optical Lever System (OptLev) Procure/Fab	1,117	876	834	-240	41	0.78	1.05	1,117	1,115	1
4.07.4.8 AOS - Photon Calibrator Fab	109	0	2	-109	-2	0.00	0.00	1,128	847	281
4.07.4.A AOS - Viewports	720	576	577	-143	0	0.00	0.00	720	722	(2)
Performance Measurement Baseline	9,192	6,710	6,955	(2,476)	(242)	0.73	0.96	12,708	12,694	14
								72.8%	Scheduled Percent complete	
								52.8%	Actual Percent complete	

- **Schedule Variance (SV) is due to delays in completion of Final Designs, First Article rework, design changes, and a material change.**
- **Cost Variance (CV) is not significant or less than 10%.**
- **Estimate At Completion (EAC) all less than 3% of the Budget at Completion (BAC).**



AOS SLC Contingency Adjustments

- **Past Adjustments –**
 - **ACR-110020 Rescheduled Viewport procurements**
 - **ACR-110033 revised the SLC and Viewport schedule due to vendor delays**
 - **ACR-110041 added budget**
 - **\$1,012K to SLC for failed first articles, baffle oxidizing, design changes, external cleaning, tooling, and suspension costs.**
 - **\$136K to Viewports for hardware, clamps, flanges, testing equipment and high power assemblies.**

- **Anticipated Adjustments for Cost and Schedule - None**



Summary of AOS SLC Status

- Working to plan and within the current EAC.
- Efforts being made to expedite deliveries for Install, as needed.
- SLC and Viewports anticipated to complete September 2012.