






Advanced LIGO



Keita KAWABE, LIGO Hanford, Caltech

- Introduction
- Current status
- Future




Introduction


- Why aLIGO
- What is aLIGO

Why aLIGO: iLIGO was not that bad

- S6 (peak, average) NSNS $\sim(21, 16)$ Mpc (H1) and $\sim(20, 14)$ Mpc (L1), took 1yr's worth of data



Strain Sensivities from Initial LIGO






Not bad, yes.
But...

-
- iLIGO needed to depend on luck to detect.
 - We need something much better!



Thus advanced LIGO (aLIGO)



Radiation pressure noise

Shot noise

Initial LIGO


- Quantum noise
- Seismic noise
- Gravity Gradients
- Suspension thermal noise
- Coating Brownian noise
- Coating Thermo-optic noise
- Substrate Brownian noise
- Excess Gas
- Total noise

Standard quantum limit

What is aLIGO

- 10 times lower noise floor
 - x1000 larger astrophysical volume

10x distance, 1000x volume



- 10 times lower noise floor
 - x1000 larger astrophysical volume.
- Will detect events routinely.
 - Tens of detections per year expected.
- Highest priority of the LIGO Laboratory.

We want to open a new window to the universe



Visible light

Gamma

Gravitational Wave!



X-ray





Visible light

radio

IR, UV etc.

Neutrino



LLTA

1600's


Starting 1930' – 60's

Starting 1980's


Starting 2010's

All images wikimedia commons except Gallilei's telescope which is from IMSS Firenze


But how? It's a multi-front attack (simplified view)




Pre-Stabilized Laser



- 2W NPRO master
- 35W medium-power amplifier (used in eLIGO system)
- 180W high power stage
- Pre-modecleaner (PMC)




Quad suspension





- Four-stage pendulum
- Monolithic last stage
- Actuation chain also suspended by the same structure (“reaction masses”)

Quad suspension






Internal Seismic Isolation (ISI) isolates SUS

- TM SUS is attached under ISI
- ISI for TM is two-stage active isolator
- Provides isolation $\sim 0.2\text{Hz}$ and higher.







ISI+SUS is isolated by HEPI


- SUS+ISI mounted on top of Hydraulic External Pre Isolator
- HEPI is connected to ISI via crossbeams and support tubes
- 0.1 Hz to 5 Hz isolation



7 stages of isolation in series



Interferometer Sensing and Control (ISC) upgrade



- Signal recycling
- ALL important beams are detected in-vac on isolated platforms
- Improved lock acquisition
(Arm Length Stabilization, or ALS)
- Improved output mode cleaner, electronics, and everything (really)




Current Status

- aLIGO project overview
- Recent developments

aLIGO project

- This is a project to build aLIGO
- 100% completion means that 2 IFOs are fully locked for two hours, and the 3rd IFO parts are cleaned, assembled and/or stored.
- It doesn't necessarily mean that IFOs are running with good sensitivity (though they could, in principle).
- 205M USD over 2008-2015
- After completion, sensitivity improvement will be covered by LIGO operations, which is out of the scope of aLIGO project

- 183M received out of 205M total.
- 83% completed in terms of actual commitment as of March, 2013.
- 61 months into 80 months total as of now (~73%)



- We're still on track for:
 - Feb 2014, 3rd IFO storage
 - July 2014 L1 acceptance
 - Sept. 2014 for H1 acceptance

Not aLIGO project, but...

- USA sequestration = 13% cut for FY2014-FY2018 operations budget. 233.1M requested VS 202.5M.
 - This is the money used, among others, for bringing the sensitivity up to the design goal.
- Serious blow to the initial plan, still committed to maximize the scientific outcome within this boundary.

- We're still calling it “the 3rd IFO”.
- Strong commitment from India as well as LIGO.
- Increased LIGO ↔ India visits.
- Assembly/storage activities ongoing.
- If you're a LVC or KAGRA member, see <http://dcc.ligo.org/LIGO-G1300221>

- We're still calling it “the 3rd IFO”.
- Strong commitment from India as well as LIGO.
- Increased LIGO ↔ India visits.
- Assembly/storage activities ongoing.
- If you're a LVC or KAGRA member, see <http://dcc.ligo.org/LIGO-G1300221>


- Vacuum leak at LLO
- Mirror coating
- Integration tests
 - High power + IMC test at LLO
 - One arm test at LHO
 - DRMI test at LLO
 - HIFO-Y test at LHO

- Leak opened ca. 2008, $\sim 2.5\text{E-}4$ torr-liter/sec
- True nature was found only recently
- 4 major leaks found (as of mid Apr.) but a leak check effort is ongoing.
- Weld+water+animal residue (mice and/or wasp) seems like a formula for leak development.

- Mirror substrate is polished in two steps
 - Superpolish: 1 Angstrom micro-roughness, within 100nm of the ideal figure
 - Ion beam figuring: Corrects figure while maintaining the micro-roughness.
- This was excellent (0.12nm rms figure error over 160mm diameter)
- But the coating has been problematic (it “distorts” the mirror)

- Finally a good usable **pair** of ETMs was produced by LMA Lyon in collaboration with aLIGO.
- Each is out of spec, but used as a pair at EX and EY, the loss would be in spec (75ppm per surface)
- Periodic pattern coming from planetary action.
 - Scattering effect (mostly into baffle) is being studied.
 - Vigorous modeling effort is ongoing.
- Right now we're using totally-out-of-spec mirrors at LHO, will install good ones for HIFO-X test.

Periodic structure





Integration testing

- Build each subsystem, install, and that's it, isn't it?

Integration testing

- Build each subsystem, install, and that's it, isn't it?
 - No! It's unlike most industrial projects.
- Proof is in the pudding. What if your window frame only accepts 1m X 1.2m +/- 1e-9 m glass panel?
- For some of the subsystems, a stand-alone test is not possible/practical at the level that is ultimately necessary.
 - Accuracy and/or overall noise level: Can you measure TM vibration at 10e-20m/sqrtHz level?
 - Complexity: If your system comprises 100s of sub components, each comprising 100s of sub-sub components, is the testing of each sub-sub component good enough?




Integration testing, continued

- We define some milestones.
- At each milestone, we perform “integration tests” to evaluate if all subsystems involved in the test satisfy the standard that can be tested at that time.
- Installation – Integration – Integration cycles
- Staggered schedule so the sites don't have to repeat the same effort again and again


- High power test of PSL+IMC (done @LLO)
- One arm test (done @LHO)
- DRMI test (being done @LLO)
- HIFO-Y (being done @LHO first)
- HIFO-X (to be done @ LHO)
- Full IFO (to be done @ both sites, LLO first)

Integration Testing Progress So Far, and Future Schedule



- Parallel INS not explicitly on this diagram
- Arrows represent copying
- X axis is not necessarily proportional to time.

- Full power PSL
- Remain locked as long as we'd like (req. 90% duty cycle)
- 86% throughput from PSL to IFO (req. 75%)
- Visibility 97-98% (req. 95%)
- Control BW 60kHz (req. 40k or higher)
- IMC transmission 0.5% RIN (req. 1% or less)




- PSL noise (freq, amp, pointing) larger than expected, some room for improvement
 - Being worked on
- Second ISS with in-vac detector needs re-engineering
 - Updated electronics to be installed
- MC optics absorption (2 of 3) larger than expected (2ppm vs 0.6-0.7)
 - An item for contamination control

- This is the first step for the new lock acquisition scheme called Arm Length Stabilization (ALS)
- We inject doubled 1064nm (i.e. 532nm) light offset-locked to PSL from the end, and lock this green light to the arm.

- In iLIGO lock scheme, sensing matrix was changed dynamically every time one or both of the arms crossed resonance.
- There was roughly 50% chance of success (depending on the carrier or the SB crossing the cavity resonance first) per each crossing, thus $\frac{1}{4}$ chance of successful full lock.
- In real world, this empirically meant 5min down time when lock is lost **IF EVERYTHING ELSE IS PERFECT.**
- And this is without signal recycling.

- In aLIGO, arms are locked first using green light from end stations that are offset-locked to PSL.
- The arms are “slowed down” using the beat signal of green light from the end and frequency-doubled PSL light
- PSL IR light is slowly brought into the arm resonance in a controlled manner


One Arm Test: The first test of ALS and an arm cavity of aLIGO



- Green beam cavity locking: Works
- Basic test of Quad SUS + ISI + HEPI: Works
- Initial alignment procedure: Works
 - Locked 7 days after the arm was opened (very good, benefit of extensive component-level testing)
- Ring heater for thermal compensation: Works
- Some action items and design changes
 - WFS determined unnecessary
 - Additional photo diodes for automation
 - PZT steering determined indispensable

- Both IMC/PSL test and OAT went very well
- Identified things that worked, and things that need further attention
- Helped to finalize the design of some of subsystems
- Very succesful.

HIFO-Y (or HIFO-one arm): Next stage of ALS test




- Being tested at LHO right now.
 - Green beam went into Y arm again last week.
- First test of corner station ALS system
 - Green beam from EY detected at the corner
 - Beat note of EY green and doubled PSL fed back to the laser and TM
 - Red light is slowly brought into resonance.



HIFO-X (or full ALS test): Next-next stage of ALS test


- Next-next stage of LHO testing (late 2013?).
- Two arms are installed.
- PSL-X beat for “common mode” that is used for controlling PSL
- X-Y beat for “differential mode” used for differential length of X and Y.
- Both arms are brought into IR resonance
- **First test of TM vibration that is not limited by frequency noise of the PSL/IMC.**

HIFO-X (or full ALS test)



Dual Recycled Corner Michelson

- Not a full IFO, but a near-final stage of all critical sensing chains necessary for a full IFO.
- Everything except ETMs (and thus ALS)
 - Michelson
 - DC differential phase read out using output mode cleaner
 - Power and signal recycling
- Installation in progress at LLO, test to start in June.





Current status summary

- We're still on track for Jul/2014 (L1) and Sep/2014 (H1) acceptance (i.e. 2hr lock), and 3rd IFO storage.
- Integration tests very successful for far:
 - Providing good FOM for what works and producing action items.
- There are still some risks (not everything was covered in this talk, e.g. contamination, software etc.)
- Each major risk is being investigated by a team of specialists

- At the very least IFOs will have been accepted by the end of aLIGO project (2015).
- Will take some time to bring IFOs to full sensitivity.
- Somewhere along the way, the first GW WILL be detected, possibly together with other projects.
 - Drama, politics, committees, usual mundane things.
- And then what?

- Global network: LIGO USA, Indigo?, VIRGO (talk by Ricci), KAGRA (Kajita), GEO-HF, 3rd generation detector(s) like EGO (Somiya), pulsar timing arrays (Manchester), space based detectors.

Global network







This is already after the aLIGO project is done, but...

- Upgrade?
 - If so, SQZ (demonstrated at H1 and GEO) is a necessity.
 - Other possibilities (again Kentaro's talk).
- And we'll be doing real astronomy together while we keep beating our own sensitivity!


LIGO





Credit: AEI, CCT, LSU



Credit: Chandra X-ray Observatory



Casey Reed, Penn State



NASA/WMAP Science Team

