

<i>Title</i>	<i>Heater Driver Test Procedure</i>
<i>Author</i>	<i>Luis E. Sánchez, Caltech-LIGO</i>
<i>Date</i>	<i>2 February 2017</i>
<i>Hardware Version</i>	<i>PCB D1600454-v1 in Chassis Assembly Drawing D1700493-v1</i>

---

## 1 Overview

This procedure is used to verify proper operation of the Heater Driver Chassis. This chassis operates at voltages of  $\pm 18\text{VDC}$  (that can be increase to a limit of  $\pm 24\text{VDC}$ ); portions of this procedure assume that the person performing the test be familiar with voltage circuit testing, SR785 Dynamic Signal Analyzer and Keithley 2450 Source Meter. **The Test Technician or Engineer MUST be a LIGO approved Qualified Electrical Worker specifically authorized to work on energized equipment.**

**Table 1**

<b>Chassis Serial Number</b>					
<b>Date</b>					
<b>Tested By</b>					
<b>Overall Test Result</b>	<table> <tr> <td>PASS</td><td>FAIL</td></tr> <tr> <td><input type="checkbox"/></td><td><input type="checkbox"/></td></tr> </table>	PASS	FAIL	<input type="checkbox"/>	<input type="checkbox"/>
PASS	FAIL				
<input type="checkbox"/>	<input type="checkbox"/>				

## 2 DC Measurements Section

### 2.1 Power ON

Use power supply to verify that modules are power up by inspecting that front and rear panel led are lightning on after the main power switch is turn on. Remove the positive power rail and check if the led are off in both rear and front panel locations. Connect the positive rail and proceed to remove the negative power rail and verify that the led are off in both the rear and the front panel locations. Record the results in the following table; mark each measurement as Pass or Fail.

**Table 2 Power Rail**

<b>Power Rail(v)</b>	<b>Specified Value</b>	<b>Measured Value</b>	<b>LED</b>	<b>Pass</b>	<b>Fail</b>
$\pm 18\text{v}$ supply ON	$\pm 18\text{v} \pm 0.5\text{v}$		ON	<input type="checkbox"/>	<input type="checkbox"/>
+18V Supply OFF	0v		OFF	<input type="checkbox"/>	<input type="checkbox"/>
-18V Supply OFF	0v		OFF	<input type="checkbox"/>	<input type="checkbox"/>

### 2.2 Quiescent current draw

External to the chassis under test insert a Fluke Multi-meter in series with each power form and measure the power supply current. Record the results in the following table. Mark each measurement as Pass or Fail.

**Table 3 Quiescent Current Draw**


<b>Quiescent Current Draw (mA)</b>	<b>Specified Value</b>	<b>Measured Value</b>	<b>Pass</b>	<b>Fail</b>
+18V Supply	200mA $\pm$ 5mA		<input type="checkbox"/>	<input type="checkbox"/>
-18V Supply	-230mA $\pm$ 5mA		<input type="checkbox"/>	<input type="checkbox"/>

### 2.3 Electronic Fuse, current limit verification

Set Keithley 2450 to verify current limit. During this test unplug the power connection from Marchand PM21 board and Heater driver board. Only Electronic Fuse and Power Protection circuit must be connected to power. Connect the Keithley as the image below.

**Table 4 Electronic Fuse Current Limit Draw**

Quiescent Current Draw (mA)	Specified Value	Measured Value	Pass	Fail
+18V Supply	930mA +/- 5mA		<input type="checkbox"/>	<input type="checkbox"/>
-18V Supply	880mA +/- 5mA		<input type="checkbox"/>	<input type="checkbox"/>



Set-up to measure the current for the short circuit protection characteristic of the Electronic Fuse, using the Keithley 2450. Positive voltage, sourcing current measuring voltage a), and Negative voltage, sourcing current measure voltage b).

## 3 Test Procedure

Attach a 75Ω test load to the Heater Driver output, 4 pin CPC Connector, label as “To SR3 Heater”. Connect Breakout Board – DB9 (D0901868) to “I/V Monitor to ADC” and “From DAC” on chassis. Test as in Table 5, Injecting voltage to “From DAC” pins and Monitoring on “I/V Monitor to ADC” pins.

**Table 5**

Front Panel “From DAC” (Input Voltage)		“I/V Monitor to ADC” (Differential Output Voltage)				Specified Result 1-6 & 3-8	Measured Value 1-6 & 3-8 ±0.2v	Specified Result Voltage Load(75Ω)	Measured Voltage At Load(75Ω) ±0.3v v	Pass	Fail
		+V(volts)		-V(volts)							
Pin	Volts(DC)	Pin	Volts(DC)	Pin	Volts(DC)	Volts(DC)	Volts(DC)	Volts(DC)	Volts(DC)	Test	Test
3-8	1	1-6	+2	3-8	-2	±2		6		<input type="checkbox"/>	<input type="checkbox"/>
3-8	2	1-6	+4	3-8	-4	±4		12		<input type="checkbox"/>	<input type="checkbox"/>
3-8	3	1-6	+6	3-8	-6	±6		18		<input type="checkbox"/>	<input type="checkbox"/>
3-8	4	1-6	+8	3-8	-8	±8		24		<input type="checkbox"/>	<input type="checkbox"/>
3-8	5	1-6	+10	3-8	-10	±10		30		<input type="checkbox"/>	<input type="checkbox"/>

To verify currents, see test on Table 6.

**Table 6**

Front Panel “From DAC” (Input Voltage)		“I/V Monitor to ADC” (Differential Output Current)				Specified Result 2-7 & 4-9	Measured Value 2-7 & 4-9 ±.3v	Specified Result Load (75Ω)	Measured Current At Load(75Ω) ±.02mA	Pass	Fail
		Current Monitor in Volts									
Pin	Volts(DC)	Pin	Volts	Pin	Volts	Volts	Volts(DC)	Amperes	Amperes	Test	Test
3-8	1	2-7	1.5	4-9	-1.5	±1.50		0.08		<input type="checkbox"/>	<input type="checkbox"/>
3-8	2	2-7	3	4-9	-3	±3.0		0.16		<input type="checkbox"/>	<input type="checkbox"/>
3-8	3	2-7	4.5	4-9	-4.5	±4.5		0.24		<input type="checkbox"/>	<input type="checkbox"/>
3-8	4	2-7	6	4-9	-6	±6.0		0.32		<input type="checkbox"/>	<input type="checkbox"/>
3-8	5	2-7	7.5	4-9	-7.5	±7.5		0.40		<input type="checkbox"/>	<input type="checkbox"/>

Set Up the SR785 to take the transfer function from Whitening Filter located in Heater Driver board. For each channel, verify that the transfer function and noise spectra are in conformance with the following data. For the transfer function the input signal need to be injected at pins 1 and 6 of J1 and the relay jumper needs to change to 2-3 position. Remember to set it back when the test is finalized.

**Table 7, Transfer Function with relay jumper on 2-3 position.**

Pins		Predicted at 100Hz		Measure at 100Hz		Pass	Fail
DAC IN	OUT(I/V Mon.)	Gain (dB)	Phase( $^{\circ}$ )	Gain (dB) $\pm 2dB$	Phase( $^{\circ}$ ) $\pm 2^{\circ}$	Test	Test
Pins 1-6	1	48	-1			<input type="checkbox"/>	<input type="checkbox"/>
Pins 1.6	6	48	-1			<input type="checkbox"/>	<input type="checkbox"/>
Pins 1-6	3	48	-1			<input type="checkbox"/>	<input type="checkbox"/>
Pins 1.6	8	48	-1			<input type="checkbox"/>	<input type="checkbox"/>

**Table 8, Noise Predictions with “From DAC” input pins 3 – 8 grounded.**

GND Pins DAC IN	Pins “I / V Monitor to ADC”	Predicted Noise at 100Hz ( $\mu V/\sqrt{Hz}$ )	Measure Noise at 100Hz( $\pm 5\mu V/\sqrt{Hz}$ )	Pass	Fail
1-6	1	27		<input type="checkbox"/>	<input type="checkbox"/>
1-6	6	27		<input type="checkbox"/>	<input type="checkbox"/>
1-6	3	27		<input type="checkbox"/>	<input type="checkbox"/>
1-6	8	27		<input type="checkbox"/>	<input type="checkbox"/>




Figure 1 shows the DB9 (D0901868) breakout board used in this test.



Figure 2 shows the dummy load,  $75\Omega$ , connected to the heater driver output, CPC connector, label as “to SR3 Heater”. Also the breakout board –DB9 (D0901868) is seen connected to the “I/V Monitor to ADC”.




Figure 3 shows the heater driver setup inside the chassis, in this shows the heater driver pcb (D1600454-v1), the power protection circuit (D1101816-v2), the electronic fuse (D1600399-v1), and the Marchand Electronics PM21 dual power amplifier module.




Figure 4 shows the voltage response when the limit has been reached at the positive rail of the Electronic Fuse.




Figure 5 shows the floor noise of the SR785 Dynamic Signal Analyzer and noise from the heater driver (Differential Reading).