
# Virgo status


From O2 to O3 and beyond Focusing on the detector

B. Mours (LAPP-Annecy) for the Virgo Collaboration GWADW - May 12, 2018






# O2 Detector Summary



- ▶ 85 % duty cycle
  - Longest lock segment: 69 hours
- ▶ Mean BNS range: 26.5 Mpc
  - online 25.6 Mpc
- Noise budget
  - Many bumps and line and some extra broadband noise
  - Scattered light, some sensing noise, unknown....



#### From O2 to O3

Comm.

12 months


Comm.

Upgrades

Strategy:

Reserve commissioning time

- Limit the number of upgrades
- Target sensitivity for O3: 60 Mpc
  - Main benefit should come from putting back the monolithic suspension
    - Removing the steel wire thermal noise from noise budget gives a 20 Mpc range increase
  - Theoretical limits: 100 Mpc @13W, no squeezing




Monolithic suspension re-installation

- Vacuum upgrade for dust protection
- AEI squeezer
- High power laser
- Newtonian noise sensors test installation

Comm.

03



 September
 October
 November

 Gen. commissioning
 SDB1/PR
 TCS and input power increase

Post O2 commissioning


SDB1 checks, PR and DET towers baffles installation, SPRB/SWEB suspensions re-tuning


#### Main topics

- Control filters optimization
- ENV: noise injections and noise sources identification
- Interventions in SDBI and PR towers
  - Baffles installed
  - Some MMT optics cleaned/replaced
- SUSP: GIPC now fully engaged
- ISC:AA in full bandwidth using quadrants (@ 56 MHz)
- TCS: DAS optimized and tested
- ISYS: ITF input power increased to 26.5 W












- Tests with 14, 17, 20 and 26 W
  - O2: I3W at the ITF input
- No major issues
  - Done in a few days
  - No need to use TCS
  - Sideband gain reduced
    - ▶ Compatible with simulation
  - But coupling to the ITF degrades
    - ▶ 1.57 power increase in the arms instead of 1.9
    - No time spent on beam matching
  - No parametric instabilities (so far...)
    - Modes density smaller than in LIGO and grouped

# Laser power increase










### Main results of the post-O2 commissioning

- ▶ Limited BNS range improvement
  - Maximum value reached around 30 Mpc
  - Mean O2 range: 26.5 Mpc
- Glitch rate much reduced








# Vacuum chamber upgrades




1) Venting circuit separation



82) Scroll pump substitution






#### Laser improvement

- ▶ 70 W amplifier replaced by a 100 W
  - Max input power in the ITF: around 50 W
  - 100 W fiber laser tests ongoing at Nice
- New pre-mode cleaner
- External Injection Bench "suspended"








## Squeezing

- ▶ AEI squeezer box installed at Virgo
  - About 10 dB of squeezing
- Integration
  - Extra clean air, cabling, DAQ,...
  - Telescope, auto-alignment alignment
  - Lock main squeezer laser to AdV laser
  - Detection system modifications
    - New Faraday isolator, extra flange...
- Maximum possible HF gain: 4.7 dB


	Loss Mechanism	Present (O2)	Expected (O3)
L1	Imperfect OPO Escape Efficiency	1 %	1%
L2	Pick-off on SDB1	1.5 %	1.5%
L3	Detection Faraday	2×7%	$2 \times 1.5\%$
L4	Injection Faradays	4×1.5 %	4×1.5 %
L5	OMC throughput	3.9%	3.9%
L6	ITF to OMC losses	5.4%	4.5 %
L7	Mode matching squeez-OMC	8%	8%
L8	Photodiodes QE	7%	1%
L9	Arms cavity losses	2.7%	2.7%
L10	Other	6%	6%
	TOTAL	44%	32%






## Newtonian Array

- Array of 38+9 sensors installed at west end building
  - Two weeks of data collected in Jan-Febio-18
  - Analysis on going
  - Sound NN as large as seismic NN
    - ▶ High sound level in Virgo building











#### The first recovery after North Arm upgrade


- Two weeks of recovery; manage to lock the full ITF
- Sensitivity reached a few hours after the full relock: 19 Mpc
  - New violins modes well visible
    - ▶ Losses larger than nominal but should not limit the O3 sensitivity



- ▶ Took a bit longer than expected...
  - Arm valves reopen on March 19
  - Other activities than just ITF recovery
- ▶ Back in "low noise 3" on May 2<sup>nd</sup>,
  - First BNS range: 19 Mpc
- ▶ Reach up to 25 Mpc
  - Preliminary calibration
- First noise budget
  - Touching steel wires thermal noise?
- Back to commissioning
  - No major shutdown scheduled before Q3


## The second recovery







#### Commissioning toward O3

- Commissioning
  - Usual noises/glitches reduction
  - Robustness
  - Commissioning of the squeezer
  - Power increase
    - Max power for O3: 50W
      - □ Not critical for the BNS range...
- Engineering Runs
  - Once per month over a weekend
  - Long ER priori O3
- ▶ O3 start early 2019; aligned with LIGO











## Beyond O3: AdV+

- Could we do better than AdV?
- ▶ AdV+ proposed to the EGO council last December
- A two steps approach:
  - For O4: Frequency dependent squeezing
    - Add a filtering cavity
  - For O5: Reduce the coating thermal noise
    - Larger beam: Four test masses or just the end test masses?
    - Improved coating
- More on the AdV challenges in Jerome's talks

### AdV+ phase I

- Complete the AdV program:
  - 200 W laser; I25W at the ITF input
  - Signal recycling → I20 Mpc
- Frequency dependent squeezing
  - →150 Mpc
  - New filtering cavity






Newtonian noise cancelation → I 60 Mpc

#### AdV+ Phase 2


- Larger mirrors
  - Diameter: 550 mm, thickness: 200 mm, mass: 105 kg (?)
  - Scenario I: ETM-only → 200 Mpc
  - Scenario 2: full upgrade → 230 Mpc
- Coating improvements
  - If factor three reduction in CTN:
    - Scenario I: ETM-only → 260 Mpc
    - Scenario 2: full upgrade → 300 Mpc
- Many challenges and activities
  - Grand Coater upgrade
  - Vacuum, infrastructure
  - Payloads and superattenuators
  - Aberration control





#### AdV+: Tentative timeline

Five year plan for observational runs, commissioning and upgrades



Note: duration of O4 has not been decided at this moment

#### Summary

- Main AdV upgrades for O3 are done
- Back to commissioning mode
  - Several months of commissioning foreseen
- AdV+ plan setup for after O3
  - Cost: up to 30 ME for full test masses upgrade
  - A very challenging phase II ...
  - Hope to get some approval during the June EGO council meeting