O3 October Commissioning Break Update

Keita Kawabe, Brian O'Reilly, Alessio Rocchi, Matteo Tacca

October 2019 Commissioning Break


- Oct. 1 2019 15:00:00 UTC to Nov. 1 2019 15:00:00 UTC.
- Both LHO and LLO are done with installations essential for the rest of O3 except for LHO's wind fence.
 - We've been pumping down the "corner" volume, but we plan to open the gate valve today to start relocking the detectors.
 - Retuning, noise mitigation, calibration etc. until we resume the observation in November.
 - No delays except H1 wind fence which won't be available until mid-Nov. Impact on the observation projected to be less than 8 hours.
- Virgo already locked their instrument with higher power stably, fine tuning is ongoing.

LIGO Commissioning break

Category	Specific task(s)	Motivation
In-vac scattering mitigation (both)	H1: In-vac window swap. L1: More in-vac baffles.	Smaller scattered light noise.
Squeezing improvement (H1 only)	Replace damaged fiber.	Smaller shot noise via more pump power into in-vac squeezer.
Vacuum (both)	L1: X-arm accumulation test, identify (and fix) the leak. H1: Swap aging equipments.	Reduced residual gas effect for L1. Risk mitigation for H1.
Environment (H1 only)	Wind fence.	Better duty factor, possibly reduced glitches, when windy.
Seismic isolation (H1 only)	Thermal control of tilt sensor.	More robust control.

There are other "me too" activities that are not essential for O3b (but may be essential for O4).


L1 Scattering Mitigation: A focus in this commissioning break.





View from ETM






ETM transmission monitor before (left), after (right)






H1 scattering mitigation: Targeting corner station

H1 scattering in the input chain causing nonstationary 48Hz bump (mitigated/eliminated during O3a).





New H1 in-vac viewport with a larger incident angle in the output chain


H1: Swapping degraded in-vac fiber for SQZ system




G1902055-v2, OpenLVEM, 24 Oct




During the break: L1 EX spot absorbers in-situ pictures











H1 Wind Fence

- Wind has an impact on duty factor as well as noise at Hanford.
- "Baseball net"-type wind mitigation.
- Installation ongoing.
- Not operational until mid-Nov.
 - Minimal (projected less than 8 hours) of impact on the run.







Virgo commissioning break


Category	Specific task(s)	Motivation
Increase Power to 25W	Retune all the interferometer at higher power (ISC working points and loops, TCS working points, etc)	Small increase in the sensitivity, learn how to handle higher power
Scattered light investigation	Cure the scattered light on the external input optics bench (known issue). Tests along in-vacuum beam path to better identify the source of scattering (and possibly cure them)	Better sensitivity Better control signals
"Flat noise" investigation	Sensitivity in the mid-frequency range is limited by the unknown "flat noise". Test the hypothesis that it's RFAM for sidebands picked up and imprinted on the carrier by ISS as per <u>Virgo log 47080</u> .	Better sensitivity

October Virgo commissioning: selected results



Input power increase: $18W \rightarrow 26W$


- TCS & AA new working points + mode matching to be done for the 2 arms
- ITF not yet relocked in low noise ... but a matter of days?



October Virgo commissioning: selected results




Sensitivity for best BNS range of the day (48 Mpc)



Lots of ENV noise studies on going:

50 Hz side bands:


- On Oct 7th found one origin on the TCS benches: CINOGY IR laser beam profilers are generating EM noise.
- Other suspected origin: 48Hz mechanical resonance in susp. F7



October Virgo commissioning: selected results




Sensitivity for best BNS range of the day (48 Mpc)




70-150 Hz: control noises bad subtraction & mysterious flat noise

 MICH, PRCL control noise are subtracted in h(t) but current hrec online subtraction algorithm requires to have uncorrelated input signals.



Relocked with 26W on Oct 22!



- Stable operation.
- No SQZ, no fine tuning of things (yet).
- But you can already see an improvement between 50 and 80 Hz!

Schedule

- Relocking, retuning, characterization in the last week of this month.
 - No known delay (yet).
- Nov 01 1500 UTC: Nominal start of O2b. Back to regular observation schedule.
- LHO wind fence installation continues in Nov, but they're mostly quiet background work (e.g. waiting for the concrete to cure). Projected impact on the observation is less than 8 hours.
 - Will be functional in mid-Nov, observe w/o wind fence until then.
- No planned break during holidays.
- End of the run is shifted by a month due to this. Committed to one year of observation.
- Eagerly waiting to see the benefits of the commissioning break as well as welcoming KAGRA later this year for O3b!