



SESSION: y-004
SESSION: y-012

- ⑤ SCRIBE, ENGRAVE (A VIBRATORY TOOL MAY BE USED), LASER MARK OR MECHANICALLY STAMP (NO INKS OR DYES) DRAWING PART NUMBER, REVISION (AND VARIANT OR TYPE) (APPLICABLE) ON NOTED SURFACE OF PART FOLLOWED ON THE NEXT LINE WITH A THREE DIGIT SERIAL NUMBER. SERIAL NUMBERS START AT 001 FOR THE FIRST ARTICLE AND PROCEED CONSECUTIVELY. USE MINIMUM 0.12" HIGH CHARACTERS, UNLESS THE SIZE OF THE TOOL DICTATES SMALLER CHARACTERS. EXAMPLE: DXXXXXX-VY, TYPE-XX, S/N XXX
6. APPROXIMATE WEIGHT: SEE FOD.
7. MACHINE ALL SURFACES TO REMOVE OXIDES AND MILL FINISH, USE OF ABRASIVE REMOVAL TECHNIQUES IS NOT ALLOWED. — REF. TO LIGO SPECIFICATION E0900364.
8. ALL PARTS SHALL BE MANUFACTURED IN ACCORDANCE WITH LIGO SPECIFICATION E0900364.
9. ALL HELL-COIL HOLES TO BE PREPARED ACCORDING TO EMHART HELL-COIL PRODUCT CATALOG, HC2000, REV. 4.
10. ALL HELL-COIL INSERTS TO BE INSTALLED BY LIGO PERSONNEL — AFTER DELIVERY OF FINISHED PARTS, USE ITRONIC 60 THREADED INSERTS.
11. ALL MATERIAL IS TO BE VIRGIN MATERIAL (I.E. NO WELD REPAIRS, PLUGS OR RECYCLED MATERIAL), NO REPAIRS SHALL BE MADE UNLESS APPROVED IN ADVANCE, AND IN WRITING, BY LIGO LABORATORY, REF. TO LIGO SPECIFICATION E0900364.
12. SURFACE FINISH TO BE AS-PROCESSED FROM MILL/SUPPLIER, FREE FROM SCRATCHES OR GOUGES.
13. REFER TO LIGO E0900408 & E0900404 FOR WELDING AND HELIUM LEAK TESTING SPECIFICATIONS.
14. FLANGES MUST BE PACKAGED, HANDLED AND SHIPPED IN SUCH A MANNER AS TO MAINTAIN SPECIFIED SURFACE FINISHES AND FLATNESS TOLERANCES.



D2600277, WELDMENT, SPOOL, $\varnothing$ 1.22M, MID

APPROX WEIGHT: XXXkg, (XXXlbs)

SCALE 2 : 25

PRELIMINARY

REV.	DATE	DCN #	DRAWING TREE #
v1	08/13/2026	E2600250-x0	

10	3	DN160CF	FLANGE,UHV,SS,BORED,FXD,8"OD, 6"C-BORE, SS	KJ LESKER	STAINLESS STL
9	5	DN63CF	FLANGE,UHV,SS,BORED,FXD,4.50" OD, 2.75" C-BORE, SS	KJ LESKER	STAINLESS STL
8	1	D2600277-08	EXPLOSION WELD, 6"OD X 10"LG CS TO HSLA (EXW)	TBD	CS / HSLA
7	2	D2600277-07	EXPLOSION WELD, 6"OD X 7"LG CS TO HSLA (EXW)	TBD	CS / HSLA
6	5	D2600277-06	EXPLOSION WELD, 2.75"OD X 7"LG CS TO HSLA (EXW)	TBD	CS / HSLA
5	5	D2600277-05	COLLAR, 3.01"ID X 4.5"OD X .25"THK, CS	TBD	CARBON STL
4	1	D2600227-04	COLLAR, 6.01ID X 8.00"OD X .25"THK, CS, MID SPOOL, LOWER	TBD	CARBON STL
3	2	D2600277-03	COLLAR, 6.01ID X 8.00"OD X .25"THK, CS	TBD	CARBON STL
2	4	D2600277-02	HEAT TUBE, 25.4MM ID X 3MM THK WALL X 762 LG	TBD	SCHED 40??
1	2	D2600277-01	SPOOL 1.22M, 1MLG, 5MM WALL, MID	TBD	CARBON STL
ITEM NO.	QTY.	PART NUMBER	DESCRIPTION	MFR	MATERIAL
D2600277 WELDMENT					

		NOTES AND TOLERANCES: (UNLESS OTHERWISE SPECIFIED)		<div> CALIFORNIA INSTITUTE OF TECHNOLOGY MASSACHUSETTS INSTITUTE OF TECHNOLOGY</div>		PART NAME									
DIMENSIONS ARE IN MILLIMETERS		1. INTERPRET DRAWING PER ASME Y14.5-1994. 2. REMOVE ALL SHARP EDGES, .005-.015. FOR MACHINED PARTS. ROUND ALL EDGES APPROXIMATELY R.02 FOR SHEET METAL PARTS. 3. DO NOT SCALE FROM DRAWING. 4. ALL MACHINING FLUIDS MUST BE FULLY SYNTHETIC, FULLY WATER SOLUBLE AND FREE OF SULFUR, SILICONE, AND CHLORINE.		SYSTEM		SUB-SYSTEM		DESIGNER			SIZE	DWG. NO.		REV.	
TOLERANCES: .XX ± .10 .XXX ± .05				CEBEX				DRAFTER		S. SHANKLE	13 AUG 2026	D		D2600277	
								CHECKER		S. SHANKLE	13 AUG 2026			v1	
ANGULAR ± 1.0°		MATERIAL SEE WELDMENT CUT LIST		FINISH μinch		NEXT ASSY D2600237		APPROVAL				SCALE: 1:10	PROJECTION:		SHEET 1 OF 2

